

APPENDIX M: WATER USAGE STUDY

This page intentionally left blank.

ELM Project

Table 5 - Total Water Demand for Project Duration

Disturbance Source	Duration (days)	Demand From Table 2 (gallons/acre/day)	Total Area (acres)	Active Areas (acres)	Daily Water Demand (gallons/day)	Evapotranspiration Table 3 (additional gallons/day)	Daily Task Demand (gallons/day)	Applications (times/day)	Duration Task Demand (Gallons)	Duration Task Demand (acre-feet)
Mid-Line Series Cap	390	1,815	8.4	1.7	3,049	661	3,711	3	1,447,122.55	4.44
OPGW Construction	234	1,815	18.4	3.7	6,679	1,449	8,128	3	1,901,932.50	5.84
Transmission	156	1,815	126.1	12.6	22,880	4,963	27,842	3	4,343,405.24	13.33
Telecommunications	286	1,815	32.1	3.2	5,826	1,264	7,090	3	2,027,694.34	6.22
Distribution	130	1,815	25.7	2.6	4,665	1,012	5,676	3	737,917.65	2.265
Substations	260	1,210	49.5	5.0	5,990	1,949	7,938	3	2,063,927.16	6.33
Staging Areas	30	1,210	182.7	18.3	22,107	7,192	29,299	3	878,973.18	2.70
Access Roads and/or Spur Roads	390	1,815	104.9	10.5	19,046	4,131	23,178	3	9,039,279.65	27.74
Hydroseeding									1,214,150.00	3.73
Fill Compaction									1,414,440.65	4.34
Total (Overall)			Total Disturbed Area: 547.8	acres					25,068,842.9	76.9

Total Demand: 77 Acre-Feet for project duration
(25 Million Gallons for project duration)

Total Demand with 10% Contingency: 85 Acre-Feet for project duration
(28 Million Gallons for project duration)

- All areas and durations based on the construction schedule as of April 2018 (Eldorado-Lugo-Mohave Capacitor Series Project).
- Total Project duration (15 months) based on current licensing and construction schedule as of April 2018 (Eldorado-Lugo-Mohave Project)
- Assume 10% of general construction/grading considered active at any given time throughout the project except within the Mid-Line Series Cap.
- Assume that the access roads may utilize soil binders and the number of water applications for dust suppression per day may be reduced.
- Assumes that the staging yards will be constructed and stabilized within 30 days.
- Assume that the project will work a 6 day work week.
- Assume 26 working days per month, on average.
- Assume that concrete for this project will be premixed offsite by the concrete provider.

0

Fill Soil Max Dry Density	126 pcf
Fill Soil Optimum Moisture Content	14%
Fill Soil Relative Compaction	95%
Imported / Excavated Moisture Content	4%
Total Water Demand for Compaction	1.44 gal/cf
Total Water Demand for Compaction	38.75 gal/cy

ELM Project					
Fill Compaction Water Needs Primary Option					
Site Soil	Volume (cuyd)	Total Duration (months)	Water Demand (gallons)	Total Daily Water Demand (gallons)	Total Water Demand (gallons)
Soil Volume					
Fill Compaction Areas (Primary - Site 2)	18,000	2.5	697,532.37	10,731.27	697,532
Fill Compaction Areas (Primary - Site 4)	18,500	2.5	716,908.27	11,029.36	716,908
		TOTAL:			1,414,441 (gallons)
Notes:				4.34 acre-feet	
-Soil dry density assumes the material is compacted to the specified relative compaction. -Assume water applied to reach OMC will be the difference between OMC and the antecedent soil moisture content.					

Water Spec. Weight:
8.3436 lbs/US gallon

Notes

Made assumptions on geotechnical fill soil max dry density, optimum moisture content, soil relative compaction percentage.