

**TABLE 3
FAIRFIELD ILA
CONSTRUCTION AND OPERATION EMISSIONS SUMMARY**

Construction Engine Emissions

SOURCE	SIZE / GROSS HP	DAILY AMOUNT (1) (hrs or trips)	NUMBER OF DAYS	NUMBER OF UNITS	ONE-WAY DISTANCE (miles)	NO _x			POC			PM ₁₀			SO _x			CO			NOTES
						EF (2)	Daily (lbs/day)	Total (tons)	EF (2)	Daily (lbs/day)	Total (tons)	EF (2)	Daily (lbs/day)	Total (tons)	EF (2)	Daily (lbs/day)	Total (tons)	EF (2)	Daily (lbs/day)	Total (tons)	
Site Grading (11 cy)																					
Backhoe Loader	200	1	1	1	-	2370	5.2	0.0026	180	0.4	0.0002	15	0.03	0.00002	135	0.3	0.0001	205	0.5	0.0002	6
Vac Truck	153	2	1	1	-	1660	7.3	0.0037	110	0.5	0.0002	15	0.07	0.00003	105	0.5	0.0002	110	0.5	0.0002	6
Surveying Lt-Heavy Duty Truck	117	3	1	1	-	780	5.2	0.0026	72	0.5	0.0002	44	0.3	0.00015	85	0.6	0.0003	105	0.7	0.0003	6
Lt-Heavy Duty Truck	10 cu yd	1	1	1	30	11.3	1.5	0.0007	2.2	0.29	0.00015	0.59	0.08	0.00004	0.31	0.04	0.0000	14.0	1.9	0.0009	7
Worker Light Truck	175	1	1	1	30	18.4	2.4	0.00122	4.4	0.58	0.00029	0.84	0.111	0.000056	0.31	0.041	0.0000	35	4.6	0.0023	6
Equipment Delivery Truck	Low boy	3	1	-	30	11.3	4.5	0.0022	2.2	0.9	0.0004	0.59	0.23	0.00012	0.31	0.12	0.0001	14.0	5.6	0.0028	7
Worker Light Truck	Light	2	1	-	30	1.0	0.26	0.00013	0.35	0.09	0.00005	0	0	0	0.06	0.02	0.0000	7.22	1.9	0.0010	7
Maxima and Subtotals (Site Grading)							16.0	0.013		2.3	0.0016		0.7	0.0004		0.8	0.0008		14.6	0.008	
Gutting of Building Interior (265 cu.yds.)																					
Semi-end Dump Trucks	20 ton	4	3	-	100	11.3	20	0.030	2.2	3.9	0.0058	0.59	1.0	0.0016	0.31	0.5	0.0008	14.0	24.8	0.037	7
Worker Light Truck	Light	12	3	-	30	1.00	1.6	0.0024	0.35	0.6	0.0008	0	0	0	0.06	0.1	0.0001	7.22	11.5	0.0172	7
Maxima and Subtotals (Demolition)							21	0.03		4.4	0.0067		1.0	0.0016		0.6	0.0010		36.2	0.05	
Pad Construction (11cy)																					
Cement Truck	10 yd3	1	1	-	30	11.3	1.5	0.0007	2.2	0.3	0.00015	0.59	0.08	0.00004	0.31	0.0	0.0000	14.0	1.9	0.0009	7
Gravel Truck	10 yd3	1	1	-	30	11.3	1.5	0.0007	2.2	0.3	0.00015	0.59	0.08	0.00004	0.31	0.0	0.0000	14.0	1.9	0.0009	7
Worker Light Truck	Light	2	1	-	30	1.00	0.3	0.0001	0.35	0.1	0.00005	0	0	0	0.06	0.0	0.0000	7.22	1.9	0.0010	7
Maxima and Subtotals (Pad Construction)							3.2	0.00		0.7	0.0003		0.16	0.00008		0.1	0.0000		5.6	0.00	
Trenching & Utility Installation (350cy)																					
Excavator	84	8	12	1	-	774	14	0.082	64	1.1	0.0068	13	0.2	0.0014	58	1.0	0.0061	79	1.4	0.008	6
Equipment Delivery Truck	Low boy	1	2	-	30	11.3	1.5	0.001	2.2	0.3	0.0003	0.59	0.08	0.0001	0.31	0.0	0.0000	14.0	1.9	0.002	7
Worker Light Truck	Light	2	12	-	30	1.00	0.3	0.002	0.35	0.1	0.0006	0	0	0	0.06	0.0	0.0001	7.2	1.9	0.011	7
Maxima and Subtotals (Trenching and Utility Installation)							15	0.08		1.5	0.0076		0.31	0.0015		1.1	0.0062		5.2	0.02	
Shelter Placement																					
Crane	150 ton	2	1	1	-	576	2.5	0.001	82	0.4	0.0002	64	0.3	0.000	41	0.2	0.000	1624	7.2	0.004	8
Equipment Delivery Truck	Low boy	1	1	-	150	11.3	7.4	0.004	2.2	1.5	0.0007	0.59	0.4	0.000	0.31	0.2	0.000	14.0	9.3	0.005	7
Worker Light Truck	Light	2	1	-	30	1.00	0.3	0.0001	0.35	0.1	0.00005	0	0	0	0.06	0.0	0.000	7.2	1.9	0.001	7
Maxima and Subtotals (Shelter Placement)							10.2	0.005		1.9	0.0010		0.67	0.000		0.4	0.00		18.4	0.01	
General Construction Activities																					
Compactor	<25 hp	1	1	1	-	8	0.018	0.00001	227	0.5	0.0002	1.4	0.00	0.0000	0	0.0	0.0000	6350	14.0	0.007	8
Equipment Delivery Truck	Low boy	1	1	-	30	11.3	1.5	0.001	2.2	0.3	0.0001	0.59	0.1	0.0000	0.31	0.0	0.0000	14.0	1.9	0.001	7
Construction Generator	<50 hp	8	12	1	-	0.02	0.0003	0.000002	0.002	0.00004	0.0000002	0.001	0.00002	0.0000001	0.00	0.0	0.0000	0.01	0.0002	0.000	8
Water Truck	4500 gal.	1	2	-	30	11.3	1.5	0.001	2.2	0.29	0.0003	0.59	0.08	0.0001	0.31	0.04	0.00004	14.0	1.9	0.002	6
Worker Light Truck	Light	1	17	-	30	1.0	0.13	0.001	0.35	0.0	0.0004	0	0	0	0.06	0.0	0.0001	7.2	1.0	0.008	7
Maxima and Subtotals (General Construction)							1.6	0.003		0.8	0.0011		0.1	0.0001		0.0	0.0001		16.8	0.02	
Maxima and Subtotals, Construction Engine Emissions ⁽³⁾								0.14			0.018			0.0040			0.0084			0.114	
Total Construction Emissions (Fugitive plus exhaust)								0.14			0.018			0.11			0.0084			0.114	
Construction Thresholds								--		-- (Precursor, POC)			Fugitive PM10 Control Measures					--			--
Insignificant Impact ⁽⁹⁾								Yes		Yes			Yes		Yes		Yes			Yes	

Construction Fugitive Dust Emissions

SOURCE	DAILY AMOUNT (hours)	DAYS OF ACTIVITY	AREA OF GRADING / TRENCHING	PM ₁₀ EMISSIONS		NOTES
				(daily lbs)	(total tons)	
Gutting of Building Interior	8	3	0.007 acres	39.4 lb/acre-day	0.3	0.0004
Access Road Use	8	17	0.23 acres	39.4 lb/acre-day	9.1	0.077
Trenching - Cable Installation	8	12	-	0.51 lb/hr	4.1	0.024
Wind Erosion	24	12	0.03 acres	6.6 lb/acre-day	0.2	0.0012
Subtotal, Construction Fugitive Emissions ⁽³⁾					9.2	0.10
Total PM10 Construction Emissions (Engine Exhaust and Fugitive) ⁽³⁾						0.11

(Continued)

Operation Emissions ⁽⁴⁾

SOURCE	SIZE / GROSS HP	DAILY AMOUNT (hours)	DAYS OF ACTIVITY	NUMBER OF UNITS	ONE-WAY DISTANCE (miles)	NO _x			POC			PM ₁₀			SO _x			CO			NOTES
						EF (g/hr) ⁽²⁾	Daily (lbs/day)	Annual (tons/year)	EF (g/hr) ⁽²⁾	Daily (lbs/day)	Annual (tons/year)	EF (g/hr) ⁽²⁾	Daily (lbs/day)	Annual (tons/year)	EF (g/hr) ⁽²⁾	Daily (lbs/day)	Annual (tons/year)	EF (g/hr) ⁽²⁾	Daily (lbs/day)	Annual (tons/year)	
Emergency Generator	337 (300 KW)	0.5	60	1		2,325	2.6	0.08	337	0.37	0.011	135	0.15	0.004	313	0.35	0.010	2,865	3.2	0.09	6,14
Worker Light Truck	Light	-	60	1	30	1.0	0.13	0.004	0.35	0.05	0.001	0	0	0	0.06	0.01	0.0002	7.2	0.96	0.03	7
Total Operation Emissions ⁽⁵⁾							2.70	0.08		0.42	0.013		0.15	0.004		0.35	0.011		4.1	0.12	
Operation Thresholds						Exempt			--			--			--			Exempt			
Insignificant Impact ⁽¹⁰⁾						Yes			Yes			Yes			Yes			Yes			

¹ - Not applicable

Unit abbreviations: g/hr = grams per hour, lb/day = pounds per day, tpy = tons per year, tpq = tons per quarter

(1) Daily amount is measured in hours for off-road construction equipment (e.g., grader), and in number of trips for on-road vehicles (e.g., worker light-truck).

(2) Emission factors are in grams per hour for off-road equipment, and in grams per mile for on-road vehicles.

(3) Construction engine emission subtotals are for the complete project. Major pieces of construction off-road equipment (e.g., grader, dozer) are used consecutively, not concurrently.

(4) Operation and construction will not occur simultaneously, and hence, the emissions are not additive.

(5) Operational emission totals are for the project. Only one generator will be tested on a single day.

(6) Emission factors are from Caterpillar Corp.

(7) EMFAC7G Emission Factors (1998, 15mph, 75°F)

(8) SCAQMD CEQA Handbook, Table A9-8-B

(9) Construction emissions have insignificant impact when no emission of a major piece of off-road equipment exceeds threshold (i.e., major pieces are used consequently, not concurrently).

(10) Operation emissions have an insignificant impact if emergency generators are exempt from regulatory limits or if no regulations apply.

(11) Number of days subject to wind erosion equal to days for trenching.

(12) Area to be graded is sum of 115-foot by 66-foot fenced compound and 10-foot wide perimeter band.

(13) Access road assumed to be 1000 ft long and 10 ft wide.

(14) The 25-minute test cycle will be conducted mostly at 50 percent load. To be conservative, the horsepower is stated and emissions are calculated at 75 percent load.

(15) Daily construction fugitive emissions includes the specific activity plus wind erosion.