

APPENDIX H
SCE PROPOSED MEASURES

SCE Proposed Measures

Environmental Resource Category	Specific measures	Measures and/or Measures Location
Air Quality	General Air Quality	Proposed Project construction activities would include implementation of emission control measures as listed in Table 4.3-3, SJVAPCD Control Measures for Construction Emissions of PM ₁₀ , in order to minimize construction impacts from PM ₁₀ and fugitive dust emissions. See Section 4.3.4
Biological Resources	San Joaquin kit foxes	If evidence of the San Joaquin kit foxes are found, SCE Proposed Measures would be implemented as outlined in Section 4.4.4.
	Migratory Birds	Tree removal for substation construction activities would not take place during nesting season (March – May) unless pre-construction surveys are conducted, and a qualified biologist verifies that no nests are present.
	General Biological Resources	Minimization of Ground Disturbance
		Spill Containment/Management
Trash Removal		
Cultural Resources	General Cultural Resources	If previously unidentified archaeological resources are unearthed during construction activities, construction would be halted in that area and directed away from the discovery until a qualified archaeologist assesses the significance of the resource. The archaeologist would recommend appropriate measures to record, preserve or recover the resources.
		If human remains are encountered during construction or any other phase of development, work in the area of the discovery must be halted in that area and directed away from the discovery. No further disturbance would occur until the county coroner makes the necessary findings as to origin pursuant to Public Resources Code 5097.98-99, Health and Safety Code 7050.5. If the remains are determined to be Native American, then the Native American Heritage Commission (NAHC) would be notified within 24 hours as required by Public Resources Code 5097. The NAHC would notify the designated Most Likely Descendants who would provide recommendations for the treatment of the remains within 24 hours. The NAHC mediates any disputes regarding treatment of remains.
Traffic and Transportation	General Traffic and Transportation	To the extent feasible, truck traffic would be scheduled for off-peak hours to reduce impacts during periods of peak traffic.
		To the extent feasible, truck traffic would be staggered throughout the 4-week grading and site preparation construction phase.
		Truck traffic would use designated truck routes to access the substation site, the majority of which are currently designated Level of Service B.
		If lane closures are required, SCE would comply with best management practices established by the Work Area Protection and Traffic Control Manual (California Joint Utility Traffic Control Committee 1996).