

AIR QUALITY CALCULATIONS

THIS PAGE IS INTENTIONALLY BLANK

Table F-1. Local Significance Threshold Impacts Summary

Local Significance Threshold (lbs/day)

| Distance to Receptor (m) | CO (lb/day) | NOx (lb/day) | PM10 (lb/day) | PM2.5 (lb/day) |
|--------------------------|-------------|--------------|---------------|----------------|
| 25 | 845 | 220 | 4 | 3 |
| 50 | 1328 | 277 | 13 | 5 |
| 100 | 2422 | 396 | 35 | 10 |
| 200 | 5,687 | 627 | 80 | 24 |
| 500 | 23,061 | 1,221 | 214 | 105 |

Note: Used SRA #30, 1 acre site.

Construction Emissions (lbs/day) ¹

| Construction Phase | Distance to Receptor (m) | CO (lb/day) | NOx (lb/day) | PM10 (lb/day) | PM2.5 (lb/day) |
|--------------------------------------|--------------------------|-------------|--------------|---------------|----------------|
| Transmission Line ^{2,3} | 25 | 2.00 | 3.81 | 3.35 | 0.67 |
| Subtransmission Line ^{2,3} | 25 | 2.74 | 6.19 | 4.58 | 1.14 |
| Devers Substation Construction | 55 | 24.64 | 45.10 | 14.13 | 2.99 |
| Mirage Substation Construction | 30 | 64.10 | 120.84 | 37.91 | 7.92 |
| Concho Substation Construction | 20 | 3.19 | 4.21 | 0.19 | 0.04 |
| Indian Wells Substation Construction | 35 | 3.19 | 4.21 | 0.19 | 0.04 |
| Santa Rosa Substation Construction | 40 | 3.19 | 4.21 | 0.19 | 0.04 |
| Eisenhower Substation Construction | 50 | 26.82 | 51.63 | 14.60 | 3.09 |
| Farrell Substation Construction | 24 | 26.82 | 51.63 | 15.45 | 3.27 |
| Garnet Substation Construction | 39 | 3.19 | 4.21 | 3.90 | 0.83 |
| Thornhill Substation Construction | 10 | 3.19 | 4.21 | 3.90 | 0.83 |
| Tamarisk Substation Construction | 41 | 19.99 | 34.32 | 1.93 | 0.41 |
| Telecommunication | 25 | 0.60 | 1.66 | 1.27 | 0.27 |

Notes:

1. Values above the LST are shown in **BOLD**.

2. There was more than one receptor within 25 meters of the construction activities. For receptor distances equal to or less than 25 m the most stringent LST values are applicable.

3. Assume 500 meters (0.31 mile) of activity (11.7 miles total) would impact one receptor.

THIS PAGE IS INTENTIONALLY BLANK

Table F-2. Maximum Daily Combined Emission Summary

| Quarter | Construction Phases Occurring Simultaneously | Combined Maximum Emissions (lb/day) | | | | | |
|-------------------|---|-------------------------------------|-------|------|-----|-------|-------|
| | | CO | NOx | ROG | SOx | PM10 | PM2.5 |
| 2nd Quarter, 2009 | <i>Subtransmission Line (Mirage-Santa Rosa)</i> | 103.3 | 233.5 | 22.6 | 0.3 | 202.6 | 43.0 |
| 3rd Quarter, 2009 | <i>Mirage Substation Construction, Devers Substation Construction, Eisenhower Substation Construction</i> | 115.6 | 217.6 | 26.6 | 0.2 | 66.6 | 14.0 |
| 3rd Quarter, 2009 | <i>Mirage Substation Construction, Devers Substation Construction, Eisenhower Substation Construction, Subtransmission Line (Mirage-Santa Rosa-Tamarisk)</i> | 218.9 | 451.1 | 49.2 | 0.5 | 269.2 | 57.0 |
| 3rd Quarter, 2009 | <i>Mirage Substation Construction, Concho Substation Construction, Eisenhower Substation Construction, Subtransmission Line (Mirage-Santa Rosa-Tamarisk)</i> | 197.4 | 410.2 | 44.1 | 0.5 | 255.3 | 54.1 |
| 4th Quarter, 2009 | <i>Mirage Substation Construction, Concho Substation Construction, Farrell Substation Construction, Subtransmission Line (Mirage-Santa Rosa-Tamarisk)</i> | 197.4 | 410.2 | 44.1 | 0.5 | 256.1 | 54.2 |
| 1st Quarter, 2010 | <i>Mirage Substation Construction, Indian Wells Substation Construction, Farrell Substation Construction, Subtransmission Line (Mirage-Devers-Capwind-Tamarisk)</i> | 197.4 | 410.2 | 44.1 | 0.5 | 256.1 | 54.2 |
| 1st Quarter, 2010 | <i>Mirage Substation Construction, Indian Wells Substation Construction, Thornhill Substation Construction, Subtransmission Line (Mirage-Devers-Capwind-Tamarisk)</i> | 134.8 | 358.7 | 34.3 | 0.4 | 16.3 | 3.4 |
| 1st Quarter, 2010 | <i>Mirage Substation Construction, Indian Wells Substation Construction, Thornhill Substation Construction, Subtransmission Line (Mirage-Concho)</i> | 173.8 | 362.8 | 38.3 | 0.4 | 244.6 | 51.8 |

Table F-2. Maximum Daily Combined Emission Summary

| Quarter | Construction Phases Occurring Simultaneously | Combined Maximum Emissions (lb/day) | | | | | |
|-----------------------------------|---|-------------------------------------|--------------|-------------|------------|--------------|-------------|
| | | CO | NOx | ROG | SOx | PM10 | PM2.5 |
| 1st Quarter, 2010 | <i>Mirage Substation Construction, Santa Rosa Substation Construction, Thornhill Substation Construction, Subtransmission Line (Mirage-Devers-Capwind-Tamarisk)</i> | 173.8 | 362.8 | 38.3 | 0.4 | 244.6 | 51.8 |
| 1st Quarter, 2010 | <i>Mirage Substation Construction, Santa Rosa Substation Construction, Thornhill Substation Construction, Subtransmission Line (Mirage-Concho)</i> | 173.8 | 362.8 | 38.3 | 0.4 | 244.6 | 51.8 |
| 2nd Quarter, 2010 | <i>Mirage Substation Construction, Santa Rosa Substation Construction, Tamarisk Substation Construction, Subtransmission Line (Mirage-Concho)</i> | 190.6 | 392.9 | 42.2 | 0.4 | 242.6 | 51.4 |
| 2nd Quarter, 2010 | <i>Mirage Substation Construction, Garnet Substation Construction, Tamarisk Substation Construction, Subtransmission Line (Mirage-Concho)</i> | 190.6 | 392.9 | 42.2 | 0.4 | 246.3 | 52.2 |
| 2nd Quarter, 2010 | <i>Mirage Substation Construction, Garnet Substation Construction, Tamarisk Substation Construction, Transmission Line (Devers-Mirage #2)</i> | 160.6 | 299.3 | 33.3 | 1.7 | 166.2 | 33.6 |
| 2nd Quarter, 2010 | <i>Transmission Line (Devers-Mirage #2, Coachella Valley-Mirage)</i> | 75.5 | 144.0 | 14.0 | 1.5 | 126.4 | 25.3 |
| MAXIMUM COMBINED EMISSIONS | | 218.9 | 451.1 | 49.2 | 1.7 | 269.2 | 57.0 |

Notes

1. Based on schedule provided by the SCE.

Table F-3. Maximum Daily Emission Per Construction Phase Summary

| Construction Phase | Maximum Emissions (lb/day) | | | | | |
|---|----------------------------|--------|-------|------|--------|-------|
| | CO | NOx | ROG | SOx | PM10 | PM2.5 |
| <i>Transmission Line Loop-In ¹</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 119.29 | 23.81 |
| On-Site Vehicle Exhaust | 69.14 | 143.32 | 13.40 | 1.54 | 7.04 | 1.46 |
| Employee Vehicles | 6.33 | 0.66 | 0.65 | 0.01 | 0.05 | 0.03 |
| Total | 75.47 | 143.99 | 14.04 | 1.55 | 126.37 | 25.30 |
| <i>Subtransmission Line ²</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 192.56 | 40.82 |
| On-Site Vehicle Exhaust | 78.53 | 230.94 | 20.06 | 0.24 | 9.84 | 2.05 |
| Employee Vehicles | 24.79 | 2.59 | 2.54 | 0.03 | 0.20 | 0.12 |
| Total | 103.32 | 233.53 | 22.59 | 0.27 | 202.60 | 42.99 |
| <i>Devers Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 11.85 | 2.51 |
| On-Site Vehicle Exhaust | 21.48 | 44.77 | 5.21 | 0.05 | 2.26 | 0.47 |
| Employee Vehicles | 3.16 | 0.33 | 0.32 | 0.00 | 0.03 | 0.02 |
| Total | 24.64 | 45.10 | 5.54 | 0.05 | 14.13 | 2.99 |
| <i>Mirage Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 31.75 | 6.60 |
| On-Site Vehicle Exhaust | 51.96 | 119.57 | 13.43 | 0.12 | 6.05 | 1.26 |
| Employee Vehicles | 12.13 | 1.27 | 1.24 | 0.01 | 0.10 | 0.06 |
| Total | 64.10 | 120.84 | 14.67 | 0.13 | 37.91 | 7.92 |
| <i>Concho Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| On-Site Vehicle Exhaust | 2.13 | 4.10 | 0.39 | 0.00 | 0.18 | 0.04 |
| Employee Vehicles | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Total | 3.19 | 4.21 | 0.50 | 0.01 | 0.19 | 0.04 |
| <i>Indian Wells Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| On-Site Vehicle Exhaust | 2.13 | 4.10 | 0.39 | 0.00 | 0.18 | 0.04 |
| Employee Vehicles | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Total | 3.19 | 4.21 | 0.50 | 0.01 | 0.19 | 0.04 |
| <i>Santa Rosa Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| On-Site Vehicle Exhaust | 2.13 | 4.10 | 0.39 | 0.00 | 0.18 | 0.04 |
| Employee Vehicles | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Total | 3.19 | 4.21 | 0.50 | 0.01 | 0.19 | 0.04 |

Table F-3. Maximum Daily Emission Per Construction Phase Summary

| Construction Phase | Maximum Emissions (lb/day) | | | | | |
|---|----------------------------|-------|------|------|-------|-------|
| | CO | NOx | ROG | SOx | PM10 | PM2.5 |
| <i>Eisenhower Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 11.94 | 2.53 |
| On-Site Vehicle Exhaust | 23.66 | 51.30 | 6.05 | 0.05 | 2.64 | 0.55 |
| Employee Vehicles | 3.16 | 0.33 | 0.32 | 0.00 | 0.03 | 0.02 |
| Total | 26.82 | 51.63 | 6.38 | 0.06 | 14.60 | 3.09 |
| <i>Farrell Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 12.78 | 2.70 |
| On-Site Vehicle Exhaust | 23.66 | 51.30 | 6.05 | 0.05 | 2.64 | 0.55 |
| Employee Vehicles | 3.16 | 0.33 | 0.32 | 0.00 | 0.03 | 0.02 |
| Total | 26.82 | 51.63 | 6.38 | 0.06 | 15.45 | 3.27 |
| <i>Garnet Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 3.71 | 0.79 |
| On-Site Vehicle Exhaust | 2.13 | 4.10 | 0.39 | 0.00 | 0.18 | 0.04 |
| Employee Vehicles | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Total | 3.19 | 4.21 | 0.50 | 0.01 | 3.90 | 0.83 |
| <i>Thornhill Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 3.71 | 0.79 |
| On-Site Vehicle Exhaust | 2.13 | 4.10 | 0.39 | 0.00 | 0.18 | 0.04 |
| Employee Vehicles | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Total | 3.19 | 4.21 | 0.50 | 0.01 | 3.90 | 0.83 |
| <i>Tamarisk Substation Construction</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 0.13 | 0.03 |
| On-Site Vehicle Exhaust | 17.88 | 34.10 | 4.24 | 0.04 | 1.79 | 0.37 |
| Employee Vehicles | 2.11 | 0.22 | 0.22 | 0.00 | 0.02 | 0.01 |
| Total | 19.99 | 34.32 | 4.46 | 0.04 | 1.93 | 0.41 |
| <i>Telecommunications Line</i> | | | | | | |
| Fugitive Dust | 0.00 | 0.00 | 0.00 | 0.00 | 44.93 | 9.46 |
| On-Site Vehicle Exhaust | 20.37 | 62.28 | 5.65 | 0.06 | 2.98 | 0.62 |
| Employee Vehicles | 2.11 | 0.22 | 0.22 | 0.00 | 0.02 | 0.01 |
| Total | 22.48 | 62.50 | 5.86 | 0.06 | 47.92 | 10.09 |

Notes

1. The emission value is the daily maximum that would occur during construction of any of the transmission line sections (Devers Mirage #2 and Coachella Valley Mirage).
2. The emission value is the daily maximum that would occur during construction of any of the subtransmission line sections (Mirage-Santa Rosa, Mirage-Santa Rosa-Tamarisk, Mirage-Capwind-Devers-Tamarisk, and Mirage-Concho).

Table F-4. Roadwork, Transmission Line, Subtransmission Line and Telecommunications Construction - Fugitive Dust Emissions

| Construction Element | Maximum Fugitive Dust Emissions (lb/day) ¹ | |
|---------------------------------------|---|--------------|
| | PM10 | PM2.5 |
| <i>Road Construction</i> | | |
| Grading | 20.23 | 10.46 |
| <i>Transmission Line Loop-In</i> | | |
| Unpaved RoadDust | 106.38 | 22.55 |
| Paved Road Dust | 5.11 | 0.86 |
| Dig Foundation Dust | 7.80 | 0.39 |
| Total | 119.29 | 23.81 |
| <i>Subtransmission Line</i> | | |
| Unpaved RoadDust | 192.56 | 40.82 |
| Paved Road Dust | 5.53 | 0.94 |
| Dig Foundation Dust | 7.80 | 0.39 |
| Total | 205.89 | 42.15 |
| <i>Telecommunications²</i> | | |
| Unpaved RoadDust | 43.32 | 9.18 |
| Paved Road Dust | 1.60 | 0.27 |
| Total | 44.93 | 9.46 |
| Total Fugitive Emissions | 370.10 | 75.41 |

Notes

1. Max assumes all max day activities, except road construction, occur on same day.

Table F-5. Substation Construction - Fugitive Dust Emissions

| | | | |
|--|----------------------|-----|-------------|
| Using Graders | | | |
| Emission Factors from AP42 Section 13.2.3 | | | |
| | E = | 80 | lb/acre-day |
| | Control Efficiency = | 60% | lb/acre-day |

| Substation | Total Acres Disturbed | Maximum Fugitive Dust Emissions (lbs/day) ¹ | |
|--------------|-----------------------|--|-------------------------------|
| | | PM10 (lb/day) ^{1,2} | PM2.5 (lb/day) ^{1,2} |
| Devers | 0.022 | 0.72 | 0.15 |
| Mirage | 0.992 | 31.75 | 6.60 |
| Concho | 0.000 | 0.00 | 0.00 |
| Indian Wells | 0.000 | 0.00 | 0.00 |
| Santa Rosa | 0.000 | 0.00 | 0.00 |
| Eisenhower | 0.025 | 0.81 | 0.17 |
| Farrell | 0.052 | 1.65 | 0.34 |
| Garnet | 0.000 | 0.00 | 0.00 |
| Thornhill | 0.000 | 0.00 | 0.00 |
| Tamarisk | 0.004 | 0.13 | 0.03 |

Notes

1. The maximum fugitive emissions are assumed to occur during site grading activities.
2. Site grading activities for each site were assumed to be completed in one day.

Table F-6. Employee Vehicle - Exhaust Emissions

Employee Vehicle Emissions

Emission Factors
from SCAQMD Highest (Most Conservative) EMFAC 2007 Emission
Factors for On-Road Passenger Vehicles and Delivery Trucks

$$E = F * VMT$$

F = Emission factor per passenger vehicle (lb/VMT)

VMT = Vehicle Miles Traveled

VMT per employee = 50 miles (Assumed)

E = Emissions lb/day

Emission Factors for 2008 (lb/VMT)

CO = 0.01055

NOx = 0.00110

ROG = 0.00108

SOx = 0.00001

PM10 = 0.00009

PM2.5 = 0.00005

Emission Summary

| Construction Phase | Employee s per day* | CO (lbs/day) | NOx (lbs/day) | ROG (lbs/day) | SOx (lbs/day) | PM10 (lbs/day) | PM2.5 (lbs/day) |
|-------------------------------|------------------------|---------------------|----------------------|----------------------|----------------------|-----------------------|--------------------|
| Transmission Line Loop- In | 12 | 6.33 | 0.66 | 0.65 | 0.01 | 0.05 | 0.03 |
| Subtransmission Lines | 47 | 24.79 | 2.59 | 2.54 | 0.03 | 0.20 | 0.12 |
| Devers Substation | 6 | 3.16 | 0.33 | 0.32 | 0.00 | 0.03 | 0.02 |
| Mirage Substation | 23 | 12.13 | 1.27 | 1.24 | 0.01 | 0.10 | 0.06 |
| Concho Substation | 2 | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Indian Wells Substation | 2 | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Santa Rosa Substation | 2 | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Eisenhower Substation | 6 | 3.16 | 0.33 | 0.32 | 0.00 | 0.03 | 0.02 |
| Farrell Substation | 6 | 3.16 | 0.33 | 0.32 | 0.00 | 0.03 | 0.02 |
| Garnet Substation | 2 | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Thornhill Substation | 2 | 1.05 | 0.11 | 0.11 | 0.00 | 0.01 | 0.01 |
| Tamarisk Substation | 4 | 2.11 | 0.22 | 0.22 | 0.00 | 0.02 | 0.01 |
| Telecommunication | 4 | 2.11 | 0.22 | 0.22 | 0.00 | 0.02 | 0.01 |

* This is the maximum number of employees per day expected for this phase of the project

THIS PAGE IS INTENTIONALLY BLANK

Table F-7. Road Grading - Fugitive Dust Emissions

On-site fugitive dust sources during grading of road

| | |
|---|-------------------------|
| Using Graders | |
| Emission Factors from AP42 Table 11.9-1 | |
| E=k*0.051*(S^2) for PM10 | |
| E=k*0.040*(S^2.5) for PM2.5 | |
| k=.6 PM10 | |
| k=.031 PM2.5 | |
| S=mean speed | |
| E=lbs/VMT | |
| E(PM10) | 0.2754 lbs/VMT |
| E(PM2.5) | 0.0193 lbs/VMT |
| Assume | 3 mph grader speed |
| E(PM10) | 0.826 lbs/hr |
| E(PM2.5) | 0.058 lbs/hr |
| Assume | 5 hours per day grading |
| E(PM10) | 4.13 lbs/day/grader |
| E(PM2.5) | 0.29 lbs/day/grader |
| Assume | 1 Grader |
| E(PM10) | 4.1 lbs/day |
| E(PM2.5) | 0.3 lbs/day |
| Assume | 10 days of grading |
| E(PM10) | 41 lbs total activity |
| E(PM2.5) | 3 lbs total activity |

| | |
|---|------------------------|
| Crawler Operation | |
| Used dozer equation in AP 42 Tables 11.9-1 and 11.9-2 | |
| E(PM10)= k*(s^1.5)/(M^1.4) | |
| E(PM2.5)= k*5.7*(^1.2)/(M^1.3) | |
| k= .75 for PM10 | |
| k=0.105 for PM2.5 | |
| s=silt content % | |
| M= moisture content % | |
| Assume | |
| s= | 8.5 % |
| M= | 8 % |
| E(PM10)= | 1.011 lb/hr |
| E(PM2.5)= | 0.523 lb/hr |
| Assume | |
| 10 | hrs/day |
| 2 | dozers |
| E(PM10) | 20.2 lbs/day |
| E(PM2.5) | 10.5 lbs/day |
| Assume | |
| 10 | days compacting |
| E(PM10) | 202 lbs total activity |
| E(PM2.5) | 105 lbs total activity |

Uncontrolled Fugitive Dust Emission Summary

| PM10 (lbs/day) | PM10 Total Activity (lbs) | PM2.5 (lbs/day) | PM2.5 Total Activity (lbs) | Activity |
|----------------|---------------------------|-----------------|----------------------------|--------------------|
| 4 | 41 | 0 | 3 | Using Graders |
| 20 | 202 | 10 | 105 | Using Crawlers |
| 24 | 244 | 11 | 107 | Total Uncontrolled |

Assume 60% control factor for using watering trucks

| PM10 (lbs/day) | PM10 Total Activity (lbs) | PM2.5 (lbs/day) | PM2.5 Total Activity (lbs) | Activity |
|----------------|---------------------------|-----------------|----------------------------|-------------------------|
| 10 | 97 | 4 | 43 | Total Controlled |

THIS PAGE IS INTENTIONALLY BLANK

Table F-8. Dig Foundation - Fugitive Dust Emissions

On-site fugitive dust sources during digging foundations

| | | |
|-------------------------------|------|--------------------------------|
| Digger Truck Operation | | |
| Used AP42 11.9-4 | | |
| E(TSP)= 1.3 lb/hole | | |
| Assume | | |
| | 10 | holes per day |
| | 0.6 | factor for PM10 (like grader) |
| | 0.03 | factor for PM2.5 (like grader) |
| E(PM10) | 7.8 | lbs/day |
| E(PM2.5) | 0.4 | lbs/day |
| Assume | | |
| | 24 | days drilling |
| E(PM10) | 187 | lbs total activity |
| E(PM2.5) | 9 | lbs total activity |

THIS PAGE IS INTENTIONALLY BLANK

Table F-9. Unpaved Road Travel During Construction - Fugitive Dust Emissions

| Unpaved Road Fugitive Dust Emissions | |
|---|---|
| From SCAQMD CEQA AQ Handbook | |
| Table A9-9-D | |
| E=V*F | |
| V= vehicle miles travelled on unpaved roads | |
| $F=2.1*(G/12)*(H/30)*((J/3)^{.7})*((I/4)^{.5})*((365-K)/365)$ | |
| G= surface silt | |
| H= mean vehicle speed | |
| I= number of wheels | |
| J= vehicle weight | |
| K= days of precipitation per year at least 0.01 inch | |
| Note that the vehicles miles traveled assumes the following: | |
| 1. The vehicles are always traveling when they are operational. | |
| 2. Per the project description, the speed of the vehicles traveling on unpaved roads will be reduced to 20 miles per hour | |
| 3. 20 percent of the roads are unpaved. | |
| | 0.212 PM2.5 fraction of PM10 from SCAQMD Table A - Updated CEIDARS Table with PM2.5 Fractions |
| Lightweight Vehicles Factor | |
| G= | 11 assumed |
| H= | 20 assumed |
| I= | 4 wheels |
| J= | 3 tons |
| | precipitation |
| k= | 18 days |
| | 1.2 F PM10 (lbs/VMT) |
| | 0.26 F PM2.5 (lbs/VMT) |
| Heavy Vehicles Factor | |
| G= | 11 assumed |
| H= | 15 assumed |
| I= | 10 wheels |
| J= | 8 tons |
| | precipitation |
| k= | 18 days |
| | 2.9 F PM10 (lbs/VMT) |
| | 0.61 F PM2.5 (lbs/VMT) |

Table F-9. Unpaved Road Travel During Construction - Fugitive Dust Emissions

| Activity | Number | Days | Hours /Day | Max VMT/day ¹ | F PM10 (lbs/VMT) | F PM2.5 (lbs/VMT) | Uncontrolled Emissions | | | | Controlled Emissions (60 percent) | | | |
|--|--------|------|------------|--------------------------|------------------|-------------------|------------------------|--------------|-----------|--------------|-----------------------------------|--------------|-----------|--------------|
| | | | | | | | PM10 | | PM2.5 | | PM10 | | PM2.5 | |
| | | | | | | | (lbs/day) | lbs activity | (lbs/day) | lbs activity | (lbs/day) | lbs activity | (lbs/day) | lbs activity |
| Subtransmission Line | | | | | | | | | | | | | | |
| <i>Survey</i> | | | | | | | | | | | | | | |
| Worker Traffic | 3 | 3 | - | 3.80 | 1.2 | 0.26 | 13.9 | 41.7 | 2.9 | 8.8 | 5.6 | 16.7 | 1.2 | 3.5 |
| ½-Ton Pick-up | 1 | 3 | 10 | 9.54 | 1.2 | 0.26 | 11.6 | 34.9 | 2.5 | 7.4 | 4.7 | 14.0 | 1.0 | 3.0 |
| <i>Roads</i> | | | | | | | | | | | | | | |
| Worker Traffic | 4 | 10 | - | 3.80 | 1.2 | 0.26 | 18.5 | 185.4 | 3.9 | 39.3 | 7.4 | 74.2 | 1.6 | 15.7 |
| 1-Ton Crew Cab 4X4 | 2 | 10 | 2 | 9.54 | 1.2 | 0.26 | 23.3 | 232.8 | 4.9 | 49.4 | 9.3 | 93.1 | 2.0 | 19.7 |
| Road Grader | 1 | 10 | 10 | 9.54 | 2.9 | 0.61 | 27.4 | 274.2 | 5.8 | 58.1 | 11.0 | 109.7 | 2.3 | 23.3 |
| Track-Type Dozer | 2 | 10 | 2.5 | 9.54 | 2.9 | 0.61 | 54.8 | 548.5 | 11.6 | 116.3 | 21.9 | 219.4 | 4.7 | 46.5 |
| Water Truck | 1 | 10 | 10 | 9.54 | 2.9 | 0.61 | 27.4 | 274.2 | 5.8 | 58.1 | 11.0 | 109.7 | 2.3 | 23.3 |
| <i>Pole Framing and Setting</i> | | | | | | | | | | | | | | |
| Worker Traffic | 16 | 147 | - | 3.80 | 1.2 | 0.26 | 74.2 | 10904.3 | 15.7 | 2311.7 | 29.7 | 4361.7 | 6.3 | 924.7 |
| ¾-Ton Suburban | 2 | 147 | 10 | 9.54 | 1.2 | 0.26 | 23.3 | 3421.9 | 4.9 | 725.5 | 9.3 | 1368.8 | 2.0 | 290.2 |
| 5-Ton Framing Truck 4X4 | 2 | 83 | 10 | 9.54 | 2.9 | 0.61 | 54.8 | 4552.4 | 11.6 | 965.1 | 21.9 | 1821.0 | 4.7 | 386.0 |
| 30-Ton Line Truck | 2 | 83 | 10 | 9.54 | 2.9 | 0.61 | 54.8 | 4552.4 | 11.6 | 965.1 | 21.9 | 1821.0 | 4.7 | 386.0 |
| Digger Truck | 1 | 24 | 10 | 9.54 | 2.9 | 0.61 | 27.4 | 658.2 | 5.8 | 139.5 | 11.0 | 263.3 | 2.3 | 55.8 |
| Water Truck | 1 | 83 | 10 | 9.54 | 2.9 | 0.61 | 27.4 | 2276.2 | 5.8 | 482.6 | 11.0 | 910.5 | 2.3 | 193.0 |
| Backhoe | 2 | 147 | 10 | 9.54 | 2.9 | 0.61 | 54.8 | 8062.7 | 11.6 | 1709.3 | 21.9 | 3225.1 | 4.7 | 683.7 |
| Bucket Truck | 2 | 147 | 10 | 9.54 | 2.9 | 0.61 | 54.8 | 8062.7 | 11.6 | 1709.3 | 21.9 | 3225.1 | 4.7 | 683.7 |
| Truck-Mounted Crane | 2 | 147 | 10 | 9.54 | 2.9 | 0.61 | 54.8 | 8062.7 | 11.6 | 1709.3 | 21.9 | 3225.1 | 4.7 | 683.7 |
| 30-Ton Crane | 1 | 14 | 10 | 9.54 | 2.9 | 0.61 | 27.4 | 383.9 | 5.8 | 81.4 | 11.0 | 153.6 | 2.3 | 32.6 |
| Cement Truck | 1 | 3 | 10 | 9.54 | 2.9 | 0.61 | 27.4 | 82.3 | 5.8 | 17.4 | 11.0 | 32.9 | 2.3 | 7.0 |
| <i>Material Delivery</i> | | | | | | | | | | | | | | |
| Worker Traffic | 3 | 5 | - | 3.80 | 1.2 | 0.26 | 13.9 | 69.5 | 2.9 | 14.7 | 5.6 | 27.8 | 1.2 | 5.9 |
| 60-Foot Flat-Bed Pole Truck | 2 | 5 | 8 | 9.54 | 2.9 | 0.61 | 54.8 | 274.2 | 11.6 | 58.1 | 21.9 | 109.7 | 4.7 | 23.3 |
| Forklift | 1 | 5 | 8 | 9.54 | 2.9 | 0.61 | 27.4 | 137.1 | 5.8 | 29.1 | 11.0 | 54.8 | 2.3 | 11.6 |
| <i>Conductor Installation</i> | | | | | | | | | | | | | | |
| Worker Traffic | 16 | 24 | - | 3.80 | 1.2 | 0.26 | 74.2 | 1780.3 | 15.7 | 377.4 | 29.7 | 712.1 | 6.3 | 151.0 |
| Flat-Bed Truck & Trailer (Wire Puller) | 1 | 24 | 6 | 9.54 | 2.9 | 0.61 | 27.4 | 658.2 | 5.8 | 139.5 | 11.0 | 263.3 | 2.3 | 55.8 |
| Flat-Bed Truck & Trailer (Wire Dolly) | 1 | 24 | 6 | 9.54 | 2.9 | 0.61 | 27.4 | 658.2 | 5.8 | 139.5 | 11.0 | 263.3 | 2.3 | 55.8 |
| 30-Ton Line Truck | 2 | 24 | 5 | 9.54 | 2.9 | 0.61 | 54.8 | 1316.4 | 11.6 | 279.1 | 21.9 | 526.5 | 4.7 | 111.6 |
| ¾-Ton Suburban | 2 | 14 | 10 | 9.54 | 1.2 | 0.26 | 23.3 | 325.9 | 4.9 | 69.1 | 9.3 | 130.4 | 2.0 | 27.6 |
| Water Truck | 1 | 24 | 10 | 9.54 | 2.9 | 0.61 | 27.4 | 658.2 | 5.8 | 139.5 | 11.0 | 263.3 | 2.3 | 55.8 |
| Bucket Truck | 2 | 24 | 6 | 9.54 | 2.9 | 0.61 | 54.8 | 1316.4 | 11.6 | 279.1 | 21.9 | 526.5 | 4.7 | 111.6 |
| Truck-Mounted Crane | 2 | 24 | 6 | 9.54 | 2.9 | 0.61 | 54.8 | 1316.4 | 11.6 | 279.1 | 21.9 | 526.5 | 4.7 | 111.6 |
| <i>Restoration</i> | | | | | | | | | | | | | | |
| Worker Traffic | 8 | 40 | - | 3.80 | 1.2 | 0.26 | 37.1 | 1483.6 | 7.9 | 314.5 | 14.8 | 593.4 | 3.1 | 125.8 |
| 1-Ton Crew Cab 4X4 | 2 | 40 | 8 | 9.54 | 1.2 | 0.26 | 23.3 | 931.1 | 4.9 | 197.4 | 9.3 | 372.5 | 2.0 | 79.0 |
| Water Truck | 1 | 40 | 8 | 9.54 | 2.9 | 0.61 | 27.4 | 1097.0 | 5.8 | 232.6 | 11.0 | 438.8 | 2.3 | 93.0 |

Table F-9. Unpaved Road Travel During Construction - Fugitive Dust Emissions

| Activity | Number | Days | Hours /Day | Max VMT/day ¹ | F PM10 (lbs/VMT) | F PM2.5 (lbs/VMT) | Uncontrolled Emissions | | | | Controlled Emissions (60 percent) | | | |
|--------------------------------------|--------|------|------------|--------------------------|------------------|-------------------|------------------------|--------------|-----------|--------------|-----------------------------------|--------------|-----------|--------------|
| | | | | | | | PM10 | | PM2.5 | | PM10 | | PM2.5 | |
| | | | | | | | (lbs/day) | lbs activity | (lbs/day) | lbs activity | (lbs/day) | lbs activity | (lbs/day) | lbs activity |
| <i>Max Subtransmission Line</i> | | | | | | | | | | | 192.6 | 20407.9 | 40.8 | 4326.5 |
| Telecommunications | | | | | | | | | | | | | | |
| Worker Traffic | 4 | 112 | - | 3.80 | 1.2 | 0.26 | 18.5 | 2077.0 | 3.9 | 440.3 | 7.4 | 830.8 | 1.6 | 176.1 |
| Crew Truck (gasoline) | 2 | 114 | 8 | 9.54 | 1.2 | 0.26 | 23.3 | 2653.7 | 4.9 | 562.6 | 9.3 | 1061.5 | 2.0 | 225.0 |
| Crew Truck (gasoline) | 1 | 85 | 8 | 9.54 | 1.2 | 0.26 | 11.6 | 989.3 | 2.5 | 209.7 | 4.7 | 395.7 | 1.0 | 83.9 |
| Bucket Truck | 2 | 25 | 8 | 9.54 | 2.9 | 0.61 | 54.8 | 1371.2 | 11.6 | 290.7 | 21.9 | 548.5 | 4.7 | 116.3 |
| | | | | | | | | | | | 43.3 | 2836.5 | 9.2 | 601.3 |
| Transmission Line Loop-In | | | | | | | | | | | | | | |
| <i>Survey</i> | | | | | | | | | | | | | | |
| ½-Ton Pick-Up | 2 | 3 | 8 | 9.54 | 1.2 | 0.26 | 23.3 | 69.8 | 4.9 | 14.8 | 9.3 | 27.9 | 2.0 | 5.9 |
| | | | | | | | | | | | 9.3 | 27.9 | 2.0 | 5.9 |
| <i>Marshalling Yards</i> | | | | | | | | | | | | | | |
| 1-Ton Crew Cab | 1 | 85 | 2 | 9.54 | 1.2 | 0.26 | 11.6 | 989.3 | 2.5 | 209.7 | 4.7 | 395.7 | 1.0 | 83.9 |
| Truck, Semi-Tractor | 1 | 85 | 1 | 9.54 | 2.9 | 0.61 | 27.4 | 2331.1 | 5.8 | 494.2 | 11.0 | 932.4 | 2.3 | 197.7 |
| | | | | | | | | | | | 15.6 | 1328.2 | 3.3 | 281.6 |
| <i>Roads and Landing Work</i> | | | | | | | | | | | | | | |
| 1-Ton Crew Cab | 1 | 3 | 5 | 9.54 | 1.2 | 0.26 | 11.6 | 34.9 | 2.5 | 7.4 | 4.7 | 14.0 | 1.0 | 3.0 |
| Water Truck | 3 | 3 | 10 | 9.54 | 2.9 | 0.61 | 82.3 | 246.8 | 17.4 | 52.3 | 32.9 | 98.7 | 7.0 | 20.9 |
| Lowboy Truck & Trailer | 1 | 3 | 4 | 9.54 | 2.9 | 0.61 | 27.4 | 82.3 | 5.8 | 17.4 | 11.0 | 32.9 | 2.3 | 7.0 |
| | | | | | | | | | | | 48.5 | 145.6 | 10.3 | 30.9 |
| <i>Install Foundations</i> | | | | | | | | | | | | | | |
| 1-Ton Crew Cab | 4 | 17 | 6 | 9.54 | 1.2 | 0.26 | 46.6 | 791.5 | 9.9 | 167.8 | 18.6 | 316.6 | 3.9 | 67.1 |
| 4,000 Gallon Water Truck | 2 | 17 | 5 | 9.54 | 2.9 | 0.61 | 54.8 | 932.4 | 11.6 | 197.7 | 21.9 | 373.0 | 4.7 | 79.1 |
| Concrete Mixer Truck | 6 | 17 | 5 | 9.54 | 2.9 | 0.61 | 164.5 | 2797.3 | 34.9 | 593.0 | 65.8 | 1118.9 | 14.0 | 237.2 |
| | | | | | | | | | | | 106.4 | 1808.5 | 22.6 | 383.4 |
| <i>Tower Legs, Haul and Erection</i> | | | | | | | | | | | | | | |
| 1-Ton Crew Cab | 1 | 4 | 6 | 9.54 | 1.2 | 0.26 | 11.6 | 46.6 | 2.5 | 9.9 | 4.7 | 18.6 | 1.0 | 3.9 |
| 30-Ton Crane Truck | 1 | 4 | 8 | 9.54 | 2.9 | 0.61 | 27.4 | 109.7 | 5.8 | 23.3 | 11.0 | 43.9 | 2.3 | 9.3 |
| Truck & Trailer | 1 | 4 | 5 | 9.54 | 2.9 | 0.61 | 27.4 | 109.7 | 5.8 | 23.3 | 11.0 | 43.9 | 2.3 | 9.3 |
| Truck & Trailer | 2 | 5 | 10 | 9.54 | 2.9 | 0.61 | 54.8 | 274.2 | 11.6 | 58.1 | 21.9 | 109.7 | 4.7 | 23.3 |
| | | | | | | | | | | | 48.5 | 216.1 | 10.3 | 45.8 |
| <i>Tower Assembly</i> | | | | | | | | | | | | | | |
| Crane Truck | 2 | 8 | 8 | 9.54 | 2.9 | 0.61 | 54.8 | 438.8 | 11.6 | 93.0 | 21.9 | 175.5 | 4.7 | 37.2 |
| Pick-Up Truck | 3 | 8 | 10 | 9.54 | 1.2 | 0.26 | 34.9 | 279.3 | 7.4 | 59.2 | 14.0 | 111.7 | 3.0 | 23.7 |
| Crew Cab Flat-Bed | 4 | 8 | 5 | 9.54 | 1.2 | 0.26 | 46.6 | 372.5 | 9.9 | 79.0 | 18.6 | 149.0 | 3.9 | 31.6 |
| Compressor Truck | 2 | 8 | 5 | 9.54 | 1.2 | 0.26 | 23.3 | 186.2 | 4.9 | 39.5 | 9.3 | 74.5 | 2.0 | 15.8 |
| | | | | | | | | | | | 63.8 | 510.7 | 13.5 | 108.3 |

Table F-9. Unpaved Road Travel During Construction - Fugitive Dust Emissions

| Activity | Number | Days | Hours /Day | Max VMT/day ¹ | F PM10 (lbs/VMT) | F PM2.5 (lbs/VMT) | Uncontrolled Emissions | | | | Controlled Emissions (60 percent) | | | |
|-------------------------------|--------|------|------------|--------------------------|------------------|-------------------|------------------------|--------------|-----------|--------------|-----------------------------------|--------------|-----------|--------------|
| | | | | | | | PM10 | | PM2.5 | | PM10 | | PM2.5 | |
| | | | | | | | (lbs/day) | lbs activity | (lbs/day) | lbs activity | (lbs/day) | lbs activity | (lbs/day) | lbs activity |
| <i>Tower and TSP Erection</i> | | | | | | | | | | | | | | |
| Pick-Up Truck | 1 | 8 | 5 | 9.54 | 1.2 | 0.26 | 11.6 | 93.1 | 2.5 | 19.7 | 4.7 | 37.2 | 1.0 | 7.9 |
| Crew Cab Flat-Bed | 2 | 8 | 5 | 9.54 | 1.2 | 0.26 | 23.3 | 186.2 | 4.9 | 39.5 | 9.3 | 74.5 | 2.0 | 15.8 |
| Compressor Truck | 1 | 8 | 5 | 9.54 | 1.2 | 0.26 | 11.6 | 93.1 | 2.5 | 19.7 | 4.7 | 37.2 | 1.0 | 7.9 |
| <i>Tower Removal</i> | | | | | | | | | | | | | | |
| Pick-Up Truck | 1 | 4 | 8 | 9.54 | 1.2 | 0.26 | 11.6 | 46.6 | 2.5 | 9.9 | 4.7 | 18.6 | 1.0 | 3.9 |
| Flat-Bed Truck | 1 | 4 | 8 | 9.54 | 1.2 | 0.26 | 11.6 | 46.6 | 2.5 | 9.9 | 4.7 | 18.6 | 1.0 | 3.9 |
| <i>Conductor Installation</i> | | | | | | | | | | | | | | |
| Crew Cab Flat-Bed | 3 | 10 | 8 | 9.54 | 1.2 | 0.26 | 34.9 | 349.2 | 7.4 | 74.0 | 14.0 | 139.7 | 3.0 | 29.6 |
| Wire Truck & Trailer | 2 | 6 | 2 | 9.54 | 2.9 | 0.61 | 54.8 | 329.1 | 11.6 | 69.8 | 21.9 | 131.6 | 4.7 | 27.9 |
| Dump Truck (Trash) | 1 | 10 | 2 | 9.54 | 2.9 | 0.61 | 27.4 | 274.2 | 5.8 | 58.1 | 11.0 | 109.7 | 2.3 | 23.3 |
| Pick-Up Truck | 1 | 10 | 10 | 9.54 | 1.2 | 0.26 | 11.6 | 116.4 | 2.5 | 24.7 | 4.7 | 46.6 | 1.0 | 9.9 |
| Log Truck & Trailer | 1 | 10 | 2 | 9.54 | 2.9 | 0.61 | 27.4 | 274.2 | 5.8 | 58.1 | 11.0 | 109.7 | 2.3 | 23.3 |
| Static Truck | 1 | 6 | 2 | 9.54 | 2.9 | 0.61 | 27.4 | 164.5 | 5.8 | 34.9 | 11.0 | 65.8 | 2.3 | 14.0 |
| Lowboy Truck & Trailer | 1 | 10 | 2 | 9.54 | 2.9 | 0.61 | 27.4 | 274.2 | 5.8 | 58.1 | 11.0 | 109.7 | 2.3 | 23.3 |
| <i>Restoration</i> | | | | | | | | | | | | | | |
| Crew Cab | 1 | 4 | 5 | 9.54 | 1.2 | 0.26 | 11.6 | 46.6 | 2.5 | 9.9 | 4.7 | 18.6 | 1.0 | 3.9 |
| Water Truck | 3 | 4 | 10 | 9.54 | 2.9 | 0.61 | 82.3 | 329.1 | 17.4 | 69.8 | 32.9 | 131.6 | 7.0 | 27.9 |
| Lowboy Truck & Trailer | 1 | 4 | 4 | 9.54 | 2.9 | 0.61 | 27.4 | 109.7 | 5.8 | 23.3 | 11.0 | 43.9 | 2.3 | 9.3 |
| <i>Max Transmission Line</i> | | | | | | | | | | | | | | |
| Substations | | | | | | | | | | | | | | |
| Devers Substation | | | | | | | | | | | | | | |
| Worker Traffic | 6 | 73 | - | 3.80 | 1.2 | 0.26 | 27.8 | 2030.6 | 5.9 | 430.5 | 11.1 | 812.3 | 2.4 | 172.2 |
| Eisenhower Substation | | | | | | | | | | | | | | |
| Worker Traffic | 6 | 73 | - | 3.80 | 1.2 | 0.26 | 27.8 | 2030.6 | 5.9 | 430.5 | 11.1 | 812.3 | 2.4 | 172.2 |
| Farrell Substation | | | | | | | | | | | | | | |
| Worker Traffic | 6 | 97 | - | 3.80 | 1.2 | 0.26 | 27.8 | 2698.3 | 5.9 | 572.0 | 11.1 | 1079.3 | 2.4 | 228.8 |
| Garnet Substation | | | | | | | | | | | | | | |
| Worker Traffic | 2 | 32 | - | 3.80 | 1.2 | 0.26 | 9.3 | 296.7 | 2.0 | 62.9 | 3.7 | 118.7 | 0.8 | 25.2 |
| Thornhill Substation | | | | | | | | | | | | | | |
| Worker Traffic | 2 | 80 | - | 3.80 | 1.2 | 0.26 | 9.3 | 741.8 | 2.0 | 157.3 | 3.7 | 296.7 | 0.8 | 62.9 |
| <i>Max Substation</i> | | | | | | | | | | | | | | |
| | | | | | | | | | | | 11.1 | 3119.2 | 2.4 | 661.3 |

Notes

1. Assumed that the vehicles will travel twice the longest distance of unpaved road, which is on the route for Farrell-Garnet

Table F-10. Paved Road Travel During Construction - Fugitive Dust Emissions

Lightweight Vehicles on Paved Road Fugitive Dust
 From SCAQMD CEQA AQ Handbook
 Table A9-9-B

E = VxG (PM10 with street cleaning)

V = vehicle miles travelled
 G = EF from table A9-9-9-B1

| G(PM10 lb/VMT) | Road Type |
|----------------|------------------------|
| 0.018 | Local Streets |
| 0.013 | Collector Streets |
| 0.0064 | Major Streets/Highways |
| 0.00065 | Freeways |

Assumed Mix of Roads

| | |
|------|--|
| 0.10 | Local Streets (assumed 10 percent) |
| 0.70 | Collector Streets (assumed 70 percent) |
| 0.10 | Major Streets/Highways (10 percent) |
| 0.10 | Freeways (assumed 10 percent) |

Note that the vehicles miles traveled assumes the following:
 1. The vehicles are always traveling when they are operational.
 2. The speed of the vehicles traveling on the paved road was assumed to be 50 miles per hour
 3. 80 percent of the roads are paved.

Composite light vehicle Emission Factor

| | |
|----------------|---|
| 0.0116 | PM10 per VMT |
| 0.169 | PM2.5 fraction of PM10 from SCAQMD Table A - Updated CEIDARS Table with PM2.5 Fractions |
| 0.00196 | PM2.5 per VMT |

Heavy Vehicles on Paved Road Fugitive Dust
 Use SCAQMD CEQA Table A9-9-C
 E = VxF (PM10 without street cleaning)
 V = vehicle miles travelled
 G from table A9-9-C1
 F = 0.77*((G*0.35)^0.3) lbs/VMT

Assume 60 percent reduction for street sweeping per Table A9-9

| | | | |
|------------------------|---------|-------------|-----------|
| Local Streets | 0.04 | 0.213958299 | 0.0855833 |
| Collector Streets | 0.03 | 0.196267104 | 0.0785068 |
| Major Streets/Highways | 0.012 | 0.149095835 | 0.0596383 |
| Freeways | 0.00065 | 0.062170612 | 0.0248682 |

Assumed Mix of Roads

| | |
|------|--|
| 0.10 | Local Streets (assumed 10 percent) |
| 0.10 | Collector Streets (assumed 10 percent) |
| 0.10 | Major Streets/Highways (10 percent) |
| 0.70 | Freeways (assumed 70 percent) |

Composite heavy vehicle Emission Factor

| | |
|---------------|---|
| 0.040 | PM10 per VMT |
| 0.169 | PM2.5 fraction of PM10 from SCAQMD Table A - Updated CEIDARS Table with PM2.5 Fractions |
| 0.0067 | PM2.5 per VMT |

Table F-10. Paved Road Travel During Construction - Fugitive Dust Emissions

| Activity | Number | Days | Hours /Day | VMT/day | F PM10 (lbs/VMT) | F PM2.5 (lbs/VMT) | Emissions Assuming Street Cleaning | | | |
|--|--------|------|------------|---------|------------------|-------------------|------------------------------------|--------------|------------|--------------|
| | | | | | | | PM10 | | PM2.5 | |
| | | | | | | | (lbs/day) | lbs activity | (lbs/day) | lbs activity |
| Subtransmission Line | | | | | | | | | | |
| <i>Survey</i> | | | | | | | | | | |
| ½-Ton Pick-Up | 1 | 3 | 10 | 9.54 | 0.0116 | 0.00196 | 0.1 | 0.3 | 0.0 | 0.1 |
| | | | | | | | <i>0.1</i> | <i>0.3</i> | <i>0.0</i> | <i>0.1</i> |
| <i>Roads</i> | | | | | | | | | | |
| 1-Ton Crew Cab 4X4 | 2 | 10 | 2 | 9.54 | 0.0116 | 0.00196 | 0.2 | 2.2 | 0.0 | 0.4 |
| Road Grader | 1 | 10 | 10 | 9.54 | 0.0398 | 0.00672 | 0.4 | 3.8 | 0.1 | 0.6 |
| Track-Type Dozer | 2 | 10 | 2.5 | 9.54 | 0.0398 | 0.00672 | 0.8 | 7.6 | 0.1 | 1.3 |
| Water Truck | 1 | 10 | 10 | 9.54 | 0.0398 | 0.00672 | 0.4 | 3.8 | 0.1 | 0.6 |
| | | | | | | | <i>1.7</i> | <i>17.4</i> | <i>0.3</i> | <i>2.9</i> |
| <i>Pole Framing and Setting</i> | | | | | | | | | | |
| ¾-Ton Suburban | 2 | 147 | 10 | 9.54 | 0.0116 | 0.00196 | 0.2 | 32.5 | 0.0 | 5.5 |
| 5-Ton Framing Truck 4X4 | 2 | 83 | 10 | 9.54 | 0.0398 | 0.00672 | 0.8 | 63.0 | 0.1 | 10.6 |
| 30-Ton Line Truck | 2 | 83 | 10 | 9.54 | 0.0398 | 0.00672 | 0.8 | 63.0 | 0.1 | 10.6 |
| Digger Truck | 1 | 24 | 10 | 9.54 | 0.0398 | 0.00672 | 0.4 | 9.1 | 0.1 | 1.5 |
| Water Truck | 1 | 83 | 10 | 9.54 | 0.0398 | 0.00672 | 0.4 | 31.5 | 0.1 | 5.3 |
| Backhoe | 2 | 147 | 10 | 9.54 | 0.0398 | 0.00672 | 0.8 | 111.6 | 0.1 | 18.9 |
| Bucket Truck | 2 | 147 | 10 | 9.54 | 0.0398 | 0.00672 | 0.8 | 111.6 | 0.1 | 18.9 |
| Truck-Mounted Crane | 2 | 147 | 10 | 9.54 | 0.0398 | 0.00672 | 0.8 | 111.6 | 0.1 | 18.9 |
| 30-Ton Crane | 1 | 14 | 10 | 9.54 | 0.0398 | 0.00672 | 0.4 | 5.3 | 0.1 | 0.9 |
| Cement Truck | 1 | 3 | 10 | 9.54 | 0.0398 | 0.00672 | 0.4 | 1.1 | 0.1 | 0.2 |
| | | | | | | | <i>5.5</i> | <i>540.3</i> | <i>0.9</i> | <i>91.3</i> |
| <i>Material Delivery</i> | | | | | | | | | | |
| 60-Foot Flat-Bed Pole Truck | 2 | 5 | 8 | 9.54 | 0.0398 | 0.00672 | 0.8 | 3.8 | 0.1 | 0.6 |
| Forklift | 1 | 5 | 8 | 9.54 | 0.0398 | 0.00672 | 0.4 | 1.9 | 0.1 | 0.3 |
| | | | | | | | <i>1.1</i> | <i>5.7</i> | <i>0.2</i> | <i>1.0</i> |
| <i>Conductor Installation</i> | | | | | | | | | | |
| Flat-Bed Truck & Trailer (Wire Puller) | 1 | 24 | 6 | 9.54 | 0.0398 | 0.00672 | 0.4 | 9.1 | 0.1 | 1.5 |
| Flat-Bed Truck & Trailer (Wire Dolly) | 1 | 24 | 6 | 9.54 | 0.0398 | 0.00672 | 0.4 | 9.1 | 0.1 | 1.5 |
| 30-Ton Line Truck | 2 | 24 | 5 | 9.54 | 0.0398 | 0.00672 | 0.8 | 18.2 | 0.1 | 3.1 |
| ¾-Ton Suburban | 2 | 14 | 10 | 9.54 | 0.0116 | 0.00196 | 0.2 | 3.1 | 0.0 | 0.5 |
| Water Truck | 1 | 24 | 10 | 9.54 | 0.0398 | 0.00672 | 0.4 | 9.1 | 0.1 | 1.5 |
| Bucket Truck | 2 | 24 | 6 | 9.54 | 0.0398 | 0.00672 | 0.8 | 18.2 | 0.1 | 3.1 |
| Truck-Mounted Crane | 2 | 24 | 6 | 9.54 | 0.0398 | 0.00672 | 0.8 | 18.2 | 0.1 | 3.1 |
| | | | | | | | <i>3.6</i> | <i>85.1</i> | <i>0.6</i> | <i>14.4</i> |
| <i>Restoration</i> | | | | | | | | | | |
| 1-Ton Crew Cab 4X4 | 2 | 40 | 8 | 9.54 | 0.0116 | 0.00196 | 0.2 | 8.9 | 0.0 | 1.5 |
| Water Truck | 1 | 40 | 8 | 9.54 | 0.0398 | 0.00672 | 0.4 | 15.2 | 0.1 | 2.6 |
| | | | | | | | <i>0.6</i> | <i>24.0</i> | <i>0.1</i> | <i>4.1</i> |
| <i>Max Subtransmission Line</i> | | | | | | | | | | |
| | | | | | | | <i>5.5</i> | <i>540.3</i> | <i>0.9</i> | <i>91.3</i> |
| Telecommunications | | | | | | | | | | |
| Crew Truck (gasoline) | 2 | 114 | 8 | 14 | 0.0116 | 0.00196 | 0.3 | 37.0 | 0.1 | 6.3 |
| Crew Truck (gasoline) | 1 | 85 | 8 | 14 | 0.0116 | 0.00196 | 0.2 | 13.8 | 0.0 | 2.3 |

Table F-10. Paved Road Travel During Construction - Fugitive Dust Emissions

| Activity | Number | Days | Hours /Day | VMT/day | F PM10 (lbs/VMT) | F PM2.5 (lbs/VMT) | Emissions Assuming Street Cleaning | | | |
|---|--------|------|------------|---------|------------------|-------------------|------------------------------------|---------------------|-------------------|--------------------|
| | | | | | | | PM10 | | PM2.5 | |
| | | | | | | | (lbs/day) | lbs activity | (lbs/day) | lbs activity |
| Bucket Truck | 2 | 25 | 8 | 14 | 0.0398 | 0.00672 | 1.1 <i>1.6</i> | 27.8 <i>78.7</i> | 0.2 <i>0.3</i> | 4.7 <i>13.3</i> |
| <i>Transmission Line Loop-In Survey</i> | | | | | | | | | | |
| ½-Ton Pick-Up | 2 | 3 | 8 | 14 | 0.0116 | 0.00672 | 0.3 <i>0.3</i> | 1.0 <i>1.0</i> | 0.2 <i>0.2</i> | 0.6 <i>0.6</i> |
| <i>Marshalling Yards</i> | | | | | | | | | | |
| 1-Ton Crew Cab | 1 | 85 | 2 | 14 | 0.0116 | 0.00196 | 0.2 | 13.8 | 0.0 | 2.3 |
| Truck, Semi-Tractor | 1 | 85 | 1 | 14 | 0.0398 | 0.00672 | 0.6 <i>0.7</i> | 47.3 <i>61.1</i> | 0.1 <i>0.1</i> | 8.0 <i>10.3</i> |
| <i>Roads and Landing Work</i> | | | | | | | | | | |
| 1-Ton Crew Cab | 1 | 3 | 5 | 14 | 0.0116 | 0.00196 | 0.2 | 0.5 | 0.0 | 0.1 |
| Water Truck | 3 | 3 | 10 | 14 | 0.0398 | 0.00672 | 1.7 | 5.0 | 0.3 | 0.8 |
| Lowboy Truck & Trailer | 1 | 3 | 4 | 14 | 0.0398 | 0.00672 | 0.6 <i>2.4</i> | 1.7 <i>7.2</i> | 0.1 <i>0.4</i> | 0.3 <i>1.2</i> |
| <i>Install Foundations</i> | | | | | | | | | | |
| 1-Ton Crew Cab | 4 | 17 | 6 | 14 | 0.0116 | 0.00196 | 0.6 | 11.0 | 0.1 | 1.9 |
| 4,000 Gallon Water Truck | 2 | 17 | 5 | 14 | 0.0398 | 0.00672 | 1.1 | 18.9 | 0.2 | 3.2 |
| Concrete Mixer Truck | 6 | 17 | 5 | 14 | 0.0398 | 0.00672 | 3.3 <i>5.1</i> | 56.8 <i>86.8</i> | 0.6 <i>0.9</i> | 9.6 <i>14.7</i> |
| <i>Tower Legs, Haul and Erection</i> | | | | | | | | | | |
| 1-Ton Crew Cab | 1 | 4 | 6 | 14 | 0.0116 | 0.00196 | 0.2 | 0.6 | 0.0 | 0.1 |
| 30-Ton Crane Truck | 1 | 4 | 8 | 14 | 0.0398 | 0.00672 | 0.6 | 2.2 | 0.1 | 0.4 |
| Truck & Trailer | 1 | 4 | 5 | 14 | 0.0398 | 0.00672 | 0.6 | 2.2 | 0.1 | 0.4 |
| Truck & Trailer | 2 | 5 | 10 | 14 | 0.0398 | 0.00672 | 1.1 <i>2.4</i> | 5.6 <i>10.7</i> | 0.2 <i>0.4</i> | 0.9 <i>1.8</i> |
| <i>Tower Assembly</i> | | | | | | | | | | |
| Crane Truck | 2 | 8 | 8 | 14 | 0.0398 | 0.00672 | 1.1 | 8.9 | 0.2 | 1.5 |
| Pick-Up Truck | 3 | 8 | 10 | 14 | 0.0116 | 0.00196 | 0.5 | 3.9 | 0.1 | 0.7 |
| Crew Cab Flat-Bed | 4 | 8 | 5 | 14 | 0.0116 | 0.00196 | 0.6 | 5.2 | 0.1 | 0.9 |
| Compressor Truck | 2 | 8 | 5 | 14 | 0.0116 | 0.00196 | 0.3 <i>2.6</i> | 2.6 <i>20.6</i> | 0.1 <i>0.4</i> | 0.4 <i>3.5</i> |
| <i>Tower and TSP Erection</i> | | | | | | | | | | |
| Pick-Up Truck | 1 | 8 | 5 | 14 | 0.0116 | 0.00196 | 0.2 | 1.3 | 0.0 | 0.2 |
| Crew Cab Flat-Bed | 2 | 8 | 5 | 14 | 0.0116 | 0.00196 | 0.3 | 2.6 | 0.1 | 0.4 |
| Compressor Truck | 1 | 8 | 5 | 14 | 0.0116 | 0.00196 | 0.2 <i>0.6</i> | 1.3 <i>5.2</i> | 0.0 <i>0.1</i> | 0.2 <i>0.9</i> |
| <i>Tower Removal</i> | | | | | | | | | | |
| Pick-Up Truck | 1 | 4 | 8 | 14 | 0.0116 | 0.00196 | 0.2 | 0.6 | 0.0 | 0.1 |
| Flat-Bed Truck | 1 | 4 | 8 | 14 | 0.0116 | 0.00196 | 0.2 <i>0.3</i> | 0.6 <i>1.3</i> | 0.0 <i>0.1</i> | 0.1 <i>0.2</i> |
| <i>Conductor Installation</i> | | | | | | | | | | |
| Crew Cab Flat-Bed | 3 | 10 | 8 | 14 | 0.0116 | 0.00196 | 0.5 | 4.9 | 0.1 | 0.8 |

Table F-10. Paved Road Travel During Construction - Fugitive Dust Emissions

| Activity | Number | Days | Hours /Day | VMT/day | F PM10 (lbs/VMT) | F PM2.5 (lbs/VMT) | Emissions Assuming Street Cleaning | | | |
|------------------------------|--------|------|------------|---------|------------------|-------------------|------------------------------------|--------------|------------|--------------|
| | | | | | | | PM10 | | PM2.5 | |
| | | | | | | | (lbs/day) | lbs activity | (lbs/day) | lbs activity |
| Wire Truck & Trailer | 2 | 6 | 2 | 14 | 0.0398 | 0.00672 | 1.1 | 6.7 | 0.2 | 1.1 |
| Dump Truck (Trash) | 1 | 10 | 2 | 14 | 0.0398 | 0.00672 | 0.6 | 5.6 | 0.1 | 0.9 |
| Pick-Up Truck | 1 | 10 | 10 | 14 | 0.0116 | 0.00196 | 0.2 | 1.6 | 0.0 | 0.3 |
| Log Truck & Trailer | 1 | 10 | 2 | 14 | 0.0398 | 0.00672 | 0.6 | 5.6 | 0.1 | 0.9 |
| Static Truck | 1 | 6 | 2 | 14 | 0.0398 | 0.00672 | 0.6 | 3.3 | 0.1 | 0.6 |
| Lowboy Truck & Trailer | 1 | 10 | 2 | 14 | 0.0398 | 0.00672 | 0.6 | 5.6 | 0.1 | 0.9 |
| <i>Restoration</i> | | | | | | | 4.0 | 33.2 | 0.7 | 5.6 |
| Crew Cab | 1 | 4 | 5 | 14 | 0.0116 | 0.00196 | 0.2 | 0.6 | 0.0 | 0.1 |
| Water Truck | 3 | 4 | 10 | 14 | 0.0398 | 0.00672 | 1.7 | 6.7 | 0.3 | 1.1 |
| Lowboy Truck & Trailer | 1 | 4 | 4 | 14 | 0.0398 | 0.00672 | 0.6 | 2.2 | 0.1 | 0.4 |
| <i>Max Telecommunication</i> | | | | | | | 2.4 | 9.6 | 0.4 | 1.6 |
| | | | | | | | 5.1 | 86.8 | 0.9 | 14.7 |

Notes

1. Assumed that the vehicles will travel twice the longest distance of paved road, which is on the route for Farrell-Garnet

Table F-11. Subtransmission Line Construction - Route Details

| Route | Distance (Miles) | |
|---|------------------|---------|
| | Paved | Unpaved |
| Farrell-Garnet (Alternative Route 1) Starting from Devers Substation | 6.00 | 2.33 |
| Farrell-Garnet (Alternative Route 2) Starting from Devers Substation | 4.60 | 4.77 |
| Farrell-Garnet (Alternative Route 3) Starting from Devers Substation | 7.00 | 2.33 |
| Devers Coachella Valley Loop-In Starting from Mirage Substation | 0.00 | 0.95 |
| Mirage-Santa Rosa (Alternative Route 1) Starting from Mirage Substation | 0.00 | 1.42 |
| Mirage-Santa Rosa (Alternative Route 2) Starting from Mirage Substation | 2.93 | 0.00 |
| Bob Hope Dr. & Dinah Shore Dr. Substation Line Reconfiguration (Alternative Route 1) Starting from Mirage Substation | 2.67 | 1.42 |
| Bob Hope & Dinah Shore Dr. Substation Line Reconfiguration (Alternative Route 2) Starting from Mirage Substation | 2.77 | 0.00 |
| Gerald Ford Dr. & Portola Ave. Substation Line Reconfiguration (Alternative Route 1) Starting from Mirage Substation | 0.00 | 2.02 |
| Gerald Ford Dr. & Portola Ave. Substation Line Reconfiguration (Alternative Route 2) Starting from Mirage Substation | 2.97 | 0.57 |

Notes

1. Based on detailed map of the area. Distances are approximate.

THIS PAGE IS INTENTIONALLY BLANK

Table F-12. Equipment Exhaust During Transmission Line Construction - Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
|--|-----|-----------------|------------------|------------------------|-----------------------|------------------------|------------------------|-------------------------|
| TRANSMISSION LINE LOOP-IN | | | | | | | | |
| Survey | | | | | | | | |
| - 2 ½-Ton Pick-Up | 200 | 3 | 8 | 1.4 | 10.5 | 11.4 | 0.0 | 0.4 |
| - Total Survey | | | | 1.4 | 10.5 | 11.4 | 0.0 | 0.4 |
| Marshalling Yards | | | | | | | | |
| - 1 1-Ton Crew Cab | 300 | 85 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| - 1 30-Ton Crane | 300 | 85 | 2 | 0.4 | 1.6 | 4.0 | 0.0 | 0.2 |
| - 2 10,000-Pound Rough-Terrain Forklift | 200 | 85 | 5 | 0.7 | 1.8 | 8.3 | 0.0 | 0.3 |
| - 1 Truck, Semi-Tractor | 350 | 85 | 1 | 0.1 | 0.4 | 1.3 | 0.0 | 0.1 |
| - Total Marshalling Yards | | | | 1.3 | 4.4 | 13.7 | 0.0 | 0.5 |
| Roads and Landing Work | | | | | | | | |
| - 1 1-Ton Crew Cab | 300 | 3 | 5 | 0.2 | 1.6 | 0.2 | 0.0 | 0.0 |
| - 1 Road Grader | 350 | 3 | 6 | 1.4 | 5.3 | 14.3 | 0.0 | 0.5 |
| - 1 Track-Type Dozer | 350 | 3 | 6 | 2.3 | 11.9 | 21.0 | 0.0 | 0.9 |
| - 1 Drum-Type Compactor | 250 | 3 | 6 | 1.5 | 4.2 | 16.9 | 0.0 | 0.6 |
| - 3 Water Truck | 350 | 3 | 10 | 3.2 | 12.3 | 40.1 | 0.0 | 1.9 |
| - 1 Lowboy Truck & Trailer | 250 | 3 | 4 | 0.4 | 1.6 | 5.3 | 0.0 | 0.3 |
| - 1 Excavator | 300 | 3 | 6 | 1.3 | 4.3 | 13.3 | 0.0 | 0.5 |
| - 1 Front-End Loader | 350 | 3 | 6 | 1.7 | 5.8 | 18.8 | 0.0 | 0.7 |
| - Total Roads and Landing Work | | | | 12.1 | 46.9 | 130.1 | 0.1 | 5.4 |
| Install Foundations | | | | | | | | |
| - 4 1-Ton Crew Cab | 300 | 17 | 6 | 0.8 | 7.6 | 0.8 | 0.0 | 0.1 |
| - 2 30-Ton Crane | 300 | 17 | 5 | 2.0 | 7.8 | 19.9 | 0.0 | 0.8 |
| - 1 Front-End Loader | 200 | 17 | 5 | 0.8 | 2.2 | 9.0 | 0.0 | 0.3 |
| - 2 Diggers | 500 | 17 | 8 | 4.6 | 15.3 | 50.2 | 0.1 | 1.8 |
| - 2 4,000-Gallon Water Truck | 350 | 17 | 5 | 1.1 | 4.1 | 13.4 | 0.0 | 0.6 |
| - 6 Concrete Mixer Truck | 425 | 17 | 5 | 3.2 | 12.3 | 40.1 | 0.0 | 1.9 |
| - Total Install Foundations | | | | 12.4 | 49.27 | 133.36 | 0.15 | 5.48 |
| Tower Legs Haul and Erect | | | | | | | | |
| - 1 1-Ton Crew Cab | 300 | 4 | 6 | 0.2 | 1.9 | 0.2 | 0.0 | 0.0 |
| - 1 30-Ton Crane Truck | 300 | 4 | 8 | 0.8 | 3.3 | 10.7 | 0.0 | 0.5 |
| - 1 10,000-Pound Rough-Terrain Forklift | 200 | 4 | 6 | 0.4 | 1.1 | 5.0 | 0.0 | 0.2 |
| - 1 Truck & Trailer | 350 | 4 | 5 | 0.5 | 2.0 | 6.7 | 0.0 | 0.3 |
| - 1 10,000-Pound Rough-Terrain Forklift | 200 | 5 | 8 | 0.6 | 1.5 | 6.7 | 0.0 | 0.2 |
| - 2 Truck & Trailer | 350 | 5 | 10 | 2.1 | 8.2 | 26.7 | 0.0 | 1.3 |
| - Total Tower Legs Haul and Erect | | | | 4.7 | 17.93 | 55.97 | 0.06 | 2.51 |

Table F-12. Equipment Exhaust During Transmission Line Construction - Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
|---------------------------------------|-----|-----------------|------------------|------------------------|-----------------------|------------------------|------------------------|-------------------------|
| Tower Assembly | | | | | | | | |
| - 2 Rough-Terrain Crane | 400 | 8 | 8 | 3.2 | 12.4 | 31.8 | 0.0 | 1.2 |
| - 2 Crane Truck | 300 | 8 | 8 | 1.7 | 6.5 | 21.4 | 0.0 | 1.0 |
| - 2 Rough-Terrain Fork Lift | 200 | 8 | 5 | 0.7 | 1.8 | 8.3 | 0.0 | 0.3 |
| - 3 Pick-Up Truck | 300 | 8 | 10 | 2.7 | 19.8 | 21.3 | 0.0 | 0.8 |
| - 4 Crew Cab Flat-Bed | 300 | 8 | 5 | 0.6 | 6.3 | 0.7 | 0.0 | 0.1 |
| - 2 Compressor Truck | 350 | 8 | 5 | 1.1 | 4.1 | 13.4 | 0.0 | 0.6 |
| - Total Tower Assembly | | | | 10.0 | 50.94 | 96.90 | 0.10 | 3.99 |
| Tower TSP Erection | | | | | | | | |
| - 1 Pick-Up Truck | 300 | 8 | 5 | 0.4 | 3.3 | 3.6 | 0.0 | 0.1 |
| - 2 Crew Cab Flat-Bed | 300 | 8 | 5 | 0.3 | 3.2 | 0.3 | 0.0 | 0.0 |
| - 1 Compressor Truck | 350 | 8 | 5 | 0.5 | 2.0 | 6.7 | 0.0 | 0.3 |
| - 1 Rough-Terrain Crane | 500 | 8 | 6 | 1.2 | 4.7 | 11.9 | 0.0 | 0.5 |
| - Total Tower TSP Erection | | | | 2.5 | 13.2 | 22.5 | 0.0 | 0.9 |
| Tower Removal | | | | | | | | |
| - 1 Pick-Up Truck | 300 | 4 | 8 | 0.7 | 5.3 | 5.7 | 0.0 | 0.2 |
| - 1 Flat-Bed Truck | 350 | 4 | 8 | 0.3 | 2.5 | 0.3 | 0.0 | 0.0 |
| - Total Tower Removal | | | | 1.0 | 7.8 | 6.0 | 0.0 | 0.2 |
| Conductor Installation | | | | | | | | |
| - 3 Crew Cab Flat-Bed Bed | 300 | 10 | 8 | 0.8 | 7.6 | 0.8 | 0.0 | 0.1 |
| - 2 Wire Truck & Trailer | 350 | 6 | 2 | 0.4 | 1.6 | 5.3 | 0.0 | 0.3 |
| - 1 Dump Truck (Trash) | 350 | 10 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| - 1 Pick-Up Truck | 300 | 10 | 10 | 0.9 | 6.6 | 7.1 | 0.0 | 0.3 |
| - 2 Manitex | 350 | 10 | 6 | 2.3 | 8.5 | 27.3 | 0.0 | 0.9 |
| - 1 Manitex | 350 | 10 | 8 | 1.6 | 5.7 | 18.2 | 0.0 | 0.6 |
| - 2 Sleeving Rigs | 350 | 10 | 2 | 0.6 | 2.3 | 8.1 | 0.0 | 0.3 |
| - 1 Log Truck & Trailer | 500 | 10 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| - 1 Rough-Terrain Fork Lift | 350 | 10 | 2 | 0.1 | 0.4 | 1.7 | 0.0 | 0.1 |
| - 1 580 Case Backhoe | 120 | 6 | 2 | 0.2 | 0.7 | 1.3 | 0.0 | 0.1 |
| - 4 Spacing Cart | 10 | 6 | 4 | 0.2 | 1.0 | 1.2 | 0.0 | 0.1 |
| - 1 Static Truck | 350 | 6 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| - 1 Static Tensioner | 0 | 6 | 2 | 0.0 | 0.1 | 0.1 | 0.0 | 0.0 |
| - 2 3-Drum Strawline Puller | 300 | 6 | 4 | 1.6 | 5.7 | 18.2 | 0.0 | 0.6 |
| - 1 60lk Puller | 525 | 6 | 3 | 0.6 | 2.1 | 6.8 | 0.0 | 0.2 |
| - 1 Sag Cat with 2 Winches | 350 | 6 | 2 | 0.4 | 1.4 | 4.6 | 0.0 | 0.2 |
| - 4 D8 Cat | 300 | 6 | 1 | 1.2 | 3.8 | 12.6 | 0.0 | 0.4 |
| - 1 Hughes 500 E Helicopter | 650 | 3 | 4 | 1.5 | 17.6 | 16.6 | 1.4 | 2.3 |
| - 1 Fuel, Helicopter Support Truck | 300 | 3 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| - 1 Low Boy Truck & Trailer | 500 | 10 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| - Total Conductor Installation | | | | 13.4 | 69.1 | 143.3 | 1.5 | 7.0 |

Table F-12. Equipment Exhaust During Transmission Line Construction - Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
|--|-----------|----------------------------|-----------------------------|---------------------------------------|----------------------------------|---------------------------------------|---------------------------------------|--|
| Restoration | | | | | | | | |
| - 1 Crew Cab | 300 | 4 | 5 | 0.2 | 1.6 | 0.2 | 0.0 | 0.0 |
| - 1 Road Grader | 350 | 4 | 6 | 1.4 | 5.3 | 14.3 | 0.0 | 0.5 |
| - 1 Track-Type Dozer | 350 | 4 | 6 | 2.3 | 11.9 | 21.0 | 0.0 | 0.9 |
| - 1 Drum-Type Compactor | 250 | 4 | 6 | 1.5 | 4.2 | 16.9 | 0.0 | 0.6 |
| - 3 Water Trucks | 350 | 4 | 10 | 3.2 | 12.3 | 40.1 | 0.0 | 1.9 |
| - 1 Lowboy Truck & Trailer | 500 | 4 | 4 | 0.4 | 1.6 | 5.3 | 0.0 | 0.3 |
| - 1 Front End Loader | 350 | 4 | 6 | 1.7 | 5.8 | 18.8 | 0.0 | 0.7 |
| - 1 Excavator | 300 | 4 | 6 | 1.3 | 4.3 | 13.3 | 0.0 | 0.5 |
| - Total Restoration | | | | 12.1 | 46.9 | 130.1 | 0.1 | 5.4 |
| Maximum Daily Emissions From Transmission Line Construction | | | | 13.4 | 69.1 | 143.3 | 1.5 | 7.0 |

THIS PAGE IS INTENTIONALLY BLANK

Table F-13. Transmission Line Emission Factors

| Off-Road Construction Equipment | Emission Factors | | | | | | Notes: |
|--|------------------|-------------|------------|-------------|-------------|------------|--|
| | HP (hp) | ROG (lb/hr) | CO (lb/hr) | NOX (lb/hr) | SOX (lb/hr) | PM (lb/hr) | |
| Bore/Drill Rigs | 350 | 0.1566 | 0.5631 | 2.0226 | 0.0031 | 0.0640 | Used for drillers, and sleeve rigs |
| Crushers/Process Equipment | 250 | 0.2529 | 0.7004 | 2.8190 | 0.0028 | 0.0959 | Used for compactors |
| Cranes | 300 | 0.2012 | 0.7762 | 1.9878 | 0.0018 | 0.0771 | Used for cranes |
| | 400 | 0.2012 | 0.7762 | 1.9878 | 0.0018 | 0.0771 | |
| | 500 | 0.2012 | 0.7762 | 1.9878 | 0.0018 | 0.0771 | |
| Excavators | 300 | 0.2175 | 0.7092 | 2.2162 | 0.0023 | 0.0803 | Used for excavators |
| Forklifts | 200 | 0.0716 | 0.1822 | 0.8315 | 0.0009 | 0.0254 | Used for forklifts |
| | 350 | 0.0716 | 0.1822 | 0.8315 | 0.0009 | 0.0254 | |
| Graders | 350 | 0.2360 | 0.8828 | 2.3908 | 0.0023 | 0.0904 | Used for graders |
| | 0 | 0.0119 | 0.0617 | 0.0750 | 0.0002 | 0.0046 | |
| | 10 | 0.0119 | 0.0617 | 0.0750 | 0.0002 | 0.0046 | |
| | 300 | 0.1944 | 0.7066 | 2.2771 | 0.0025 | 0.0770 | |
| | 350 | 0.1944 | 0.7066 | 2.2771 | 0.0025 | 0.0770 | |
| Other Construction Equipment | 525 | 0.1944 | 0.7066 | 2.2771 | 0.0025 | 0.0770 | Used for manitex, spacing carts, pullers, and tensioners |
| Other General Industrial Equipment | 650 | 0.4552 | 1.5794 | 4.8663 | 0.0044 | 0.1724 | |
| Rubber-Tired Dozers | 300 | 0.3895 | 1.9869 | 3.5050 | 0.0026 | 0.1495 | Used for dozers |
| | 350 | 0.3895 | 1.9869 | 3.5050 | 0.0026 | 0.1495 | |
| Tractors/Loaders/Backhoes | 120 | 0.1083 | 0.3703 | 0.6510 | 0.0006 | 0.0595 | Used for all backhoes, excavators, loaders & ditch diggers |
| | 200 | 0.1598 | 0.4453 | 1.7937 | 0.0019 | 0.0598 | |
| | 300 | 0.2897 | 0.9591 | 3.1387 | 0.0039 | 0.1102 | |
| | 350 | 0.2897 | 0.9591 | 3.1387 | 0.0039 | 0.1102 | |
| | 500 | 0.2897 | 0.9591 | 3.1387 | 0.0039 | 0.1102 | |
| Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html) | | | | | | | |
| | HP (hp) | ROG (lb/hr) | CO (lb/hr) | NOX (lb/hr) | SOX (lb/hr) | PM (lb/hr) | |
| Helicopters | 650 | 0.3677 | 4.4054 | 4.1474 | 0.3483 | 0.5805 | Used for helicopters |
| Source: EPA 420-R-92-009 - Procedures for Emission Inventory Preparation, Volume IV, Mobile Sources, December 1992 | | | | | | | |
| - (http://www.ntl.bts.gov/docs/AQP.html - Table 5-7, Pg. 185) | | | | | | | |
| On-Road Vehicles | HP (hp) | ROG (lb/hr) | CO (lb/hr) | NOX (lb/hr) | SOX (lb/hr) | PM (lb/hr) | |
| Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour) | Composite | 0.032376 | 0.316453 | 0.033086 | 0.000323 | 0.002552 | Used 'passenger vehicle' emfac |
| Pick-Up Trucks (pounds/mile) x 30 miles/hour | Composite | 0.089781 | 0.658475 | 0.711377 | 0.00077 | 0.025682 | Used 'delivery trucks' emfac |
| Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour | Composite | 0.105474 | 0.40841 | 1.337405 | 0.001241 | 0.064691 | Used 'heavy-heavy-duty trucks' emfac |
| Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html | | | | | | | |

THIS PAGE IS INTENTIONALLY BLANK

| Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions | | | | | | | | | |
|---|--|-----------|------------------------|-------------------------|-------------------------------|------------------------------|-------------------------------|-------------------------------|--------------------------------|
| | Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
| Subtransmission Lines | | | | | | | | | |
| Survey | | | | | | | | | |
| | 1 ½-Ton Pick-Up Truck, 4X4 | 200 | 3 | 10 | 0.9 | 6.6 | 7.1 | 0.0 | 0.3 |
| | Total Survey | | | | 0.9 | 6.6 | 7.1 | 0.0 | 0.3 |
| Roads | | | | | | | | | |
| | 2 1-Ton Crew Cab, 4X4 | 300 | 10 | 2 | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| | 1 Road Grader | 350 | 10 | 10 | 2.4 | 8.8 | 23.9 | 0.0 | 0.9 |
| | 2 Track Type Dozer | 350 | 10 | 2.5 | 1.9 | 9.9 | 17.5 | 0.0 | 0.7 |
| | 1 Water Truck | 350 | 10 | 10 | 1.1 | 4.1 | 13.4 | 0.0 | 0.6 |
| | Total Roads | | | | 5.5 | 24.1 | 54.9 | 0.0 | 2.3 |
| Pole Framing and Setting | | | | | | | | | |
| | 2 ¾-Ton Suburban | 300 | 147 | 10 | 0.6 | 6.3 | 0.7 | 0.0 | 0.1 |
| | 2 5-Ton Framing Truck, 4X4 | 350 | 83 | 10 | 2.1 | 8.2 | 26.7 | 0.0 | 1.3 |
| | 2 30-Ton Line Truck | 350 | 83 | 10 | 2.1 | 8.2 | 26.7 | 0.0 | 1.3 |
| | 1 Digger Truck | 500 | 24 | 10 | 1.1 | 4.1 | 13.4 | 0.0 | 0.6 |
| | 1 Water Truck | 350 | 83 | 10 | 1.1 | 4.1 | 13.4 | 0.0 | 0.6 |
| | 2 Backhoe | 350 | 147 | 10 | 5.8 | 19.2 | 62.8 | 0.1 | 2.2 |
| | 2 Bucket Truck | 350 | 147 | 10 | 2.1 | 8.5 | 27.3 | 0.0 | 1.0 |
| | 2 Truck Mounted Crane | 350 | 147 | 10 | 2.1 | 8.2 | 26.7 | 0.0 | 1.3 |
| | 1 30-Ton Crane | 500 | 14 | 10 | 2.0 | 7.8 | 19.9 | 0.0 | 0.8 |
| | 1 Cement Truck | 350 | 3 | 10 | 1.1 | 4.1 | 13.4 | 0.0 | 0.6 |
| | Total Pole Framing and Setting | | | | 20.1 | 78.5 | 230.9 | 0.2 | 9.8 |
| Material Delivery | | | | | | | | | |
| | 2 60-Foot Flat-Bed Pole Truck | 350 | 5 | 8 | 1.7 | 6.5 | 21.4 | 0.0 | 1.0 |
| | 1 Forklift | 200 | 5 | 8 | 0.6 | 1.5 | 6.7 | 0.0 | 0.2 |
| | Total Material Delivery | | | | 2.3 | 8.0 | 28.1 | 0.0 | 1.2 |
| Conductor Installation | | | | | | | | | |
| | 1 Flat-Bed Truck & Trailer (Wire Puller) | 300 | 24 | 6 | 0.6 | 2.5 | 8.0 | 0.0 | 0.4 |
| | 1 Flat-Bed Truck & Trailer (Wire Dolly) | 300 | 24 | 6 | 0.6 | 2.5 | 8.0 | 0.0 | 0.4 |
| | 2 30-Ton Line Truck | 300 | 24 | 5 | 1.1 | 4.1 | 13.4 | 0.0 | 0.6 |
| | 2 ¾-Ton Suburban | 300 | 14 | 10 | 0.6 | 6.3 | 0.7 | 0.0 | 0.1 |
| | 1 Water Truck | 350 | 24 | 10 | 1.1 | 4.1 | 13.4 | 0.0 | 0.6 |
| | 2 Bucket Truck | 350 | 24 | 6 | 1.3 | 4.9 | 16.0 | 0.0 | 0.8 |
| | 2 Truck Mounted Crane | 350 | 24 | 6 | 1.3 | 4.9 | 16.0 | 0.0 | 0.8 |
| | Total Conductor Installation | | | | 6.6 | 29.2 | 75.6 | 0.1 | 3.7 |
| Restoration | | | | | | | | | |
| | 2 1-Ton Crew Cab, 4X4 | 300 | 40 | 8 | 0.5 | 5.1 | 0.5 | 0.0 | 0.0 |
| | 1 Water Truck | 350 | 40 | 8 | 0.8 | 3.3 | 10.7 | 0.0 | 0.5 |
| | Total Restoration | | | | 1.4 | 8.3 | 11.2 | 0.0 | 0.6 |

| Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions | | | | | | | | |
|---|-----------|-----------------|------------------|------------------------|-----------------------|------------------------|------------------------|-------------------------|
| Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
| Maximum Daily Emissions From Subtransmission Line Construction | | | | 20.1 | 78.5 | 230.9 | 0.2 | 9.8 |
| Mirage Substation | | | | | | | | |
| Civil | | | | | | | | |
| 1 Driller | Composite | 50 | 8 | 1.0 | 4.2 | 10.7 | 0.0 | 0.5 |
| 2 Crew Truck | Composite | 80 | 2 | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| 1 14-Ton Crane | Composite | 25 | 4 | 0.7 | 2.4 | 6.4 | 0.0 | 0.3 |
| 1 Dump Truck | Composite | 75 | 6 | 0.6 | 2.5 | 8.0 | 0.0 | 0.4 |
| 1 Tractor | Composite | 75 | 6 | 0.7 | 2.4 | 4.6 | 0.0 | 0.4 |
| 1 5-Ton Truck | Composite | 15 | 4 | 0.4 | 1.6 | 5.3 | 0.0 | 0.3 |
| 1 Forklift | Composite | 75 | 4 | 0.3 | 1.0 | 2.4 | 0.0 | 0.1 |
| 1 Ditch Digger | Composite | 55 | 6 | 1.0 | 3.5 | 7.9 | 0.0 | 0.4 |
| Total Civil | | | | 5.0 | 18.9 | 45.7 | 0.0 | 2.3 |
| Electrical | | | | | | | | |
| 2 Manlift | Composite | 100 | 6 | 0.9 | 2.6 | 4.7 | 0.0 | 0.3 |
| 1 Pick-Up Truck | Composite | 110 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| 1 14-Ton Crane Truck | Composite | 90 | 6 | 0.6 | 2.5 | 8.0 | 0.0 | 0.4 |
| 2 Crew Truck | Composite | 110 | 2 | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| 1 150-Ton Crane | Composite | 60 | 6 | 1.1 | 3.6 | 9.7 | 0.0 | 0.4 |
| 1 5-Ton Truck | Composite | 50 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| 1 Forklift | Composite | 100 | 6 | 0.5 | 1.5 | 3.6 | 0.0 | 0.2 |
| 2 Carryall Vehicle | Composite | 110 | 2 | 0.4 | 1.6 | 5.3 | 0.0 | 0.3 |
| 1 Support Truck | Composite | 25 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| Total Electrical | | | | 4.2 | 16.0 | 38.2 | 0.0 | 1.9 |
| Transformer Installation | | | | | | | | |
| 2 Carryall Vehicle | Composite | 22 | 6 | 1.3 | 4.9 | 16.0 | 0.0 | 0.8 |
| 1 Manlift | Composite | 20 | 6 | 0.4 | 1.3 | 2.3 | 0.0 | 0.2 |
| 1 Forklift | Composite | 22 | 6 | 0.5 | 1.5 | 3.6 | 0.0 | 0.2 |
| 1 50-Ton Crane | Composite | 15 | 6 | 1.1 | 3.6 | 9.7 | 0.0 | 0.4 |
| 2 Crew Truck | Composite | 22 | 2 | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| Total Transformer Installation | | | | 3.4 | 12.5 | 31.8 | 0.0 | 1.6 |
| Maintenance | | | | | | | | |
| 1 Foreman Truck | Composite | 40 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| 1 Manlift | Composite | 40 | 6 | 0.4 | 1.3 | 2.3 | 0.0 | 0.2 |
| 2 Crew Truck | Composite | 110 | 2 | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| Total Maintenance | | | | 0.6 | 3.2 | 2.5 | 0.0 | 0.2 |
| Test | | | | | | | | |
| 1 Pick-Up Truck | Composite | 110 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| Total Test | | | | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| Total Mirage Substation | | | | 13.43 | 51.96 | 119.57 | 0.12 | 6.05 |

| Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions | | | | | | | | | |
|---|--------------------------------------|-----------|------------------------|-------------------------|-------------------------------|------------------------------|-------------------------------|-------------------------------|--------------------------------|
| | Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
| <u>Concho Substation</u> | | | | | | | | | |
| | Electrical | | | | | | | | |
| | 1 Carryall Vehicle | Composite | 34 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| | Test | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 34 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Concho Substation | | | | 0.39 | 2.13 | 4.10 | 0.00 | 0.18 |
| <u>Indian Wells Substation</u> | | | | | | | | | |
| | Electrical | | | | | | | | |
| | 1 Carryall Vehicle | Composite | 50 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| | Test | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 50 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Indian Wells Substation | | | | 0.4 | 2.1 | 4.1 | 0.0 | 0.2 |
| <u>Santa Rosa Substation</u> | | | | | | | | | |
| | Electrical | | | | | | | | |
| | 1 Carryall Vehicle | Composite | 40 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| | Test | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 40 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Santa Rosa Substation | | | | 0.4 | 2.1 | 4.1 | 0.0 | 0.2 |
| <u>Devers Substation</u> | | | | | | | | | |
| | Civil | | | | | | | | |
| | 1 Driller | Composite | 2 | 8 | 1.0 | 4.2 | 10.7 | 0.0 | 0.5 |
| | 1 Crew Truck | Composite | 5 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 Dump Truck | Composite | 5 | 6 | 0.6 | 2.5 | 8.0 | 0.0 | 0.4 |
| | 1 Tractor | Composite | 5 | 6 | 0.7 | 2.4 | 4.6 | 0.0 | 0.4 |
| | Total Civil | | | | 2.5 | 9.7 | 23.5 | 0.0 | 1.2 |
| | Electrical | | | | | | | | |
| | 1 Manlift | Composite | 45 | 6 | 0.4 | 1.3 | 2.3 | 0.0 | 0.2 |
| | 1 Pick-Up Truck | Composite | 60 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | 1 Crew Truck | Composite | 60 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 150-Ton Crane | Composite | 10 | 6 | 1.1 | 3.6 | 9.7 | 0.0 | 0.4 |
| | 1 Forklift | Composite | 40 | 6 | 0.5 | 1.5 | 3.6 | 0.0 | 0.2 |
| | 1 Carryall Vehicle | Composite | 60 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| | Total Electrical | | | | 2.4 | 9.1 | 19.7 | 0.0 | 1.0 |

| Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions | | | | | | | | | |
|---|------------------------------------|-----------|------------------------|-------------------------|-------------------------------|------------------------------|-------------------------------|-------------------------------|--------------------------------|
| | Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
| | Maintenance | | | | | | | | |
| | 1 Foreman Truck | Composite | 5 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 Crew Truck | Composite | 10 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | Total Maintenance | | | | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| | Test | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 20 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Test | | | | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Devers Substation | | | | 5.2 | 21.5 | 44.8 | 0.0 | 2.3 |
| | | | | | | | | | |
| | Eisenhower Substation | | | | | | | | |
| | Civil | | | | | | | | |
| | 1 Driller | Composite | 5 | 8 | 1.0 | 4.2 | 10.7 | 0.0 | 0.5 |
| | 1 Crew Truck | Composite | 15 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 Dump Truck | Composite | 15 | 6 | 0.6 | 2.5 | 8.0 | 0.0 | 0.4 |
| | 1 Tractor | Composite | 15 | 6 | 0.7 | 2.4 | 4.6 | 0.0 | 0.4 |
| | 1 Ditch Digger | Composite | 5 | 6 | 1.0 | 3.5 | 7.9 | 0.0 | 0.4 |
| | Total Civil | | | | 3.5 | 13.2 | 31.4 | 0.0 | 1.7 |
| | Electrical | | | | | | | | |
| | 1 Manlift | Composite | 35 | 6 | 0.4 | 1.3 | 2.3 | 0.0 | 0.2 |
| | 1 Crew Truck | Composite | 45 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 150-Ton Crane | Composite | 20 | 6 | 1.1 | 3.6 | 9.7 | 0.0 | 0.4 |
| | 1 Forklift | Composite | 45 | 6 | 0.5 | 1.5 | 3.6 | 0.0 | 0.2 |
| | 1 Carryall Vehicle | Composite | 45 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| | Total Electrical | | | | 2.3 | 7.8 | 18.3 | 0.0 | 0.9 |
| | Maintenance | | | | | | | | |
| | 1 Foreman Truck | Composite | 5 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 Crew Truck | Composite | 10 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | Total Maintenance | | | | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| | Test | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 45 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Test | | | | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Eisenhower Substation | | | | 6.1 | 23.7 | 51.3 | 0.1 | 2.6 |

| Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions | | | | | | | | | |
|---|-----------------------------------|-----------|------------------------|-------------------------|-------------------------------|------------------------------|-------------------------------|-------------------------------|--------------------------------|
| | Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
| Farrell Substation | | | | | | | | | |
| Civil | | | | | | | | | |
| | 1 Driller | Composite | 10 | 8 | 1.0 | 4.2 | 10.7 | 0.0 | 0.5 |
| | 1 Crew Truck | Composite | 20 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 Dump Truck | Composite | 20 | 6 | 0.6 | 2.5 | 8.0 | 0.0 | 0.4 |
| | 1 Tractor | Composite | 20 | 6 | 0.7 | 2.4 | 4.6 | 0.0 | 0.4 |
| | 1 Ditch Digger | Composite | 10 | 6 | 1.0 | 3.5 | 7.9 | 0.0 | 0.4 |
| | Total Civil | | | | 3.5 | 13.2 | 31.4 | 0.0 | 1.7 |
| Electrical | | | | | | | | | |
| | 1 Manlift | Composite | 40 | 6 | 0.4 | 1.3 | 2.3 | 0.0 | 0.2 |
| | 1 Crew Truck | Composite | 55 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 150-Ton Crane | Composite | 25 | 6 | 1.1 | 3.6 | 9.7 | 0.0 | 0.4 |
| | 1 Forklift | Composite | 55 | 6 | 0.5 | 1.5 | 3.6 | 0.0 | 0.2 |
| | 1 Carryall Vehicle | Composite | 55 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| | Total Electrical | | | | 2.3 | 7.8 | 18.3 | 0.0 | 0.9 |
| Maintenance | | | | | | | | | |
| | 1 Foreman Truck | Composite | 5 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 Crew Truck | Composite | 10 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | Total Maintenance | | | | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| Test | | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 55 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Test | | | | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Farrell Substation | | | | 6.1 | 23.7 | 51.3 | 0.1 | 2.6 |
| Garnet Substation | | | | | | | | | |
| Electrical | | | | | | | | | |
| | 1 Carryall Vehicle | Composite | 16 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| Test | | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 16 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Garnet Substation | | | | 0.4 | 2.1 | 4.1 | 0.0 | 0.2 |
| Thornhill Substation | | | | | | | | | |
| Electrical | | | | | | | | | |
| | 1 Carryall Vehicle | Composite | 40 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| Test | | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 40 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Thornhill Substation | | | | 0.4 | 2.1 | 4.1 | 0.0 | 0.2 |

| Table F-14. Equipment Exhaust During Subtransmission Line Construction - Exhaust Emissions | | | | | | | | | |
|--|----------------------------------|-----------|------------------------|-------------------------|-------------------------------|------------------------------|-------------------------------|-------------------------------|--------------------------------|
| | Construction | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
| Tamarisk Substation | | | | | | | | | |
| Civil | | | | | | | | | |
| | 1 Crew Truck | Composite | 5 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 Dump Truck | Composite | 5 | 6 | 0.6 | 2.5 | 8.0 | 0.0 | 0.4 |
| | 1 Tractor | Composite | 5 | 6 | 0.7 | 2.4 | 4.6 | 0.0 | 0.4 |
| | Total Civil | | | | 1.4 | 5.5 | 12.7 | 0.0 | 0.8 |
| Electrical | | | | | | | | | |
| | 1 Manlift | Composite | 5 | 6 | 0.4 | 1.3 | 2.3 | 0.0 | 0.2 |
| | 1 Pick-Up Truck | Composite | 40 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | 1 Crew Truck | Composite | 40 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 1 150-Ton Crane | Composite | 2 | 6 | 1.1 | 3.6 | 9.7 | 0.0 | 0.4 |
| | 1 Forklift | Composite | 5 | 6 | 0.5 | 1.5 | 3.6 | 0.0 | 0.2 |
| | 1 Carryall Vehicle | Composite | 40 | 2 | 0.2 | 0.8 | 2.7 | 0.0 | 0.1 |
| | Total Electrical | | | | 2.4 | 9.1 | 19.7 | 0.0 | 1.0 |
| Maintenance | | | | | | | | | |
| | 1 Foreman Truck | Composite | 1 | 2 | 0.1 | 0.6 | 0.1 | 0.0 | 0.0 |
| | 2 Crew Truck | Composite | 2 | 2 | 0.1 | 1.3 | 0.1 | 0.0 | 0.0 |
| | Total Maintenance | | | | 0.2 | 1.9 | 0.2 | 0.0 | 0.0 |
| Test | | | | | | | | | |
| | 1 Pick-Up Truck | Composite | 30 | 2 | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Test | | | | 0.2 | 1.3 | 1.4 | 0.0 | 0.1 |
| | Total Tamarisk Substation | | | | 4.2 | 17.9 | 34.1 | 0.0 | 1.8 |
| Note: Each simultaneous construction phase is calculated separately. Maximum daily emissions are for each construction segment are the maximum daily simultaneous emissions and are bold, italicized, and underlined. | | | | | | | | | |

Table F-15. Subtransmission Line Emission Factors

| Off-Road Construction Equipment | | Emission Factors | | | | | Notes: | |
|--|--------------------|-------------------------|------------------------|------------------------|------------------------|------------------------|--|--|
| | HP (hp) | ROG (lb/hr) | CO (lb/hr) | NOX (lb/hr) | SOX (lb/hr) | PM (lb/hr) | | |
| Aerial Lifts | Composite | 0.0746 | 0.2200 | 0.3885 | 0.0004 | 0.0269 | Used for manlifts | |
| Bore/Drill Rigs | Composite | 0.1295 | 0.5281 | 1.3416 | 0.0017 | 0.0591 | Used for drillers, and sleeve rigs | |
| | 500 | 0.2012 | 0.7762 | 1.9878 | 0.0018 | 0.0771 | | |
| Cranes | Composite | 0.1778 | 0.6011 | 1.6100 | 0.0014 | 0.0715 | Used for all cranes | |
| Excavators | Composite | 0.1695 | 0.5828 | 1.3249 | 0.0013 | 0.0727 | Used for excavators and ditch diggers | |
| | 200 | 0.0716 | 0.1822 | 0.8315 | 0.0009 | 0.0254 | | |
| Forklifts | Composite | 0.0799 | 0.2422 | 0.5982 | 0.0006 | 0.0324 | Used for forklifts | |
| Graders | 350 | 0.2360 | 0.8828 | 2.3908 | 0.0023 | 0.0904 | Used for graders | |
| Off-Highway Trucks | Composite | 0.2730 | 0.8499 | 2.7256 | 0.0027 | 0.0989 | Used for all diesel trucks & carryall vehicles | |
| Other Material Handling Equipment | Composite | 0.1952 | 0.6041 | 1.7655 | 0.0015 | 0.0786 | Used for cable puller & conductor tensioner | |
| Other Construction Equipment | Composite | 0.1215 | 0.4504 | 1.1575 | 0.0013 | 0.0503 | Used for cable dollies | |
| Rubber-Tired Dozers | 350 | 0.3895 | 1.9869 | 3.5050 | 0.0026 | 0.1495 | Used for dozers | |
| | 350 | 0.2897 | 0.9591 | 3.1387 | 0.0039 | 0.1102 | | |
| Tractors/Loaders/Backhoes | Composite | 0.1204 | 0.4063 | 0.7746 | 0.0008 | 0.0599 | Used for all backhoes & ditch diggers | |
| Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html) | | | | | | | | |
| On-Road Vehicles | | HP (hp) | ROG (lb/hr) | CO (lb/hr) | NOX (lb/hr) | SOX (lb/hr) | PM (lb/hr) | |
| Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour) | Composite | 0.032376 | 0.316453 | 0.033086 | 0.000323 | 0.002552 | Used 'passenger vehicle' emfac | |
| Pickup Trucks (pounds/mile) x 30 miles/hour | Composite | 0.089781 | 0.658475 | 0.711377 | 0.00077 | 0.025682 | Used 'delivery trucks' emfac | |
| Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour | Composite | 0.105474 | 0.40841 | 1.337405 | 0.001241 | 0.064691 | Used 'heavy-heavy-duty trucks' emfac | |
| Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html | | | | | | | | |

THIS PAGE IS INTENTIONALLY BLANK

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

| Construction Phase | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) | |
|-----------------------------------|----------------|-----------------|------------------|------------------------|-----------------------|------------------------|------------------------|-------------------------|-------------|
| Mirage-Santa Rosa | | | | | | | | | |
| Cable Construction | | | | | | | | | |
| 2 | Bucket Truck | Composite | 5 | 8 | 1.7 | 6.5 | 21.4 | 0.0 | 1.0 |
| 1 | Pick-Up | Composite | 5 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| 1 | 2-Axle Trailer | Composite | 5 | 8 | 1.6 | 4.8 | 14.1 | 0.0 | 0.6 |
| Total Cable Construction | | | | | 3.3 | 11.5 | 35.7 | 0.0 | 1.7 |
| Receive and Loadout | | | | | | | | | |
| 1 | 5-Ton Forklift | Composite | 1 | 8 | 0.6 | 1.9 | 4.8 | 0.0 | 0.3 |
| 1 | Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Receive and Loadout | | | | | 0.7 | 2.1 | 5.0 | 0.0 | 0.3 |
| Clean-Up | | | | | | | | | |
| 2 | Bucket Truck | Composite | 1 | 8 | 1.7 | 6.5 | 21.4 | 0.0 | 1.0 |
| 1 | Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | | 1.7 | 6.7 | 21.6 | 0.0 | 1.0 |
| Total Mirage Santa Rosa | | | | | 5.65 | 20.37 | 62.28 | 0.06 | 2.98 |
| Farrell-Garnet | | | | | | | | | |
| Cable Construction | | | | | | | | | |
| 2 | Bucket Truck | Composite | 18 | 8 | 1.7 | 6.5 | 21.4 | 0.0 | 1.0 |
| 1 | Pick-Up | Composite | 18 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| 1 | 2-Axle Trailer | Composite | 18 | 8 | 1.6 | 4.8 | 14.1 | 0.0 | 0.6 |
| Total Cable Construction | | | | | 3.3 | 11.5 | 35.7 | 0.0 | 1.7 |
| Receive and Loadout | | | | | | | | | |
| 1 | 5-Ton Forklift | Composite | 1 | 8 | 0.6 | 1.9 | 4.8 | 0.0 | 0.3 |
| 1 | Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Receive and Loadout | | | | | 0.7 | 2.1 | 5.0 | 0.0 | 0.3 |
| Clean-Up | | | | | | | | | |
| 2 | Bucket Truck | Composite | 1 | 8 | 1.7 | 6.5 | 21.4 | 0.0 | 1.0 |
| 1 | Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | | 1.7 | 6.7 | 21.6 | 0.0 | 1.0 |
| Total Farrel Garnet | | | | | 5.65 | 20.37 | 62.28 | 0.06 | 2.98 |
| Devers | | | | | | | | | |
| Equipment Installation | | | | | | | | | |
| 2 | Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Cable Construction | | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | | |
| 2 | Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Circuit Installation | | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

| Construction Phase | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
|-----------------------------------|-----------|-----------------|------------------|------------------------|-----------------------|------------------------|------------------------|-------------------------|
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Devers | | | | 0.12 | 0.88 | 0.95 | 0.00 | 0.03 |
| Mirage | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Mirage | | | | 0.12 | 0.88 | 0.95 | 0.00 | 0.03 |
| Tamarisk | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Tamarisk | | | | 0.12 | 0.88 | 0.95 | 0.00 | 0.03 |
| Eisenhower | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Eisenhower | | | | 0.12 | 0.88 | 0.95 | 0.00 | 0.03 |

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

| Construction Phase | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
|-----------------------------------|-----------|-----------------|------------------|------------------------|-----------------------|------------------------|------------------------|-------------------------|
| Concho | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Concho | | | | 0.12 | 0.88 | 0.95 | 0.00 | 0.03 |
| Indian Wells | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Indian Wells | | | | 0.12 | 0.88 | 0.95 | 0.00 | 0.03 |
| Santa Rosa | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.4 | 0.4 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Santa Rosa | | | | 0.12 | 0.88 | 0.95 | 0.00 | 0.03 |

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

| Construction Phase | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
|-----------------------------------|-----------|-----------------|------------------|------------------------|-----------------------|------------------------|------------------------|-------------------------|
| Thornhill | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Thornhill | | | | 0.07 | 0.53 | 0.57 | 0.00 | 0.02 |
| Garnet | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 1 Pick-up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Garnet | | | | 0.07 | 0.53 | 0.57 | 0.00 | 0.02 |
| Farrell | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Farrell | | | | 0.07 | 0.53 | 0.57 | 0.00 | 0.02 |

Table F-16. Equipment Exhaust During Telecommunication Construction - Exhaust Emissions

| Construction Phase | HP | Duration (days) | Usage (hour/day) | ROG Emissions (lb/day) | CO Emissions (lb/day) | NOX Emissions (lb/day) | SOX Emissions (lb/day) | PM10 Emissions (lb/day) |
|--|-----------|-----------------|------------------|------------------------|-----------------------|------------------------|------------------------|-------------------------|
| EDOM Hill | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total EDOM Hills | | | | 0.07 | 0.53 | 0.57 | 0.00 | 0.02 |
| Palm Springs | | | | | | | | |
| Equipment Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Cable Construction | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Circuit Installation | | | | | | | | |
| 1 Pick-Up | Composite | 6 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Circuit Installation | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Clean-Up | | | | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Clean-Up | | | | 0.0 | 0.2 | 0.2 | 0.0 | 0.0 |
| Total Palm Springs | | | | 0.07 | 0.53 | 0.57 | 0.00 | 0.02 |
| MAX DAILY EMISSIONS DURING CONSTRUCTION | | | | 5.6 | 20.4 | 62.3 | 0.1 | 3.0 |

Note: Each simultaneous construction phase is calculated separately. Maximum daily emissions are for each construction segment are the maximum daily simultaneous emissions and are bold, italicized, and underlined. Annual emissions are the sum of all construction phases.

THIS PAGE IS INTENTIONALLY BLANK

Table F-17. Telecommunication Equipment Emission Factors

| Off-Road Construction Equipment | Emission Factors | | | | | | Notes: |
|--|------------------|----------------|---------------|----------------|----------------|---------------|--|
| | HP (hp) | ROG (lb/hr) | CO (lb/hr) | NOX (lb/hr) | SOX (lb/hr) | PM (lb/hr) | |
| Forklifts | Composite | 0.0799 | 0.2422 | 0.5982 | 0.0006 | 0.0324 | Used for forklifts |
| Off-Highway Trucks | Composite | 0.2730 | 0.8499 | 2.7256 | 0.0027 | 0.0989 | Used for all diesel trucks & carryall vehicles |
| Other Material Handling Equipment | Composite | 0.1952 | 0.6041 | 1.7655 | 0.0015 | 0.0786 | Used for cable puller & conductor tensioner |
| Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html) | | | | | | | |
| On-Road Vehicles | Emission Factors | | | | | | Notes: |
| | HP (hp) | ROG (lb/hr) | CO (lb/hr) | NOX (lb/hr) | SOX (lb/hr) | PM (lb/hr) | |
| Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour) | Composite | 0.001079 | 0.010548 | 0.001103 | 1.08E-05 | 0.000085 | Used 'passenger vehicle' emfac |
| Pickup Trucks (pounds/mile) x 30 miles/hour | Composite | 0.002993 | 0.021949 | 0.023713 | 2.57E-05 | 0.000856 | Used 'delivery trucks' emfac |
| Heavy Duty Trucks and Truck-Mounted Equipment (pounds/miles) x 30 miles/hour | Composite | 0.105474 | 0.40841 | 1.337405 | 0.001241 | 0.064691 | Used 'heavy-heavy-duty trucks' emfac |
| Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html | | | | | | | |

THIS PAGE IS INTENTIONALLY BLANK

Table F-18. Maximum Project CO2 Emissions Summary

| Construction Phase | Maximum Emissions (tons/project) | |
|--|----------------------------------|---------|
| | CO2 | |
| <i>Transmission Line Loop-In¹</i> | | |
| On-Site Vehicle Exhaust | | 356.27 |
| Employee Vehicles | | 19.31 |
| Total | | 375.58 |
| <i>Subtransmission Line²</i> | | |
| On-Site Vehicle Exhaust | | 1377.29 |
| Employee Vehicles | | 141.32 |
| Total | | 1518.62 |
| <i>Devers Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 36.03 |
| Employee Vehicles | | 12.05 |
| Total | | 48.09 |
| <i>Mirage Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 319.04 |
| Employee Vehicles | | 128.29 |
| Total | | 447.33 |
| <i>Concho Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 7.07 |
| Employee Vehicles | | 3.72 |
| Total | | 10.79 |
| <i>Indian Wells Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 10.40 |
| Employee Vehicles | | 5.48 |
| Total | | 15.87 |
| <i>Santa Rosa Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 8.32 |
| Employee Vehicles | | 4.38 |
| Total | | 12.70 |
| <i>Eisenhower Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 44.32 |
| Employee Vehicles | | 12.05 |
| Total | | 56.37 |
| <i>Farrell Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 58.97 |
| Employee Vehicles | | 15.89 |
| Total | | 74.85 |

Table F-18. Maximum Project CO2 Emissions Summary

| Construction Phase | Maximum Emissions (tons/project) | |
|--|----------------------------------|----------------|
| | CO2 | |
| <i>Garnet Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 3.33 |
| Employee Vehicles | | 1.75 |
| Total | | 5.08 |
| <i>Thornhill Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 8.32 |
| Employee Vehicles | | 4.38 |
| Total | | 12.70 |
| <i>Tamarisk Substation Construction</i> | | |
| On-Site Vehicle Exhaust | | 17.42 |
| Employee Vehicles | | 14.05 |
| Total | | 31.47 |
| <i>Telecommunications Line</i> | | |
| On-Site Vehicle Exhaust | | 125.82 |
| Employee Vehicles | | 14.05 |
| Total | | 139.87 |
| Project Total Emissions | | 2749.31 |

Table F-19. Employee Vehicle - CO2 Exhaust Emissions

Employee Vehicle Emissions

| | |
|--|--------------------|
| Emission Factors from SCAQMD Highest (Most Conservative) EMFAC 2007 Emission Factors for On-Road Passenger Vehicles and Delivery Trucks | |
| E=F* VMT* DAYS/2000 | |
| F = Emission factor per passenger vehicle (lb/VMT) | |
| VMT = Vehicle Miles Traveled | |
| VMT per employee = | 50 miles (assumed) |
| DAYS = Employee-days traveling to/from project | |
| E = Emissions tons/project | |
| Emission Factors for 2008 (lb/VMT) | |
| CO2 = | 1.09553 |

Emission Summary

| Construction Phase | Employee-days per project* | CO2 (tons/project) |
|---------------------------|----------------------------|--------------------|
| Transmission Line Loop-In | 705 | 19.31 |
| Subtransmission Lines | 5160 | 141.32 |
| Devers Substation | 440 | 12.05 |
| Mirage Substation | 4684 | 128.29 |
| Concho Substation | 136 | 3.72 |
| Indian Wells Substation | 200 | 5.48 |
| Santa Rosa Substation | 160 | 4.38 |
| Eisenhower Substation | 440 | 12.05 |
| Farrell Substation | 580 | 15.89 |
| Garnet Substation | 64 | 1.75 |
| Thornhill Substation | 160 | 4.38 |
| Tamarisk Substation | 195 | 5.34 |
| Telecommunication | 513 | 14.05 |
| Total Emissions | | 368.02 |

* Computed by calculating the person-days for each activity with the construction phase and summing over all activities.

| Table F-20. Subtransmission Line Construction - Route Details | | |
|---|-------------------------|----------------|
| Route | Distance (Miles) | |
| | Paved | Unpaved |
| Farrell-Garnet (Alternative Route 1) Starting from Devers Substation | 6.00 | 2.33 |
| Farrell-Garnet (Alternative Route 2) Starting from Devers Substation | 4.60 | 4.77 |
| Farrell-Garnet (Alternative Route 3) Starting from Devers Substation | 7.00 | 2.33 |
| Devers Coachella Loo Starting from Mirage Substation | 0.00 | 0.95 |
| Mirage-Santa Rosa (Alternative Route 1) Starting from Mirage Substation | 0.00 | 1.42 |
| Mirage-Santa Rosa (Alternative Route 2) Starting from Mirage Substation | 2.93 | 0.00 |
| Bob Hope Dr. & Dinah Shore Dr. Substation Line Reconfiguration (Alternative Route 1) Starting from Mirage Substation | 2.67 | 1.42 |
| Bob Hope Dr. & Dinah Shore Dr. Substation Line Reconfiguration (Alternative Route 2) Starting from Mirage Substation | 2.77 | 0.00 |
| Gerald Ford Dr. & Portola Ave. Substation Line Reconfiguration (Alternative Route 1) Starting from Mirage Substation | 0.00 | 2.02 |
| Gerald Ford Dr. & Portola Ave. Substation Line Reconfiguration (Alternative Route 2) Starting from Mirage Substation | 2.97 | 0.57 |
| Notes | | |
| 1. Based on detailed map of the area. Distances are approximate. | | |

Table F-21. Equipment Exhaust During Transmission Line Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (pounds/day) | CO2 Emissions (tons/project) |
|---------------------------------------|-----|-----------------|------------------|----------------------------|------------------------------|
| TRANSMISSION LINE LOOP-IN | | | | | |
| <u>Survey</u> | | | | | |
| - 2 ½-Ton Pick-Up | 200 | 3 | 8 | 1305.3 | 2.0 |
| - Total Survey | | | | 1305.3 | 2.0 |
| <u>Marshalling Yards</u> | | | | | |
| - 1 1-Ton Crew Cab | 300 | 85 | 2 | 66.0 | 2.8 |
| - 1 30-Ton Crane | 300 | 85 | 2 | 360.2 | 15.3 |
| - 10,000-Pound Rough-Terrain | | | | | |
| - 2 Forklift | 200 | 85 | 5 | 771.0 | 32.8 |
| - 1 Truck, Semi-Tractor | 350 | 85 | 1 | 126.3 | 5.4 |
| - Total Marshalling Yards | | | | 1323.5 | 56.2 |
| <u>Roads and Landing Work</u> | | | | | |
| - 1 1-Ton Crew Cab | 300 | 3 | 5 | 164.9 | 0.2 |
| - 1 Road Grader | 350 | 3 | 6 | 1377.0 | 2.1 |
| - 1 Track-Type Dozer | 350 | 3 | 6 | 1589.4 | 2.4 |
| - 1 Drum-Type Compactor | 250 | 3 | 6 | 1467.0 | 2.2 |
| - 3 Water Truck | 350 | 3 | 10 | 3789.6 | 5.7 |
| - 1 Lowboy Truck & Trailer | 250 | 3 | 4 | 505.3 | 0.8 |
| - 1 Excavator | 300 | 3 | 6 | 1402.2 | 2.1 |
| - 1 Front End Loader | 350 | 3 | 6 | 2069.4 | 3.1 |
| - Total Roads and Landing Work | | | | 12364.8 | 18.5 |
| <u>Install Foundations</u> | | | | | |
| - 4 1-Ton Crew Cab | 300 | 17 | 6 | 791.7 | 6.7 |
| - 2 30-Ton Crane | 300 | 17 | 5 | 1801.0 | 15.3 |
| - 1 Front End Loader | 200 | 17 | 5 | 858.5 | 7.3 |
| - 2 Digger | 500 | 17 | 8 | 5518.4 | 46.9 |

Table F-21. Equipment Exhaust During Transmission Line Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (pounds/day) | CO2 Emissions (tons/project) |
|--|-----------|------------------------|-------------------------|-----------------------------------|-------------------------------------|
| - 2 4,000 Gallon Water Truck | 350 | 17 | 5 | 1263.2 | 10.7 |
| - 6 Concrete Mixer Truck | 425 | 17 | 5 | 3789.6 | 32.2 |
| - Total Install Foundations | | | | 14022.37 | 119.19 |
| <u>Tower Legs Haul and Erect</u> | | | | | |
| - 1 Ton Crew Cab | 300 | 4 | 6 | 197.9 | 0.4 |
| - 1 30-Ton Crane Truck | 300 | 4 | 8 | 1010.6 | 2.0 |
| - 10,000-Pound Rough-Terrain | | | | | |
| - 1 Forklift | 200 | 4 | 6 | 462.6 | 0.9 |
| - 1 Truck & Trailer | 350 | 4 | 5 | 631.6 | 1.3 |
| - 10,000-Pound Rough-Terrain | | | | | |
| - 1 Forklift | 200 | 5 | 8 | 616.8 | 1.5 |
| - 2 Truck & Trailer | 350 | 5 | 10 | 2526.4 | 6.3 |
| - Total Tower Legs Haul and Erect | | | | 5445.88 | 12.46 |
| <u>Tower Assembly</u> | | | | | |
| - 2 Rough-Terrain Crane | 400 | 8 | 8 | 2881.6 | 11.5 |
| - 2 Crane Truck | 300 | 8 | 8 | 2021.1 | 8.1 |
| - 2 Rough-Terrain Fork Lift | 200 | 8 | 5 | 771.0 | 3.1 |
| - 3 Pick-Up Truck | 300 | 8 | 10 | 2447.5 | 9.8 |
| - 4 Crew Cab Flat-Bed | 300 | 8 | 5 | 659.7 | 2.6 |
| - 2 Compressor Truck | 350 | 8 | 5 | 1263.2 | 5.1 |
| - Total Tower Assembly | | | | 10044.13 | 40.18 |

Table F-21. Equipment Exhaust During Transmission Line Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (pounds/day) | CO2 Emissions (tons/project) |
|--------------------------------------|-----------|------------------------|-------------------------|-----------------------------------|-------------------------------------|
| <u>Tower TSP Erection</u> | | | | | |
| - 1 Pick-Up Truck | 300 | 8 | 5 | 407.9 | 1.6 |
| - 2 Crew Cab Flat-Bed | 300 | 8 | 5 | 329.9 | 1.3 |
| - 1 Compressor Truck | 350 | 8 | 5 | 631.6 | 2.5 |
| - 1 Rough-Terrain Crane | 500 | 8 | 6 | 1080.6 | 4.3 |
| - Total Tower TSP Erection | | | | 2450.0 | 9.8 |
| <u>Tower Removal</u> | | | | | |
| - 1 Pick-Up Truck | 300 | 4 | 8 | 652.7 | 1.3 |
| - 1 Flat-Bed Truck | 350 | 4 | 8 | 263.9 | 0.5 |
| - Total Tower Removal | | | | 916.6 | 1.8 |
| <u>Conductor Installation</u> | | | | | |
| - 3 Crew Cab Flat-Bed Bed | 300 | 10 | 8 | 791.7 | 4.0 |
| - 2 Wire Truck & Trailer | 350 | 6 | 2 | 505.3 | 1.5 |
| - 1 Dump Truck (Trash) | 350 | 10 | 2 | 252.6 | 1.3 |
| - 1 Pick-Up Truck | 300 | 10 | 10 | 815.8 | 4.1 |
| - 2 Manitex | 350 | 10 | 6 | 3050.4 | 15.3 |
| - 1 Manitex | 350 | 10 | 8 | 2033.6 | 10.2 |
| - 2 Sleeving Rigs | 350 | 10 | 2 | 1245.2 | 6.2 |
| - 1 Log Truck & Trailer | 500 | 10 | 2 | 252.6 | 1.3 |
| - 1 Rough-Terrain Fork Lift | 350 | 10 | 2 | 154.2 | 0.8 |
| - 1 580 Case Backhoe | 120 | 6 | 2 | 103.4 | 0.3 |
| - 4 Spacing Cart | 10 | 6 | 4 | 161.6 | 0.5 |
| - 1 Static Truck | 350 | 6 | 2 | 252.6 | 0.8 |
| - 1 Static Tensioner | 0 | 6 | 2 | 20.2 | 0.1 |
| - 2 3-Drum Strawline Puller | 300 | 6 | 4 | 2033.6 | 6.1 |
| - 1 60lk Puller | 525 | 6 | 3 | 762.6 | 2.3 |
| - 1 Sag Cat with 2 Winches | 350 | 6 | 2 | 508.4 | 1.5 |

Table F-21. Equipment Exhaust During Transmission Line Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (pounds/day) | CO2 Emissions (tons/project) |
|--|-----------|----------------------------|-----------------------------|---|---|
| - 4 D8 Cat | 300 | 6 | 1 | 1379.6 | 4.1 |
| - 1 Hughes 500 E Helicopter | 650 | 3 | 4 | 6343.8 | 9.5 |
| - 1 Fuel, Helicopter Support Truck | 300 | 3 | 2 | 252.6 | 0.4 |
| - 1 Lowboy Truck & Trailer | 500 | 10 | 2 | 252.6 | 1.3 |
| Total Conductor Installation | | | | 21172.6 | 71.3 |
| Restoration | | | | | |
| - 1 Crew Cab | 300 | 4 | 5 | 164.9 | 0.3 |
| - 1 Road Grader | 350 | 4 | 6 | 1377.0 | 2.8 |
| - 1 Track-Type Dozer | 350 | 4 | 6 | 1589.4 | 3.2 |
| - 1 Drum-Type Compactor | 250 | 4 | 6 | 1467.0 | 2.9 |
| - 3 Water Truck | 350 | 4 | 10 | 3789.6 | 7.6 |
| - 1 Lowboy Truck & Trailer | 500 | 4 | 4 | 505.3 | 1.0 |
| - 1 Front End Loader | 350 | 4 | 6 | 2069.4 | 4.1 |
| - 1 Excavator | 300 | 4 | 6 | 1402.2 | 2.8 |
| Total Restoration | | | | 12364.8 | 24.7 |
| Maximum Daily Emissions from Transmission Line Construction | | | | | 356.3 |

Table F-22. Transmission Line Emission Factors

| Off-Road Construction Equipment | | Emission Factor | | Notes: |
|---|--------------------|------------------------|------------------------|--|
| | HP (hp) | CO2 (lb/hr) | | |
| Bore/Drill Rigs | 350 | 311.3000 | | Used for drillers and sleeve rigs |
| Crushers/Process Equipment | 250 | 244.5000 | | Used for compactors |
| | 300 | 180.1000 | | |
| | 400 | 180.1000 | | |
| Cranes | 500 | 180.1000 | | Used for cranes |
| Excavators | 300 | 233.7000 | | Used for excavators |
| | 200 | 77.1000 | | |
| Forklifts | 350 | 77.1000 | | Used for forklifts |
| Graders | 350 | 229.5000 | | Used for graders |
| | 0 | 10.1000 | | |
| | 10 | 10.1000 | | |
| | 300 | 254.2000 | | |
| | 350 | 254.2000 | | |
| Other Construction Equipment | 525 | 254.2000 | | Used for manitex, spacing carts, pullers, and tensioners |
| Other General Industrial Equipment | 650 | 0.1724 | | |
| | 300 | 264.9000 | | |
| Rubber-Tired Dozers | 350 | 264.9000 | | Used for dozers |
| | 120 | 51.7000 | | |
| | 200 | 171.7000 | | |
| | 300 | 344.9000 | | |
| | 350 | 344.9000 | | |
| Tractors/Loaders/Backhoes | 500 | 344.9000 | | Used for all backhoes, excavators, loaders & ditch diggers |
| Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html) | | | | |
| | HP (hp) | CO2 (lb/hr) | | |
| Helicopters | 650 | 1585.9440 | | Used for helicopters - No emission factor, estimated by assuming a 360 times factor of the CO emission factor. |
| Source: EPA 420-R-92-009 - Procedures for Emission Inventory Preparation, Volume IV, Mobile Sources, December 1992 - (http://www.ntl.bts.gov/docs/AQP.html - Table 5-7, Pg. 185) | | | | |
| On-Road Vehicles | | HP (hp) | CO2 (lb/hr) | |
| Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour) | Composite | 32.985968 | | Used 'passenger vehicle' emfac |
| Pick-Up Trucks (pounds/mile) x 30 miles/hour | Composite | 81.58302 | | Used 'delivery trucks' emfac |
| Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour | Composite | 126.32014 | | Used 'heavy-heavy-duty trucks' emfac |
| Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html | | | | |

THIS PAGE IS INTENTIONALLY BLANK

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|---|-----|-----------------|------------------|------------------------|------------------------------|
| Subtransmission Lines | | | | | |
| Survey | | | | | |
| - 1 ½-Ton Pick-Up Truck 4X4 | 200 | 3 | 10 | 815.8 | 1.2 |
| - Total Survey | | | | 815.8 | 1.2 |
| Roads | | | | | |
| - 2 1-Ton Crew Cab 4X4 | 300 | 10 | 2 | 131.9 | 0.7 |
| - 1 Road Grader | 350 | 10 | 10 | 2295.0 | 11.5 |
| - 2 Track-Type Dozer | 350 | 10 | 2.5 | 1324.5 | 6.6 |
| - 1 Water Truck | 350 | 10 | 10 | 1263.2 | 6.3 |
| - Total Roads | | | | 5014.6 | 25.1 |
| Pole Framing and Setting | | | | | |
| - 2 ¾-Ton Suburban | 300 | 147 | 10 | 659.7 | 48.5 |
| - 2 5-Ton Framing Truck 4X4 | 350 | 83 | 10 | 2526.4 | 104.8 |
| - 2 30-Ton line Truck | 350 | 83 | 10 | 2526.4 | 104.8 |
| - 1 Digger Truck | 500 | 24 | 10 | 1263.2 | 15.2 |
| - 1 Water Truck | 350 | 83 | 10 | 1263.2 | 52.4 |
| - 2 Backhoe | 350 | 147 | 10 | 6898.0 | 507.0 |
| - 2 Bucket Truck | 350 | 147 | 10 | 2601.0 | 191.2 |
| - 2 Truck-Mounted Crane | 350 | 147 | 10 | 2526.4 | 185.7 |
| - 1 30-Ton Crane | 500 | 14 | 10 | 1801.0 | 12.6 |
| - 1 Cement Truck | 350 | 3 | 10 | 1263.2 | 1.9 |
| - Total Pole Framing and Setting | | | | 23328.5 | 1224.1 |

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|---|-----------|-----------------|------------------|------------------------|------------------------------|
| Material Delivery | | | | | |
| 2 60-Foot Flat-Bed Pole Truck | 350 | 5 | 8 | 2021.1 | 5.1 |
| 1 Forklift | 200 | 5 | 8 | 616.8 | 1.5 |
| Total Material Delivery | | | | 2637.9 | 6.6 |
| Conductor Installation | | | | | |
| 1 Flat-Bed Truck & Trailer (Wire Puller) | 300 | 24 | 6 | 757.9 | 9.1 |
| 1 Flat-Bed Truck & Trailer (Wire Dolly) | 300 | 24 | 6 | 757.9 | 9.1 |
| 2 30-Ton line Truck | 300 | 24 | 5 | 1263.2 | 15.2 |
| 2 ¾-Ton Suburban | 300 | 14 | 10 | 659.7 | 4.6 |
| 1 Water Truck | 350 | 24 | 10 | 1263.2 | 15.2 |
| 2 Bucket Truck | 350 | 24 | 6 | 1515.8 | 18.2 |
| 2 Truck-Mounted Crane | 350 | 24 | 6 | 1515.8 | 18.2 |
| Total Conductor Installation | | | | 7733.6 | 89.5 |
| Restoration | | | | | |
| 2 1-Ton Crew Cab 4X4 | 300 | 40 | 8 | 527.8 | 10.6 |
| 1 Water Truck | 350 | 40 | 8 | 1010.6 | 20.2 |
| Total Restoration | | | | 1538.3 | 30.8 |
| Total Emissions from Subtransmission Line Construction | | | | | 1377.3 |
| Mirage Substation | | | | | |
| Civil | | | | | |
| 1 Driller | Composite | 50 | 8 | 1319.2 | 33.0 |
| 2 Crew Truck | Composite | 80 | 2 | 131.9 | 5.3 |
| 1 14-Ton Crane | Composite | 25 | 4 | 514.8 | 6.4 |
| 1 Dump Truck | Composite | 75 | 6 | 757.9 | 28.4 |
| 1 Tractor | Composite | 75 | 6 | 400.8 | 15.0 |

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|---|-----------|------------------------|-------------------------|-------------------------------|-------------------------------------|
| - 1 5-Ton Truck | Composite | 15 | 4 | 505.3 | 3.8 |
| - 1 Forklift | Composite | 75 | 4 | 217.6 | 8.2 |
| - 1 Ditch Digger | Composite | 55 | 6 | 717.6 | 19.7 |
| - Total Civil | | | | 4565.1 | 119.8 |
| - Electrical | | | | | |
| - 2 Manlift | Composite | 100 | 6 | 416.4 | 20.8 |
| - 1 Pick-Up Truck | Composite | 110 | 2 | 163.2 | 9.0 |
| - 1 14-Ton Crane Truck | Composite | 90 | 6 | 757.9 | 34.1 |
| - 2 Crew Truck | Composite | 110 | 2 | 131.9 | 7.3 |
| - 1 150-Ton Crane | Composite | 60 | 6 | 772.2 | 23.2 |
| - 1 5-Ton Truck | Composite | 50 | 2 | 252.6 | 6.3 |
| - 1 Forklift | Composite | 100 | 6 | 326.4 | 16.3 |
| - 2 Carryall Vehicle | Composite | 110 | 2 | 505.3 | 27.8 |
| - 1 Support Truck | Composite | 25 | 2 | 252.6 | 3.2 |
| - Total Electrical | | | | 3578.6 | 147.9 |
| - Transformer Installation | | | | | |
| - 2 Carryall Vehicle | Composite | 22 | 6 | 1515.8 | 16.7 |
| - 1 Manlift | Composite | 20 | 6 | 208.2 | 2.1 |
| - 1 Forklift | Composite | 22 | 6 | 326.4 | 3.6 |
| - 1 50-Ton Crane | Composite | 15 | 6 | 772.2 | 5.8 |
| - 2 Crew Truck | Composite | 22 | 2 | 131.9 | 1.5 |
| - Total Transformer Installation | | | | 2954.6 | 29.6 |
| - Maintenance | | | | | |
| - 1 Foreman Truck | Composite | 40 | 2 | 66.0 | 1.3 |
| - 1 Manlift | Composite | 40 | 6 | 208.2 | 4.2 |
| - 2 Crew Truck | Composite | 110 | 2 | 131.9 | 7.3 |
| - Total Maintenance | | | | 406.1 | 12.7 |

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|---------------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 110 | 2 | 163.2 | 9.0 |
| Total Test | | | | 163.2 | 9.0 |
| Total Mirage Substation | | | | | 319.04 |
| <u>Concho Substation</u> | | | | | |
| Electrical | | | | | |
| 1 Carryall Vehicle | Composite | 34 | 2 | 252.6 | 4.3 |
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 34 | 2 | 163.2 | 2.8 |
| Total Concho Substation | | | | | 7.07 |
| <u>Indian Wells Substation</u> | | | | | |
| Electrical | | | | | |
| 1 Carryall Vehicle | Composite | 50 | 2 | 252.6 | 6.3 |
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 50 | 2 | 163.2 | 4.1 |
| Total Indian Wells Substation | | | | | 10.4 |
| <u>Santa Rosa Substation</u> | | | | | |
| Electrical | | | | | |
| 1 Carryall Vehicle | Composite | 40 | 2 | 252.6 | 5.1 |

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|------------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 40 | 2 | 163.2 | 3.3 |
| Total Santa Rosa Substation | | | | | 8.3 |
| Devers Substation | | | | | |
| Civil | | | | | |
| 1 Driller | Composite | 2 | 8 | 1319.2 | 1.3 |
| 1 Crew Truck | Composite | 5 | 2 | 66.0 | 0.2 |
| 1 Dump Truck | Composite | 5 | 6 | 757.9 | 1.9 |
| 1 Tractor | Composite | 5 | 6 | 400.8 | 1.0 |
| Total Civil | | | | 2543.9 | 4.4 |
| Electrical | | | | | |
| 1 Manlift | Composite | 45 | 6 | 208.2 | 4.7 |
| 1 Pick-Up Truck | Composite | 60 | 2 | 163.2 | 4.9 |
| 1 Crew Truck | Composite | 60 | 2 | 66.0 | 2.0 |
| 1 150-Ton Crane | Composite | 10 | 6 | 772.2 | 3.9 |
| 1 Forklift | Composite | 40 | 6 | 326.4 | 6.5 |
| 1 Carryall Vehicle | Composite | 60 | 2 | 252.6 | 7.6 |
| Total Electrical | | | | 1788.6 | 29.5 |
| Maintenance | | | | | |
| 1 Foreman Truck | Composite | 5 | 2 | 66.0 | 0.2 |
| 1 Crew Truck | Composite | 10 | 2 | 66.0 | 0.3 |
| Total Maintenance | | | | 131.9 | 0.5 |

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|--------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 20 | 2 | 163.2 | 1.6 |
| Total Test | | | | 163.2 | 1.6 |
| Total Devers Substation | | | | | 36.0 |
| Eisenhower Substation | | | | | |
| Civil | | | | | |
| 1 Driller | Composite | 5 | 8 | 1319.2 | 3.3 |
| 1 Crew Truck | Composite | 15 | 2 | 66.0 | 0.5 |
| 1 Dump Truck | Composite | 15 | 6 | 757.9 | 5.7 |
| 1 Tractor | Composite | 15 | 6 | 400.8 | 3.0 |
| 1 Ditch Digger | Composite | 5 | 6 | 717.6 | 1.8 |
| Total Civil | | | | 3261.5 | 14.3 |
| Electrical | | | | | |
| 1 Manlift | Composite | 35 | 6 | 208.2 | 3.6 |
| 1 Crew Truck | Composite | 45 | 2 | 66.0 | 1.5 |
| 1 150-Ton Crane | Composite | 20 | 6 | 772.2 | 7.7 |
| 1 Forklift | Composite | 45 | 6 | 326.4 | 7.3 |
| 1 Carryall Vehicle | Composite | 45 | 2 | 252.6 | 5.7 |
| Total Electrical | | | | 1625.4 | 25.9 |
| Maintenance | | | | | |
| 1 Foreman Truck | Composite | 5 | 2 | 66.0 | 0.2 |
| 1 Crew Truck | Composite | 10 | 2 | 66.0 | 0.3 |
| Total Maintenance | | | | 131.9 | 0.5 |

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|------------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 45 | 2 | 163.2 | 3.7 |
| Total Test | | | | 163.2 | 3.7 |
| Total Eisenhower Substation | | | | | 44.3 |
| Farrell Substation | | | | | |
| Civil | | | | | |
| 1 Driller | Composite | 10 | 8 | 1319.2 | 6.6 |
| 1 Crew Truck | Composite | 20 | 2 | 66.0 | 0.7 |
| 1 Dump Truck | Composite | 20 | 6 | 757.9 | 7.6 |
| 1 Tractor | Composite | 20 | 6 | 400.8 | 4.0 |
| 1 Ditch Digger | Composite | 10 | 6 | 717.6 | 3.6 |
| Total Civil | | | | 3261.5 | 22.4 |
| Electrical | | | | | |
| 1 Manlift | Composite | 40 | 6 | 208.2 | 4.2 |
| 1 Crew Truck | Composite | 55 | 2 | 66.0 | 1.8 |
| 1 150-Ton Crane | Composite | 25 | 6 | 772.2 | 9.7 |
| 1 Forklift | Composite | 55 | 6 | 326.4 | 9.0 |
| 1 Carryall Vehicle | Composite | 55 | 2 | 252.6 | 6.9 |
| Total Electrical | | | | 1625.4 | 31.6 |
| Maintenance | | | | | |
| 1 Foreman Truck | Composite | 5 | 2 | 66.0 | 0.2 |
| 1 Crew Truck | Composite | 10 | 2 | 66.0 | 0.3 |
| Total Maintenance | | | | 131.9 | 0.5 |

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|------------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 55 | 2 | 163.2 | 4.5 |
| Total Test | | | | 163.2 | 4.5 |
| Total Farrell Substation | | | | | 59.0 |
| <u>Garnet Substation</u> | | | | | |
| Electrical | | | | | |
| 1 Carryall Vehicle | Composite | 16 | 2 | 252.6 | 2.0 |
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 16 | 2 | 163.2 | 1.3 |
| Total Garnet Substation | | | | | 3.3 |
| <u>Thornhill Substation</u> | | | | | |
| Electrical | | | | | |
| 1 Carryall Vehicle | Composite | 40 | 2 | 252.6 | 5.1 |
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 40 | 2 | 163.2 | 3.3 |
| Total Thornhill Substation | | | | | 8.3 |
| <u>Tamarisk Substation</u> | | | | | |
| Civil | | | | | |
| 1 Crew Truck | Composite | 5 | 2 | 66.0 | 0.2 |
| 1 Dump Truck | Composite | 5 | 6 | 757.9 | 1.9 |
| 1 Tractor | Composite | 5 | 6 | 400.8 | 1.0 |
| Total Civil | | | | 1224.7 | 3.1 |

Table F-23. Equipment Exhaust During Subtransmission Line Construction – CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|----------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Electrical | | | | | |
| 1 Manlift | Composite | 5 | 6 | 208.2 | 0.5 |
| 1 Pick-Up Truck | Composite | 40 | 2 | 163.2 | 3.3 |
| 1 Crew Truck | Composite | 40 | 2 | 66.0 | 1.3 |
| 1 150-Ton Crane | Composite | 2 | 6 | 772.2 | 0.8 |
| 1 Forklift | Composite | 5 | 6 | 326.4 | 0.8 |
| 1 Carryall Vehicle | Composite | 40 | 2 | 252.6 | 5.1 |
| Total Electrical | | | | 1788.6 | 11.7 |
| Maintenance | | | | | |
| 1 Foreman Truck | Composite | 1 | 2 | 66.0 | 0.0 |
| 2 Crew Truck | Composite | 2 | 2 | 131.9 | 0.1 |
| Total Maintenance | | | | 197.9 | 0.2 |
| Test | | | | | |
| 1 Pick-Up Truck | Composite | 30 | 2 | 163.2 | 2.4 |
| Total Test | | | | 163.2 | 2.4 |
| Total Tamarisk Substation | | | | | 17.4 |

THIS PAGE IS INTENTIONALLY BLANK

Table F-24. Subtransmission Line Emission Factors

| Off-Road Construction Equipment | Emission Factors | | Notes: |
|--|-------------------------|------------------------|--|
| | HP (hp) | CO2 (lb/hr) | |
| Aerial Lifts | Composite | 34.7000 | Used for manlifts |
| Bore/Drill Rigs | Composite | 164.9000 | Used for drillers and sleeve rigs |
| Cranes | 500 | 180.1000 | Used for all cranes |
| | Composite | 128.7000 | |
| Excavators | Composite | 119.6000 | Used for excavators and ditch diggers |
| Forklifts | 200 | 77.1000 | Used for forklifts |
| | Composite | 54.4000 | |
| Graders | 350 | 229.5000 | Used for graders |
| Off-Highway Trucks | Composite | 260.1000 | Used for all diesel trucks & carryall vehicles |
| Other Material Handling Equipment | Composite | 141.2000 | Used for cable puller & conductor tensioner |
| Other Construction Equipment | Composite | 122.8000 | Used for cable dollies |
| Rubber-Tired Dozers | 350 | 264.9000 | Used for dozers |
| Tractors/Loaders/Backhoes | 350 | 344.9000 | Used for all backhoes & ditch diggers |
| | Composite | 66.8000 | |
| Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html) | | | |
| On-Road Vehicles | | | |
| | HP (hp) | CO2 (lb/hr) | |
| Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour) | Composite | 32.985968 | Used 'passenger vehicle' emfac |
| Pick-Up Trucks (pounds/mile) x 30 miles/hour | Composite | 81.58302 | Used 'delivery trucks' emfac |
| Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour | Composite | 126.3201435 | Used 'heavy-heavy-duty trucks' emfac |
| Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html | | | |

THIS PAGE IS INTENTIONALLY BLANK

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|-----------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Mirage-Santa Rosa | | | | | |
| Cable Construction | | | | | |
| 2 Bucket Truck | Composite | 5 | 8 | 2021.1 | 5.1 |
| 1 Pick-Up | Composite | 5 | 8 | 652.7 | 1.6 |
| 1 2-Axle Trailer | Composite | 5 | 8 | 1129.6 | 2.8 |
| Total Cable Construction | | | | 3803.4 | 9.5 |
| Receive and Loadout | | | | | |
| 1 5-Ton Forklift | Composite | 1 | 8 | 435.2 | 0.2 |
| 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| Total Receive and Loadout | | | | 1087.9 | 0.5 |
| Clean-Up | | | | | |
| 2 Bucket Truck | Composite | 1 | 8 | 2021.1 | 1.0 |
| 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| Total Clean-Up | | | | 2673.8 | 1.3 |
| Total Mirage Santa Rosa | | | | | 11.39 |
| Farrell-Garnet | | | | | |
| Cable Construction | | | | | |
| 2 Bucket Truck | Composite | 18 | 8 | 2021.1 | 18.2 |
| 1 Pick-Up | Composite | 18 | 8 | 652.7 | 5.9 |
| 1 2-Axle Trailer | Composite | 18 | 8 | 1129.6 | 10.2 |
| Total Cable Construction | | | | 3803.4 | 34.2 |
| Receive and Loadout | | | | | |
| 1 5-Ton Forklift | Composite | 1 | 8 | 435.2 | 0.2 |
| 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| Total Receive and Loadout | | | | 1087.9 | 0.5 |
| Clean-Up | | | | | |
| 2 Bucket Truck | Composite | 1 | 8 | 2021.1 | 1.0 |
| 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| Total Clean-Up | | | | 2673.8 | 1.3 |
| Total Farrel Garnet | | | | | 36.11 |
| Devers | | | | | |
| Equipment Installation | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| Total Cable Construction | | | | 1305.3 | 3.9 |
| Circuit Installation | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| Total Circuit Installation | | | | 1305.3 | 3.9 |

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|-----------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Clean-Up | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| Total Clean-Up | | | | 652.7 | 0.3 |
| Total Devers | | | | | 8.16 |
| Mirage | | | | | |
| Equipment Installation | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| Total Cable Construction | | | | 1305.3 | 3.9 |
| Circuit Installation | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| Total Circuit Installation | | | | 1305.3 | 3.9 |
| Clean-Up | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| Total Clean-Up | | | | 652.7 | 0.3 |
| Total Mirage | | | | | 8.16 |
| Tamarisk | | | | | |
| Equipment Installation | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| Total Cable Construction | | | | 1305.3 | 3.9 |
| Circuit Installation | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| Total Circuit Installation | | | | 1305.3 | 3.9 |
| Clean-Up | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| Total Clean-Up | | | | 652.7 | 0.3 |
| Total Tamarisk | | | | | 8.16 |
| Eisenhower | | | | | |
| Equipment Installation | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| Total Cable Construction | | | | 1305.3 | 3.9 |
| Circuit Installation | | | | | |
| 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| Total Circuit Installation | | | | 1305.3 | 3.9 |
| Clean-Up | | | | | |
| 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total Eisenhower | | | | | 8.16 |
| Concho | | | | | |
| - Equipment Installation | | | | | |
| - 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| - Total Cable Construction | | | | 1305.3 | 3.9 |
| - Circuit Installation | | | | | |
| - 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| - Total Circuit Installation | | | | 1305.3 | 3.9 |
| - Clean-Up | | | | | |
| - 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total Concho | | | | | 8.16 |
| Indian Wells | | | | | |
| - Equipment Installation | | | | | |
| - 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| - Total Cable Construction | | | | 1305.3 | 3.9 |
| - Circuit Installation | | | | | |
| - 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| - Total Circuit Installation | | | | 1305.3 | 3.9 |
| - Clean-Up | | | | | |
| - 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total Indian Wells | | | | | 8.16 |
| Santa Rosa | | | | | |
| - Equipment Installation | | | | | |
| - 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| - Total Cable Construction | | | | 1305.3 | 3.9 |
| - Circuit Installation | | | | | |
| - 2 Pick-Up | Composite | 6 | 8 | 1305.3 | 3.9 |
| - Total Circuit Installation | | | | 1305.3 | 3.9 |
| - Clean-Up | | | | | |
| - 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total Santa Rosa | | | | | 8.16 |

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|-------------------------------------|-----------|-----------------|------------------|------------------------|------------------------------|
| Thornhill | | | | | |
| - Equipment Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Cable Construction | | | | 652.7 | 2.0 |
| - | | | | | |
| - Circuit Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Circuit Installation | | | | 652.7 | 2.0 |
| - | | | | | |
| - Clean-Up | | | | | |
| - 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total Thornhill | | | | | 4.24 |
| Garnet | | | | | |
| - Equipment Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Cable Construction | | | | 652.7 | 2.0 |
| - | | | | | |
| - Circuit Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Circuit Installation | | | | 652.7 | 2.0 |
| - | | | | | |
| - Clean-Up | | | | | |
| - 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total Garnet | | | | | 4.24 |
| Farrell | | | | | |
| - Equipment Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Cable Construction | | | | 652.7 | 2.0 |
| - | | | | | |
| - Circuit Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Circuit Installation | | | | 652.7 | 2.0 |
| - | | | | | |
| - Clean-Up | | | | | |
| - 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total Farrell | | | | | 4.24 |

Table F-25. Equipment Exhaust During Telecommunication Construction - CO2 Exhaust Emissions

| Construction | HP | Duration (days) | Usage (hour/day) | CO2 Emissions (lb/day) | CO2 Emissions (tons/project) |
|--|-----------|-----------------|------------------|------------------------|------------------------------|
| EDOM Hill | | | | | |
| - Equipment Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Cable Construction | | | | 652.7 | 2.0 |
| - Circuit Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Circuit Installation | | | | 652.7 | 2.0 |
| - Clean-Up | | | | | |
| - 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total EDOM Hills | | | | | 4.24 |
| Palm Springs | | | | | |
| - Equipment Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Cable Construction | | | | 652.7 | 2.0 |
| - Circuit Installation | | | | | |
| - 1 Pick-Up | Composite | 6 | 8 | 652.7 | 2.0 |
| - Total Circuit Installation | | | | 652.7 | 2.0 |
| - Clean-Up | | | | | |
| - 1 Pick-Up | Composite | 1 | 8 | 652.7 | 0.3 |
| - Total Clean-Up | | | | 652.7 | 0.3 |
| - Total Palm Springs | | | | | 4.24 |
| TOTAL EMISSIONS DURING CONSTRUCTION | | | | | 125.8 |

THIS PAGE IS INTENTIONALLY BLANK

Table F-26. Telecommunication Equipment Emission Factors

| <u>Off-Road Construction Equipment</u> | Emission Factors | | Notes: |
|--|------------------|----------------|--|
| | HP (hp) | CO2 (lb/hr) | |
| Forklifts | Composite | 54.4000 | Used for forklifts |
| Off-Highway Trucks | Composite | 260.1000 | Used for all diesel trucks & carryall vehicles |
| Other Material Handling Equipment | Composite | 141.2000 | Used for cable puller & conductor tensioner |
| Source: SCAQMD Air Quality Handbook, Off-Road Emissions Sources - (http://www.aqmd.gov/ceqa/handbook/offroad/offroad.html) | | | |
| <u>On-Road Vehicles</u> | | | |
| | HP (hp) | CO2 (lb/hr) | |
| Crew & Foreman Trucks (Suburbans) (pounds/mile x 30 miles/hour) | Composite | 32.985968 | Used 'passenger vehicle' emfac |
| Pickup Trucks (pounds/mile) x 30 miles/hour | Composite | 81.58302 | Used 'delivery trucks' emfac |
| Heavy Duty Trucks and Truck-Mounted Equipment (pounds/mile) x 30 miles/hour | Composite | 126.3201435 | Used 'heavy-heavy-duty trucks' emfac |
| Source: SCAQMD Air Quality Handbook, Emfac2007 (Ver2.3) Emission Factors (On-Road), Scenario Year 2008 - http://www.aqmd.gov/ceqa/handbook/onroad/onroad.html | | | |

THIS PAGE IS INTENTIONALLY BLANK

Notes

Devers-Mirage 115 kV Construction

AQ Calculations by: Eric Rivero-Montes
 Last Calculation Date: 11/20/2007
 Project Description: As provided in PEA
 Equipment List: As provided in PEA
 Provided by:
 Date Provided:

Schedule
 Provided by:
 Date Provided

| Construction Element | Number of Personnel | Number of Days | Start Date | Finish Date | Equipment Requirements | | HP | Hrs/Day | Notes |
|----------------------|---------------------|----------------|------------|-------------|------------------------|---------------------------|-----|---------|----------------|
| | | | | | Number | Description | | | |
| Roads | 3 | 10 | | | 2 | Crew Truck (gasoline) | 200 | 2 | ALW assumed HP |
| | | 10 | | | 2 | Light Truck | 180 | 2 | ALW assumed HP |
| | | 10 | | | 1 | Crawler D6 | 250 | 10 | ALW assumed HP |
| | | 10 | | | 1 | Crawler D8 | 250 | 10 | ALW assumed HP |
| | | 10 | | | 1 | Motor Grader | 250 | 5 | ALW assumed HP |
| | | 10 | | | 1 | Water Truck | 250 | 2 | ALW assumed HP |
| Subtransmission Line | 30 | 171 | | | 2 | Crew Truck (gasoline) | 200 | 10 | ALW assumed HP |
| | | 107 | | | 2 | Line Truck | 250 | 10 | ALW assumed HP |
| | | 107 | | | 2 | Light Truck | 180 | 10 | ALW assumed HP |
| | | 171 | | | 2 | Bucket Truck | 250 | 10 | ALW assumed HP |
| | | 107 | | | 2 | Truck-Mounted Crane | 250 | 10 | ALW assumed HP |
| | | 24 | | | 1 | Conductor-Pulling Machine | 300 | 10 | ALW assumed HP |
| | | 24 | | | 1 | Tensioner (gasoline) | 300 | 10 | ALW assumed HP |

| Construction Element | Number of Personnel | Number of Days | Start Date | Finish Date | Equipment Requirements | HP | Hrs/Day | Notes |
|------------------------|---------------------|----------------|------------|-------------|-------------------------|-----|---------|------------------------------|
| | | 14 | | | 1 30-Ton Crane | 250 | 10 | ALW assumed HP |
| | | 171 | | | 2 Backhoe | 250 | 10 | ALW assumed HP |
| | | 24 | | | 1 Drilling Rig | 500 | 10 | ALW assumed HP |
| | | 107 | | | 1 Water Truck | 250 | 10 | ALW assumed HP |
| | | 3 | | | 1 Concrete Truck | 500 | 10 | ALW assumed truck needed |
| | | 0 | | | 0 Flat-Bed Pole Truck | 500 | 10 | ALW assumed truck needed |
| Staging areas | | 0 | | | 0 Crane (diesel) | 250 | 10 | ALW assumed equipment needed |
| Staging areas | | 0 | | | 0 980 Loader (diesel) | 250 | 10 | ALW assumed equipment needed |
| Staging areas | | 0 | | | 0 Forklift (diesel) | 250 | 10 | ALW assumed equipment needed |
| Telecommunications | | | | | | | | |
| Equipment Construction | 2 | 13 | | | 2 Van (gasoline) | 200 | 7 | ALW assumed HP |
| Overhead Construction | 4 | 50 | | | 1 Bucket Truck | 250 | 8 | ALW assumed HP |
| | | 50 | | | 1 Reel Truck | 250 | 8 | ALW assumed HP |
| Underground Conduit | 3 | 5 | | | 1 Flat-Bed Truck | 250 | 1 | ALW assumed HP |
| | | 5 | | | 1 Backhoe | 250 | 8 | ALW assumed HP |
| | | 5 | | | 1 Stake-Bed Truck | 250 | 2 | ALW assumed HP |
| | | 5 | | | 1 Crew Truck (gasoline) | 200 | 2 | ALW assumed HP |
| | 4 | 2 | | | 1 Bucket Truck | 250 | 2 | ALW assumed HP |
| | | 2 | | | 1 Reel Truck | 250 | 2 | ALW assumed HP |