

Table 3-5. Right-of-Way Miles and Construction Methods - San Luis Obispo to Bakersfield

Route Segment	Right-of-Way Miles				Construction Methods			
	Local Roads	State Highways	Railroad	Utility/Pipeline	Plow or Trench	Existing Pipeline or Duct	Bore	Bridge Attach
Granada	0.25				✓			
South Higuera	1.50					✓		
South Street	0.75					✓	✓	
Broad Street	0.25					✓		
Chorro Street	0.75					✓	✓	
Mill Street	0.50					✓		
Johnson Street	0.12					✓	✓	
Monterey Street	0.75					✓		
Miossi Street	0.50					✓	✓	
Pacific Bell right-of-way (generally follows U.S. Highway 101)				5.10	✓	✓		
UPRR to Atascadero			5.10		✓			
Atascadero to Shandon Pump Station				20.75		✓		
Shandon to Middle Station				37.00		✓		
Middle Station to Wasco Road				34.00		✓		
Wasco Road to Morris Road				5.00		✓		
Morris Road	1.00				✓			
Bellevue (Stockdale) to UPRR	7.00				✓			
UPRR to Bakersfield			20.20		✓			
Open space	0.30				✓		✓	
20 th Street	0.30				✓			
Total	13.97		25.3	101.85				
			GRAND TOTAL	141.12				