

Table 3-7. Right-of-Way Miles and Construction Methods - Riverside to California/Arizona Border

Route Segment	Right-of-Way Miles				Construction Methods			
	Local Roads	State Highways	Railroad	Utility/Pipeline	Plow or Trench	Existing Pipeline or Duct	Bore	Bridge Attach
Orange Street	2.75				✓		✓	
Center Street	0.40				✓		✓	
West La Cadena Drive	0.45				✓		✓	
South La Cadena Drive	1.80				✓		✓	
Kinder-Morgan Pipeline				189.80		✓		
UPRR right-of-way			0.75		✓			
Colorado River bank			0.10				✓	
Total	5.40		0.85	189.80				
			<b>GRAND TOTAL</b>	<b>196.05</b>				