

Table 3-8. Right-of-Way Miles and Construction Methods - Los Angeles to Riverside

Route Segment	Right-of-Way Miles				Construction Methods			
	Local Roads	State Highways	Railroad	Utility/ Pipeline	Plow or Trench	Existing Pipeline or Duct	Bore	Bridge Attach
South Grand Avenue	0.15				✓	✓	✓	
7 th Street	2.00				✓	✓	✓	✓
UPRR from Downtown			6.75		✓		✓	✓
Mission Road	2.30				✓		✓	✓
UPRR			44.70		✓		✓	✓
Cedar Avenue	0.35				✓		✓	
Slover Avenue	1.75				✓		✓	
Kinder-Morgan Pipeline				3.10		✓		
South La Cadena Drive	1.80				✓		✓	
West La Cadena Drive	0.45				✓		✓	
Center Street	0.40				✓		✓	
Orange Street	2.75				✓		✓	
Total	11.95		51.45	3.10				
			GRAND TOTAL	66.50				