

Table 3-9. Right-of-Way Miles and Construction Methods - Los Angeles to Anaheim

Route Segment	Right-of-Way Miles				Construction Methods			
	Local Roads	State Highways	Railroad	Utility/Pipeline	Plow or Trench	Existing Pipeline or Duct	Bore	Bridge Attach
South Grand Avenue	0.15				✓	✓	✓	
7 th Street	2.00				✓	✓	✓	✓
UPRR to Branchline Split			6.55		✓		✓	✓
Branchline Split to Gilbert Street			14.55		✓		✓	✓
Gilbert Street	0.20				✓	✓	✓	
La Palma Street	0.15				✓	✓	✓	
Total	2.50		21.10					
			GRAND TOTAL	23.6				