

**Table DR 15: Preliminary Spans Requiring Marking**

<b>From Structure</b>	<b>To Structure</b>	<b>Cable</b>	<b>Highest Clearance (ft)</b>	<b>Height of Catenary Above Ground Level (AGL)</b>
<b>Segment A</b>				
P3	P4	OPGW	293.17	293.17
P6	P7	OPGW	251.79	251.79
P8	P9	OPGW	272.63	272.63
P13	P14	OPGW	238.85	238.85
P14	P15	OPGW	198.84	198.84
P23	P24	OPGW	249.42	249.42
P25	P26	OPGW	157.38	157.38
P38	P39	OPGW	212.99	212.99
<b>Segment C</b>				
E7	E8	OPGW	228.11	228.11
<b>Segment D</b>				
E23	E24	OPGW	285.37	285.37
E22	E23	OPGW	270.31	270.31
P45	E14	OPGW	174.16	174.16