



CPUC Meeting Materials

MAOP Validation Methodology

FEBRUARY 18, 2011

- Pressure Test Records Criteria
 - Verifiable, Traceable and Complete
- MAOP Validation Methodology



Pressure Test Records Criteria

Verifiable, Traceable and Complete

VERIFIABLE	TRACEABLE	COMPLETE
INITIAL PASS		
<p><u>Criteria:</u></p> <ul style="list-style-type: none"> ▪ Pressure test record (e.g. STPR¹, chart) exists ▪ Record has been collected and available for review 	<p><u>Criteria:</u></p> <ul style="list-style-type: none"> ▪ Total pipeline footage that is pressure tested per the pressure test records correlates with information contained on the Job Estimate Face Sheet 	<p><u>Criteria:</u></p> <ul style="list-style-type: none"> ▪ Pressure test record contains the following 4 elements required by current regulations (CFR Title 49, Part 192.517²): <ul style="list-style-type: none"> - Name of Operator - Test Pressure - Test Duration - Test Medium
ADDITIONAL ANALYSIS REQUIRED		
(One or more of the above criteria has not been met)		
<p><u>Criteria:</u></p> <ul style="list-style-type: none"> ▪ Other data sources need to be researched (e.g. test logs, As Builts, etc.) 	<p><u>Criteria:</u></p> <ul style="list-style-type: none"> ▪ Other data sources need to be researched (e.g. As Builts, Bill of Materials, etc.) 	<p><u>Criteria:</u></p> <ul style="list-style-type: none"> ▪ Other data sources need to be researched to identify 4 key elements above

¹Strength Test Pressure Report. Please refer to the Appendix for an example report.

²CFR Title 49, Part 192 includes 3 additional elements including pressure chart, elevation and leak and failure survey. These elements are being documented when available as part of the Data Validation Project.



1. MAOP Validation of the Job

- Establishes MAOP of the pipe segment


2. MAOP Validation of the HCA Pipeline System

- Establishes MAOP of the pipeline system based on the lowest MAOP of the HCA pipe segment or component



MAOP Validation Methodology

1. MAOP Validation of Job





MAOP Validation Methodology

2. MAOP Validation of HCA Pipeline System

Establish
MAOP of
the Job
(prior step)

Develop
comprehensive
Pipeline Features
List (PFL)

Follow 1998 PHMSA
guideline,
Determination of
MAOP in Natural Gas
Pipelines

Determine valid
MAOP of HCA
pipeline system

**Components include
(but not limited to):**

- Pipe
- Valves
- Fittings
- Overpressure Protection Devices
- *Other*

PHMSA References

- Based on requirements as outlined in CFR Title 49, Part 192

PHMSA Guideline

- Determine the appropriate pressure limit for each pipeline component
- Lowest value of the component establishes the MAOP of the pipeline system

Appendix

STPR EXAMPLE

MAOP VALIDATION METHODOLOGY DETAILS

Criteria for Complete

- Four key elements:
 1. Operator name
 2. Test pressure
 3. Test medium
 4. Test duration

- Additional information (captured if available):
 - Elevation variation
 - Pressure charts
 - Leaks and failures

PG AND E
GAS OPERATIONS
STRENGTH TEST PRESSURE REPORT
(FOR PIPE FACILITIES OPERATING OVER 100 PSIG)

USE IN ACCORDANCE WITH
GAS STD. A-54 AND G.O. 110
SHEET 1 OF 1

2-401 REV. 1-73

PART I - DESIGN DATA - (TO BE PREPARED BY PROJECT ENGINEER OR GAS SYSTEM DESIGN DEPT.)

DIST. MAIN OR LINE NO. NAPA VALLEY FEEDER	DIVISION NORTH DAY	DISTRICT VAL-NAPA "I,"	W.G. OR G.M. NO. GM 180428	DATE APPROVED 4-10-73
DESCRIPTION OF JOB - INCLUDE REFERENCE DRAWING NUMBERS Reinforce Napa Valley distribution feeder main				
LOCATION CLASSIFICATION (PRESENT MAP OF LINE (PSIG)) I and III	DESIGN FACTOR .5	DESIGN PRESSURE - THIS SECTION 450	DESIGN PRESSURE - PLANNED FUTURE MAP 675	PLANNED FUTURE MAP 675
SPECIAL PROTECTION REQUIRED WHERE COVER OVER PIPE IS LESS THAN SPECIFIED IN PAR. 15.3.37 - G.O. 118 - SEE PAR. 15.1.10 GIVE W.P. & REF. DWG. NO. FOR EACH LOCATION				
STATIC HEAD DUE TO ELEVATION DIFFERENCE (WHERE APPLICABLE)	MAX. ELEVATION MIN. ELEVATION DIFF. N/A	FT. FT. FT.	STATIC HEAD CALCULATION FOR WATER OTHER	8.33 X DIFF. N/A PSIG
PIPE SIZE O.D. 10.750	W.T. 0.188	PIPE SPECIFICATION API 5LX GR. X-42	VERIFIED IN FIELD YES	AT DESIGN PRESS. 45.0
				AT 90% TEST PRESS. 90
				AT 100% TEST PRESS. 100
				PRESS. TO BE TESTED 1323
				FOOTAGE TO BE TESTED 870
				VERIFIED IN FIELD 765
MINIMUM PRESSURE FOR TEST 1323 PSIG	TEST FLUID TO BE USED WATER	MINIMUM TEST DURATION UNDER PRESSURE (HOURS) 8	APPROVED BY: R. L. Hayes DATE: 6-19-73	
MAXIMUM PERMISSIBLE TEST PRESSURE 1469 PSIG	FOR INFORMATION OR CHANGED CALL Ext. 7381			

PART II - TEST DATA - (TO BE PREPARED BY PERSON SUPERVISING TEST AT TIME OF TEST)

TIME AND DATE REACHED TEST PRESSURE 6-28-73	ELEVATION AT TEST POINT NA	INDICATED TEST PRESSURE 1390 PSIG
TIME AND DATE TEST ENDED 6-29-73	MAX. ELEVATION IN TEST SECTION NA	MINIMUM TEST PRESSURE 1323 PSIG
ACTUAL DURATION OF TEST 9 Hours 45 Min.	MIN. ELEVATION IN TEST SECTION NA	MAXIMUM TEST PRESSURE 1469 PSIG

TEST FLUID USED: O-2000 PSI
MARK, RANGE & SERIAL NO. OF RECORDING GAUGE: Bristol's 6701466
DATE LAST CALIBRATION: 6-10-73
MARK, RANGE & SERIAL NO. OF DEAD WEIGHT TESTER: _____
DATE LAST CALIBRATION: _____

TEST SUPERVISED BY: L. Sanchietti
APPROVED BY: Mr. H. Thompson

SCHEMATIC SKETCH SHOW LOCATION OF FACILITY TESTED, MIN & MAX ELEVATION IN FEET, MILE POINTS OR ENGINEERING STATIONS AND INCORPORATED AREAS. USE SPACE BELOW. SHOW REFERENCE DRAWING NUMBERS.
USE BACK OR AN ADDITIONAL SHEET IF NECESSARY (SHOW REFERENCE NUMBERS ON FACE OF ALL DRAWINGS AND ATTACHMENTS)

Job Number GM 180428
SEE ATTACHED SHEET FOR DRAWING.

DISTRIBUTION

DIST. GAS SUPT. JOB FILE _____

DIV. GAS SUPT. _____

GC GAS DESIGN JOB# _____

GAS SYSTEM DESIGN (S) _____

PLANT ACCTG. DEPT. _____

FORWARD COPY OF JOB# _____

PIPELINE HISTORY FILE _____

RECORD FAILURES UNDER _____

RECORD GAS SYSTEM DESIGN _____



Job Estimate Face Sheet Example

Criteria for Complete

- Face sheet includes footage
- Used to correlate with footage on STPR's

REV. 9-69
 PACIFIC GAS AND ELECTRIC COMPANY
 ESTIMATE FOR AUTHORIZATION
 RC#04-445

DATE OF ESTIMATE May 5, 1972
 DEPARTMENT Gas DISTRICT Vjo.-Napa "L" DIVISION North Bay OFFICE 04
 NAMES OF APPLICANTS: Pacific Gas & Electric Company ESTIMATE NO. Q-40306
 LOCATION Oakville to South of Rutherford, Napa Rural COUNTY Napa
 JOB TITLE Reinforce Napa Valley Distribution Fender Main.
 REASON FOR PROPOSED WORK AND DESCRIPTION (HEREIN):
 In order to supply firm gas demands to North Napa Valley, (Calistoga, St. Helena, Sanitarium & Angwin), it is proposed to install 8350' of 10" HP gas main from south of Oakville to South of Rutherford along hwy. #29.
 This reinforcement is recommended by Gas System Planning and is another portion of a master plan to maintain 150 PSI level to the Northern Napa Valley Area.
 This extension will assure adequacy of supply into 1974.
 CP Area NC-TP

RECOMMENDATION & RULE NO.
 Company Expense

ESTIMATE OF DIRECT COSTS (FOR ADDED ESTIMATES GIVE SUMMARY HERE - DETAIL EXTRA SHEETS)
 SPLIT AMOUNT (WHEN REQ.)

ACCOUNT NO.	ITEM NO.	LOCATION AND/OR ITEM NO.	ESTIMATE OF DIRECT COSTS	SPLIT AMOUNT (WHEN REQ.)	AMOUNT (DOLLARS ONLY)			TOTAL
					FROM UNIT COST OR OTHER	LARGE MATERIAL	OTHER	
122h		1000	Install 8350'- 10" HP Gas Main		65628	32888	59040	157556
122h		2000	Install 35'-6" HP Gas Main		400	75		475
122h		3000	Install 6" Valve in P&G		400	1500		1900

PLANT TO BE REMOVED OR ABANDONED (GIVE JOB NO., PREVIOUS JOB NO. AND PERIOD OF INSTALLATION AS APPROPRIATE)
 TOTAL DIRECT COST (EXCL. MGMT. & OPER.) 164,211
 INDIRECT COSTS (EXCL. MGMT. & OPER.) 32,675
 SUB-TOTAL 196,886
 GEN. OVERHEADS (EXCL. MGMT. & OPER.) 17,508
 MAINTENANCE & OPER. 214,466
 AMOUNT AUTHORIZED 214,466
 NET AMOUNT 214,466

CHECK LIST	REQ'D.	SEC'D.	CHECK LIST	REQ'D.	SEC'D.	PROGRESS REPORT CODES (ACT'S. ONLY)	APPROVED	GENERAL OFFICE
J.P.G.T. INTENTION			RIGHT OF WAY			1222		
J.P./J.T. APPL. NO.			OVER 20% YIELD	Yes				
TREE TRIMMING			STRENGTH TEST	Yes				
CITY OR CO. PERMIT			PAYMENT - 30 FT.	25000				
HIWAY PERMIT		X	MACHINE TRENCH - FT.	99%				
R.R. X-RAY PERMIT			MAX DATE	105%				
OTHER PERMITS			COST REPORT REQUIRED	Yes	NO X			

APPROVED: R.H. JONES
 APPROVED: J.G. FOSTER
 AUTHORIZED: J.G. FOSTER
 SUPERVISOR: J.G. FOSTER
 GENERAL OFFICE: J.G. FOSTER

Appendix


STPR EXAMPLE

MAOP VALIDATION METHODOLOGY DETAILS



MAOP Validation Methodology Details

MAOP Validation of Job





Sufficient Pressure

$$[\text{MAOP to be established}] * [\text{Pressure Test Class Factor}] \leq [\text{Minimum Test Pressure}]$$

Critical Inputs*
MAOP to be established
Class location
Minimum Test Pressure
Installation date

Class location	Pressure Test Class Factors		
	Installed before Nov. 12, 1970	Installed after Nov. 11, 1970	Converted under §192.14
1	1.1	1.1	1.25
2	1.25	1.25	1.25
3	1.4	1.5	1.5
4	1.4	1.5	1.5

* Note: See Appendix for sources

Code References: Operations (DOT § 192 Subpart L), MAOP (DOT § 192.619), Pressure Test (DOT § 192.619 paragraph [a,2,ii])



Sufficient Duration

Test Date:	Prior to July 1, 1961	Between July 1, 1961 and Prior to March 12, 1971	March 12, 1971 and Beyond
Minimum Duration:	No minimum threshold required	1 hour	1 hour if %SMYS < 30% and P > 100 psig - OR - 8 hours if %SMYS ≥ 30%

Critical Inputs*	
Test Date	
Test Duration	
%SMYS	

Where $\%SMYS = P / [(2 St / D) * E]$, and:

P = MAOP to be established

S = Yield strength in pounds per square inch

t = Nominal wall thickness of the pipe in inches

D = Nominal outside diameter of the pipe in inches

E = Longitudinal joint factor

* Note: See Appendix for sources

Code References: DOT § 192 Subpart J, DOT § 192.505, DOT § 192.507, DOT § 192.105



Operating Within Current Class Location

$$[\text{MAOP to be established}] * [\text{Pressure Test Class Factor}] \leq [\text{Minimum Test Pressure}]$$

Critical Inputs*
MAOP to be established
Class location
Minimum Test Pressure
Installation date

Class location	Pressure Test Class Factors		
	Installed before Nov. 12, 1970	Installed after Nov. 11, 1970	Converted under §192.14
1	1.1	1.1	1.25
2	1.25	1.25	1.25
3	1.4	1.5	1.5
4	1.4	1.5	1.5

* Note: See Appendix for sources
 Code References: Operations (DOT § 192 Subpart L), MAOP (DOT § 192.619), Pressure Test (DOT § 192.619 paragraph [a,2,ii])



$$\%SMYS = [\text{MOP from PG\&E Engineering Drawing*}] / [(2 St / D) * E]$$

MAOP OF NUMBERED TRANSMISSION LINES



* Source: PG&E Engineering Drawing DWG 086868 Rev 20