

From: Dowdell, Jennifer
Sent: 10/24/2011 12:07:25 PM
To: 'jmh@cpuc.ca.gov' (jmh@cpuc.ca.gov); 'mlc@cpuc.ca.gov' (mlc@cpuc.ca.gov);
'sks@cpuc.ca.gov' (sks@cpuc.ca.gov)
Cc: Doll, Laura (/O=PG&E/OU=CORPORATE/CN=RECIPIENTS/CN=LRDD);
Horner, Trina (/O=PG&E/OU=CORPORATE/CN=RECIPIENTS/CN=TNHC);
Ramaiya, Shilpa R (/o=PG&E/ou=Corporate/cn=Recipients/cn=SRRd)
Bcc:
Subject:

Michelle, Julie, and Sunil,

I know you've seen the pressure test failure report that was submitted to the CPUC this morning on L300B in a rural area.

Shilpa is following up. Not sure if you have all info below yet.

Hope this helps

Jennifer

Basic info on failed line is as follows:

- 34 inch line
- DSAW
- 757 MAOP
- Class 1
- Failed at 998 psig, or 131.8% of MAOP or 94.9% SMYS

Additional Background:

Line 300B failed a pressure test this morning. The location of the failure was in an agricultural field near Rosedale. It appears that the pipe failed along a longitudinal seam during the ramp portion of the test. A team is en route to further evaluate the failure.