

Pipeline Specifications for Line 300B at Colorado River

Location Description

Redacted

Redacted

The ownership and maintenance of the pipeline is shared between PG&E Co. and El Paso Natural Co. and is split mid-span at the center of the river.

Redacted

Background

The below presented attachments are in conflict regarding the specifications for the 34" Pipe as specified on suspension bridge crossing the Colorado River at Topock, specifically Line 1113, also known as Line 300B. A concern regarding the yield strength of the pipeline has come in question. A letter dated from March 4th, 1966 to the El Paso Gas Company indicates the specified Minimum Yield Strength on the 34" X ½" WT pipeline as 46,000 psi (X-46). This documentation was the only documentation found in the Job File indicating a Minimum Yield Strength of 46,000.

Not to be used

JEV To JEV

1113

PACIFIC GAS AND ELECTRIC COMPANY

PG&E +

Redacted

Redacted
MANAGER

PIPE LINE OPERATIONS DEPARTMENT

March 4, 1966

Mr. Carlton C. Holman, Chief Engineer
El Paso Natural Gas Company
El Paso, Texas 79999

R
e
d
a
c
t
e
d

Dear Mr. Holman:

The information tabulated below is being sent to you in response to your request to Mr. Redacted for data on the Colorado River pipeline crossings.

	Crossing Installed on	
	Old Highway Bridge	New Suspension
Outside Diameter & Wall Thickness	30" x 3/8"	34" x 1/2"
Specified Minimum Yield Strength	52,000 psi	46,000 psi
Manufacturer	Consolidated Western Steel Corporation	
Plant Site	Maywood & So. S.F.	Maywood
Ladle Analysis - Carbon	0.30% max.	0.30% max.
Manganese	1.25% max.	1.25% max.
Phosphorus	0.045% max.	0.045% max.
Sulfur	0.05% max.	0.05% max.
Transverse Ultimate Strength	72,000 pai	65,000 psi
Factory Test Pressure	1,170 psi	1,215 psi

Very truly yours,

Redacted

The following attachment from October 11th, 1974 indicates a Minimum Yield Strength on the pipeline of "X-52" (34" O.D. , .500"wt X52 grade pipe) which differs from the above memo.

EL PASO NATURAL GAS COMPANY

Memorandum

File (022)
rom: J. W. Rowland

Date: October 11, 1974
Place: Engineering Department
Codes & Standards Division

Subject: MAOP of 34" San Juan Crossover "C" Line (1113)
VA-15 Through Colorado River Crossing

This review is for the purpose of evaluating the present maximum allowable operating pressure of 660 psig on the subject line segment.

An area extending from the Colorado River eastward to E.S. 902 + 50 presently has a population density level equal to a Class 2 Location. The class location limit had previously been at E.S. 886 + 29.5 during the period near 1967. The segment was constructed in 1955 of 34" O.D., .406" w.t., X52 and 34" O.D., .500" w.t., X52 grade pipe. The limiting pressure of the pipe in the Class 2 Location is 745 psig. In the present system configuration, the operation of Line 1113 must be in concert with Line 1104. Thus, the lower limiting design pressure of the 30" O.D., .324 w.t., X52 grade pipe found in the Class 2 Location on Line 1104 dictates that 674 psig is the minimum design pressure for operation of the unisolated Line 1113.

The line segment from approximately E.S. 917 + 22 eastward to Valve 16, E.S. 855 + 75, was hydrostatically tested in February, 1957 to a minimum pressure of 1020 psig for an unknown period. The line was subsequently gas tested from Valve 15 on Line 1104 to a valve near the P.G.&E. compressor station. The test was to a minimum pressure of 880 psig for a period of 24 hours in March, 1957.

The operating pressure of the segment has been controlled at Valve 15 since a date prior to 1965. The exact date could not be determined. Mr. Redacted of Systems Dispatching indicated in a conversation that he felt the operating pressure of the segment during the period July 1, 1965 to July 1, 1970 was substantially higher than 660 psig on numerous occasions. No records could be found in the Home Office Dispatching Center, the Topock Dispatching Office, nor the Measurement Department that could substantiate this.

In view of the information gathered, the segment maximum allowable operating pressure is correctly established at 660 psig in compliance with Department of Transportation standards.

Jim Rowland
J. W. Rowland

JWR:cvg
" " Defahl

Research

The original intent of the project was to install 34" API 5LX X-52 piping as date by the memo from July 1, 1955 as seen below. The original installation was completed in 1957 under GM 134616.

R
a
c
t
e
d

02-0224

134616
C2

PACIFIC GAS AND ELECTRIC COMPANY

COPY

GAS OPERATIONS

Tentative Order for 34" O.D. Steel Pipe
to Increase Main 300 Capacity to 750 M²/Day

July 1, 1955

MR. Redacted;

We have had a number of discussions with the Consolidated Western Steel Division, U. S. Steel Corporation, concerning the delivery of 34" O.D. steel pipe required by the P. G. & E. Company in 1956, if the Company is to be in a position to accept minimum gas purchase obligations from the El Paso Natural Gas Company by November, 1956.

Consolidated has supplied us with preliminary estimates concerning costs, specifications and rolling schedules, together with their recommendation that a tentative order be placed for our requirements, as early as possible, if they will be expected to protect a mill rolling schedule as early as May, 1956. We are told that recent large orders have been booked for the El Paso Co., the Pacific Northwest Co. and others which is effectively filling up their 1956 rolling schedules.

In view of Consolidated's concern, we recommend that consideration be given their request and that a tentative order for 34" pipe be placed, conditional upon receipt by the P. G. & E. Co. of the necessary California Public Utility and Federal Power Commission approvals for the project and further subject to cancellation or adjustment by P. G. & E. Co. within an agreed upon time prior to actual mill rolling.

We are listing below our current minimum 34" O. D. pipe requirements. Delivery should start in June, 1956:

34" O. D. Steel Pipe to API 5LX - x 52 Specifications


Wall thickness Section	11/32"		13/32"		7/16"		Total	
	Miles	Tons	Miles	Tons	Miles	Tons	Miles	Tons
1 - Colorado River	-	-	-	-	0.44	182	0.44	182
2 - Topock-Hinkley	-	-	20.8	8,005	-	-	20.8	8,005
3 - Kettleman-Milpitas	26.7	8,711	25.5	9,811	11.8	4,885	64.0	23,410
Totals	26.7	8,711	46.3	17,819	12.24	5,067	85.25	31,597

P. E. BECKMAN

RDS:rr
cc:NRS
AJS

R
e
d
a
c
t
e
d

The specifications found on the As-Built Drawing 383779 indicate a 34" pipeline with a ½" W.T. was used on the span which connected on the bridge ends at the spring anchors. No indication of the Minimum Yield Strength was found on the drawings available..



From the job file there were various wall thicknesses of the 34" ordered all being grade X-52 piping. The maximum wall thickness was ½" or 0.500" WT. Likely, using the best engineering practices, the 0.500" WT piping would be used for the bridge span, in agreement with the above drawing.

Supporting Documentation for X-52 piping

Supporting documentation for 34" X .500" wall X-52 can also be found in the job file for GM 134616. All the available "Receiving Records" from PG&E and "Invoices" from Redacted indicate shipments of "34" O.D. X 0.500" Wall Grade X-52" Pipe. Shipments of 34" pipe not the 0.500" Wall had also indicated a Grade of X-52 for the piping. (Multiple ship documents exist, one example shown)

Redacted

8221 5123
7211590

NO ORDER NO.: TRMC #L-11500
PRICE DATE: SEPT. 21, 1956
ORDER NO.: 6158

SOLD TO: PACIFIC GAS & ELECTRIC CO.
245 MARKET STREET
SAN FRANCISCO 6, CALIFORNIA

SHIP TO: SAME
DESTINATION: DECATO, CALIFORNIA
DATE SHIPPED: SEPT. 13, 15, 16 & 17, 1956
SHIPPER VIA: UNION PACIFIC & D&RGW
CAR NUMBERS: SEE BELOW

SHIPPER FROM: PIPE MILL, UTAH
F.O.B.: PIPE MILL, UTAH
PREPAID OR COLLECT: COLLECT
TERMS: 30-2-10 SEMI-MONTHLY
8% INTEREST CHARGED ON OVERDUE ACCOUNTS

QUANTITY	DESCRIPTION	WEIGHT	PRICE	UNIT	AMOUNT
BILLING #2 - PARTIAL					
16,797.89 FT.	30" GRADE X-52 LINE PIPE	1,036,373#	\$1,542.15	CFT.	\$89,971.34
16,797.89 FT.	34" O.D. X .344" WALL, PLAIN END BEVELED 30" GRADE X-52 LINE PIPE	2,064,175#	1,102.23	CFT.	185,151.38
					\$275,122.72
					\$ 8,253.68
					\$283,376.40
					566753
					27770887

MANIFESTS #L-3309 TO #L-3316 INCLUSIVE AND #L-3319 TO 3339, INCLUSIVE.

IF APPLICABLE, COUNTY SALES AND/OR USE TAX WILL BE BILLED AT A LATER DATE.

maop05427340.tif

F.O.B. POINT OF ORIGIN
ALL PRICES SUBJECT TO CHANGE WITHOUT NOTICE.
CLAIMS FOR DEDUCTIONS MUST BE MADE WITHIN FIVE DAYS AFTER RECEIPT OF GOODS.

61-9025 REV. 3-53

PARTIAL RECEIVING RECORD

PACIFIC GAS AND ELECTRIC COMPANY

ORDER NUMBER 7-B-11590 DATE September 20, 1956

REQ'D FOR GM-134616 (2) REQUISITION NUMBER CAR NUMBER Below
(STOCK, RESALE, G. M., ETC.)

REC'D FROM Redacted CARRIER'S BILL NO. SPRR-see below AMT. \$ 7,219.17
(SHIPPER'S NAME)

REC'D BY R. E. Leurey CHECKED BY A. E. Leifried PREPAID COLLECT X
(WRITE NAME IN FULL)

PURCHASE SHEET NO.	ORDER ITEM NO.	QUANTITY	DESCRIPTION	MATERIAL NUMBER
LIST ALL ARTICLES IN DETAIL INCLUDING CASES AND WEIGHT				
1	1	3,967.26	1/2" Ft. Pipe, 3/4" OD, expanded line wald, Grade X-52 .500" wall	
			Bare	
			S. P. R. R. F/B # 5267 - \$ 2,375.32	Car # Loaded UP-59145 3113 UP-59102 2117
			5268 5.05	UP-56808 UP-51149 UP-51685
			5269 2,411.33	UP-59142 3117 UP-59041 3173
			5270 2,422.42	UP-59057 3177 UP-59005 3177
			5271 5.05	UP-51155 UP-51670 UP-51543
			\$7,219.17	

Additional Support

During the production period in 1956 inspections were made at the production facility at Redacted in Utah as shown in this weekly inspection report below. During this time, inspections were also made of the piping and steel including offsite inspection by Redacted. These samples indicate steel was made at the facility with a Yield Point in excess 52,000 psi. Although this does not prove the piping was X-52, it would indicate the facility had produced steel at this time which have met the requirements of X-52.

PACIFIC GAS AND ELECTRIC COMPANY
 DEPARTMENT OF ENGINEERING
 BUREAU OF TESTS AND INSPECTION

ORDER OR SPEC. No. 7 R 11590
 G. M. No. 134616
 SERIAL REPORT NO. 5

FILE NO. _____

WEEKLY INSPECTION REPORT

WEEK ENDING 10-13-56

MATERIAL INSPECTED: 34" O.D. STEEL PIPE
 FOR SHIPMENT TO: Desoto, California
 INSPECTED AT: Redacted - Provo, Utah

DATE OF _____ USE REQUIRED _____ SHIPMENT PROMISED _____ PRESENT _____ EST. TRANSIT TIME _____
 PREVIOUS _____

TESTS AND INSPECTIONS

34" O.D. x 7/16" wall x 40' sections - completed 10-8-56
 34" O.D. x 13/32" wall x 40' sections.

13/32" wall pipe in 40' sections started through the mill October 8 and expected to complete approximately October 23. P.G. & E inspection offered approximately 410 pipe per 24 hour day of which there is a rejection of about 10% for further repair, making an acceptance of approx. 350 pipe for the three shifts. Rejection is for plate slivers, gouges, scabs, pits, refacing, lamination and longitudinal weld repairs. Physical and chemical tests satisfactory.

Production: 34" O.D. x 7/16" wall.

Shipped	40' Sections	80' Sections	Footage
	19	821	64,757.34
		Total	736.43
			65,494.27

Completes 7/16" wall.

Shipped	PROGRESS OF WORK	80' sections	Footage
		259	20,512.30

Round seam production is approximately 120 round seams for 3 - 8 hour shifts 13/32" wall pipe.

X RAYS AS OF October 10, 1956

Wall	Total R.S. X rayed.	N. S. Cut	Accepted R.S.		Total X rays	
			R.S. X rays OK	X rays repaired		
1/2"	6	0	6	45	3	48
11/32"	135	15	120	906	54	560 completed
7/16"	73	7	66	492	36	328 completed

SHIPMENTS

ENGINEERING - WD-2 FEB RDS
 OPER. & MAINT.
 CONSTRUCTION - AJS JAL RDT
 PURCH. & STORES - FEB
 DIVISION

INSPECTOR A V TATE

W. N. LINDBLAD, CHIEF

Test Number	85	86	87	88	
Description or Mark	Welding Test				
HEAT NUMBER	#3	#4	#7	#10	Welding
TENSILE TEST—					
Nominal Dimensions					Welding
Actual Dimensions	3/16 x .77	3/16 x .76	3/16 x .91	3/16 x .77	
Actual Area—Sq. in.273	.266	.267	.266	
Yield Point—Lbs.	20310	21530	21810	21100	
Maximum Load—Lbs.	29790	27830	28810	28210	
Yield Point—Lbs. per sq. in.	57450	56070	51420	57120	
Tensile Strength—Lbs. per sq. in.	77260	76230	77710	77270	
Elongation in inches					
Elongation, per cent					
Reduction of area, per cent					
Fracture	Silly	Silly	Silly	Silly	
BENDING TEST					
Result of Test	Broke Outside of Weld.				

Telephone Olympic 3-7611

Re
da
cte
d

Sampled by our Inspector Job Public Works Vendor

Submitted by Vendor Report To: _____

Yes No: Machine Charge Address: _____

Yes No: Chemical Analysis Charge To: Invoice 11533-517

Meets Requirements of P. O. No. _____ Copies of Report _____

Fails

Date Received 7/26/56 Date Tested 9/26/56 Tested By R. G. Cox

FORM 503

Additional Memos

Further documentation can be found supporting the use of X-52 with a Yield Strength of 52,000 psi. The search yielded an additional memo from PG&E to El Paso Natural Gas Company. On January 10th 1964, the El Paso Natural Gas Company requested information from PG&E concerning specifications regarding the pipe crossings at this location. The second item in question of this correspondence refers to GM 134616 used for the suspension bridge in question. In the response dated January 15th 1964, PG&E indicate the pipelines in question have a Minimum Yield Strength of 52,000 psi. This documentation from 1964 is not only closer to the completion date of the project, but it also predates the memo with the lowered minimum yield strength.

1113

January 10, 1964

Mr. [Redacted]
Pacific Gas and Electric Company
[Redacted]

Re: Minimum Yield of Colorado River
Pipeline Crossings

Dear Mr. [Redacted]

Would you please furnish us with the minimum yield of pipe on the [Redacted]
[Redacted], California. Listed below is the
information that we already have pertaining to this pipe:

- 30" O. D., .375"w. t. - your invoice No. 85747 of September
26, 1950
- 34" O. D., .500"w. t. - your invoice No. GM 134616 of April
19, 1960

This information will be very much appreciated.

Very truly yours,

EL PASO NATURAL GAS COMPANY

Clinton McClure
Senior Engineer - Southern Division

CMc. f
cc: [Redacted]

PACIFIC GAS AND ELECTRIC COMPANY

Redacted

1113

STATER 1-1-211

In reply please refer to

January 15, 1964

Mr. Clinton McClure
Senior Engineer - Southern Division
El Paso Natural Gas Company
P. O. Box 1492
El Paso, Texas

Dear Mr. McClure:

In answer to your letter of January 10, 1964, the 30" and 34" pipe to which you refer has a minimum yield strength of 52,000 psi.

If we can be of further assistance to you, please do not hesitate to call on us.

Very truly yours,

Redacted

RDS:ha

Conclusion

Likely the memo dated March 4th 1966 indicating the piping crossing the Colorado River is in error as there is no technical supporting documentation. All the documentation and correspondence reviewed in the Job file indicate that the piping used on [Redacted] ing the Colorado River for line 300B is 34" X 0.500" WT X-52, with the exception of this memo. The memos pre-dating and memos post-dating this memo define this piping to be X-52. All the found technical drawings, invoices, receiving records, and inspections provide further evidence to the installation of X-52 piping on the [Redacted]