A planner's view of the role of demand response in meeting resource adequacy requirements

Demand Response Workshop German Consulate Sponsored Workshop October 15, 2013

Redacted

PG&E

Manager, Renewable Integration Pacific Gas and Electric Company

Q1: What are Resource Adequacy (RA) requirements?

A:

- Load Serving Entities' requirement to procure qualifying capacity to ensure the system operates reliably
- RA requirements are changing and will continue to change over time with the needs of the system
- The RA requirements will include a flexible capacity requirement starting in 2015

Q2: Should all demand response (DR) programs be modified to provide flexible capacity?

A: No, at least for now. See p. 4 for explanation

RA requirements change with the needs of the system

Today's RA requirements

- Procure qualifying capacity = 115% to 117% of forecasted 1-in-2 peak
- Today's RA requirements can be satisfied with non-flexible capacity

Starting in 2015,

A small amount of flexible capacity required (See Appendix)

– Flexible requirement =

Largest three-hour contiguous ramp in the month

+ The larger of the Most Severe Single Contingency, or 3.5% of the month's expected peak load

+ ε: Error term to account for uncertainties (set to zero)

More changes in RA requirements are likely in the future


- Initial flexible requirement may not be enough
- Downward flexibility requirements
- Other

For now, DR's best role is to reduce the residual peak, or for emergencies

Why?

- Summer will continue to be where capacity is needed most
- Reducing the peak, also reduces the ramp
- Initial 2015-2017 flexible capacity requirements are small (<20% of summer peak)
- Existing resources can satisfy 2015-2017 flexibility requirements
- More information is needed about additional flexibility requirements to re-design programs for flexibility services
 - How much more, what type of flexible capacity?
 - What are the operating attributes of the additional flexibility requirements?
 - How fast will the flexibility requirements change?


4



* **Source**: CAISO's, Flexible Resource Adequacy Criteria and Must-Offer Obligation, Third Revised Straw Proposal, Figure 2, October 3, 2013.

5

 New RA requirements for flexible capacity are being added to meet the system's higher ramping



Does this graph look like a duck?