



Overall Visual Change: high. Replacing existing single-circuit 220-kV lattice steel towers (LSTs) and architectural (Dreyfus) structures with double-circuit 500-kV LSTs and tubular steel poles (TSPs) would create high visual contrast, high dominance, and high view/skyline blockage/impairment. The overall visual change would be high; and combined with moderate-to-high overall visual sensitivity of the visual setting and viewing characteristics, visual impacts would be **Adverse and Potentially Significant**, as indicated in Table 2-2.

Adverse Visual Impacts. In the vicinity of KOP-South-18, implementation of the Project would result in adverse and potentially significant visual impacts V-1, V-3, and V-5, as detailed in Table 6-1.

Mitigation Measures. Implementation of Mitigation Measures (MMs) would reduce these visual impacts somewhat, but because of the height of the new structures, visual impacts of the Project would be adverse and significant (**Class I**). MMs would include: V-1 – Clean up staging areas, storage areas, marshalling yards, access and spur roads, and structure locations on a regular periodic basis; V-2a – Use tubular steel poles instead of lattice steel towers in designated areas (same as APM AES-2 - TSPs Near Existing Residential Development); V-2b – Treat surfaces with appropriate colors, textures, and finishes; V-4b – Slope-round and re-contour in areas as prescribed; and V-4d – Dispose of excavated materials as prescribed.

Figure A-53b
Visual Simulation
for KOP- South-18
Chipola Court, Chino
(Alternative 2, Segment 8)

Source: SCE, 2007.