



Overall Visual Change: high. Routes B and D have structures in the same location on this skyline ridge, but in a different location than Routes A and C. With high visual contrast, high dominance, and high skyline blockage/impairment, the overall visual change would be high; and combined with high overall visual sensitivity of the visual setting and viewing characteristics, visual impacts would be **Adverse and Significant**, as indicated in Table 2-2.

Adverse Visual Impacts. In the vicinity of KOP-South-21, implementation of Alternative 4 would result in adverse and significant visual impacts V-1, V-3, and V-5, as detailed in Table 6-1.

Mitigation Measures. Implementation of Mitigation Measures (MMs) would reduce these visual impacts somewhat, but because of the height of the new structures, visual impacts of the Project would remain adverse and significant (**Class I**). MMs would include: V-1 – Clean up staging areas, storage areas, marshalling yards, access and spur roads, and structure locations on a regular periodic basis; V-2a – Use tubular steel poles instead of lattice steel towers in designated areas; V-2b – Treat surfaces with appropriate colors, textures, and finishes; V-3a – Match spans of existing transmission structures; V-4b – Slope-round and re-contour in areas as prescribed; and V-4d – Dispose of excavated materials as prescribed.

Figure A-57c (Revised)
Visual Simulation
for KOP- South-21
Carbon Canyon Road
(Highway 142), Orange County.
(Alternative 4, Routes B & D,
Segment 8A)

Source: Lee Anderson and 3DScape, 2008.