



**Overall Visual Change:** high. With high visual contrast, high dominance, and high skyline blockage/impairment, the overall visual change would be high; and combined with high overall visual sensitivity of the visual setting and viewing characteristics, visual impacts would be **Adverse and Significant**, as indicated in Table 2-2.

**Adverse Visual Impacts.** In the vicinity of KOP-South-22, implementation of Alternative 4 would result in adverse and significant visual impacts V-1, V-3, and V-5, as detailed in Table 6-1.

**Mitigation Measures.** Implementation of Mitigation Measures (MMs) would reduce these visual impacts somewhat, but because of the height of the new structures, visual impacts of the Project would remain adverse and significant (**Class I**). MMs would include: V-1 – Clean up staging areas, storage areas, marshalling yards, access and spur roads, and structure locations on a regular periodic basis; V-2a – Use tubular steel poles instead of lattice steel towers in designated areas; V-2b – Treat surfaces with appropriate colors, textures, and finishes; V-3a – Match spans of existing transmission structures; V-4b – Slope-round and re-contour in areas as prescribed; and V-4d – Dispose of excavated materials as prescribed.

**Figure A-58e (Revised)**  
**Visual Simulation**  
**for KOP-South-22**  
**Vellano Planned Development,**  
**Chino Hills (Alternative 4,**  
**Route D, Segment 8A)**

*Source: Lee Anderson and 3DScape, 2008.*