

Frank Gaines
Project Manager
City of San Diego
225 Broadway Suite 1100
San Diego, CA 92101

Keith Kranda
Manager of Maintenance of Way
NCTD
810 Mission Avenue
Oceanside, CA 92054

John Shurson
Assistant Director Public Projects
BNSF Railway
740 East Carnegie Dr.
San Bernardino CA 92408

John Eschenbach
Senior Project Manager
Amtrak Engineering
603-C Garrison Street
Oceanside, CA 92054

Wayne Terry
Vice President of Operations
MTS
1255 Imperial Avenue, Suite 1000
San Diego, CA 92101

PUBLIC UTILITIES COMMISSION

515 L Street, Suite 1119
Sacramento, CA 95814



March 29, 2010

File Number: G.10-01-010
City of San Diego, County of San Diego

Frank Gaines
Project Manager
City of San Diego
225 Broadway Suite 1100
San Diego, CA 92101

Re: General Order 88-B Request for Authority to Modify the Ketner Boulevard and G Street Highway-Rail Crossing, CPUC Crossing No. 002-267.80 in the City of San Diego, San Diego County.

Dear Mr. Gaines:

This refers to your letter, dated January 8, 2010, requesting authorization, pursuant to Commission General Order (GO) 88-B, to modify the existing at-grade crossing of Ketner Boulevard and G Street in the City of San Diego, San Diego County. The crossing is identified by CPUC Crossing Number 002-267.80. The initial GO 88-B requests submitted on behalf of the City did not clearly describe all the proposed modifications at the crossings. On February 4, 2010, a revised set of GO 88-B requests were submitted that included additional detail of the proposed alterations and revised engineering plans.

This crossing is over one mainline BNSF Railway (BNSF) track, and two San Diego Metropolitan Transit Systems (MTS) tracks. In addition to BNSF and MTS trains, the North County Transit District (NCTD) and the National Passenger Railroad Corporation (Amtrak) operate passenger trains over this line. The proposed improvements are part of the downtown San Diego Quiet Zone (Q.0612001).

The City proposes the following alterations:

- Install a 130 foot raised median and a 110 foot raised median on Ketner Boulevard, north and south of the tracks respectively.
- Install four foot aluminum fencing on the raised medians on Ketner Boulevard.
- Curb realignment on G Street and crosswalk reconfiguration.
- Closure of the west sidewalk on Ketner Boulevard.
- Install four foot high aluminum fencing along the sidewalks to channelize pedestrians to crosswalks.
- Conversion of G Street to one way eastbound traffic.
- Modification of the existing northbound and southbound pre-signals on Ketner Boulevard.
- Install a Commission Standard 8 (flashing light signal assembly) warning device between the NCTD and MTS tracks.

- Install Commission Standard 8 warning devices on the sidewalk at the northwest, northeast, southwest, and southeast quadrants of the crossing.
- Remove the existing Commission Standard 9A (Commission Standard 9 with additional flashing light signals over the roadway on a cantilevered arm) warning device at the northeast quadrant of the crossing.
- Install Americans with Disabilities Act (ADA) compliant detectable warning tactile strips on all sidewalk approaches.
- Install MUTCD compliant signage including W10-9 “NO TRAIN HORN” signs.
- Application of MUTCD compliant pavement markings.

The Commission’s Rail Crossings Engineering Section (RCES) investigated the request filed by the City, and finds it adequately addresses compliance and safety. As the City, NCTD, MTS, BNSF, and Amtrak are all in agreement as to the design and apportionments of the cost under the provisions of GO 88-B, the improvements as described in your request dated February 4, 2010 and summarized above are authorized.

Temporary traffic controls shall be provided in compliance with Section 8A.05, Temporary Traffic Control Zones, of the California Manual on Uniform Traffic Control Devices (CA MUTCD), published by the California Department of Transportation.

All parties shall comply with all applicable rules, including Commission General Orders and the CA MUTCD.

This project is categorically exempt from the requirements of the California Environment Quality Act of 1970, as amended. [California Pubic Resources Code 21084].

This authorization shall expire if the above conditions are not complied with or if the work is not completed within two years of the date of this letter. Upon written request to this office, the time to complete the project may be extended. Any written request for a time extension must include concurrence letters by involved parties in support of the time extension. If an extension is requested, RCES may reevaluate the crossing prior to granting an extension.

Within 30 days after completion of this project, BNSF shall notify RCES that the authorized work is completed, by submitting a completed Commission Standard Form G titled *Report of Changes at Highway Grade Crossings and Separations*. Form G requirements and forms can be obtained at the CPUC web site Form G page at <http://www.cpuc.ca.gov/formg>. This report may be submitted electronically to rces@cpuc.ca.gov as outlined on the web page.

If you have any questions, please contact Laurence Michael at (213) 576-7076 or ldi@cpuc.ca.gov.

Sincerely,

Frank Gaines
G. 10-01-010
March 29, 2010
Page 3 of 3

A handwritten signature in black ink that reads "Daren Gilbert". The signature is written in a cursive style with a large, stylized "D" and "G".

Daren Gilbert, Supervisor
Rail Crossings Engineering Section
Consumer Protection and Safety Division

C: John Shurson, BNSF
Wayne Terry, MTS

Keith Kranda, NCTD
John Eschenbach, Amtrak