

Frank Gaines  
Project Manager  
City of San Diego  
225 Broadway Suite 1100  
San Diego, CA 92101

Keith Kranda  
Manager of Maintenance of Way  
NCTD  
810 Mission Avenue  
Oceanside, CA 92054

John Shurson  
Assistant Director Public Projects  
BNSF Railway  
740 East Carnegie Dr.  
San Bernardino CA 92408

John Eschenbach  
Senior Project Manager  
Amtrak Engineering  
603-C Garrison Street  
Oceanside, CA 92054

Wayne Terry  
Vice President of Operations  
MTS  
1255 Imperial Avenue, Suite 1000  
San Diego, CA 92101

## PUBLIC UTILITIES COMMISSION

515 L Street, Suite 1119  
Sacramento, CA 95814



March 29, 2010

File Number: G.10-01-012  
City of San Diego, County of San Diego

Frank Gaines  
Project Manager  
City of San Diego  
225 Broadway Suite 1100  
San Diego, CA 92101

Re: **General Order 88-B Request for Authority to Modify the Front Street Highway-Rail Crossing, CPUC Crossing No. 002-268.20 in the City of San Diego, San Diego County.**

Dear Mr. Gaines:

This refers to your letter, dated January 8, 2010, requesting authorization, pursuant to Commission General Order (GO) 88-B, to modify the existing at-grade crossing of Front Street in the City of San Diego, San Diego County. The crossing is identified by CPUC Crossing Number 002-268.20. The initial GO 88-B requests submitted on behalf of the City did not clearly describe all the proposed modifications at the crossings. On February 4, 2010, a revised set of GO 88-B requests were submitted that included additional detail of the proposed alterations and revised engineering plans.

This crossing is over one mainline BNSF Railway (BNSF) track, and two San Diego Metropolitan Transit Systems (MTS) tracks. In addition to BNSF and MTS trains, the North County Transit District (NCTD) and the National Passenger Railroad Corporation (Amtrak) operate passenger trains over this line. The proposed improvements are part of the downtown San Diego Quiet Zone (Q.0612001).

The City proposes the following alterations:

- Install a westbound pre-signal on Front Street with in-pavement detection loops in the track area as part of the vehicle presence detection system.
- Install two Commission Standard 8 (flashing light signal assembly) warning devices at the pedestrian path that runs adjacent to the tracks.
- Install Commission Standard 8 warning devices at the northwest and southwest quadrants of the crossing.
- Install pedestrian barriers at the existing pedestrian path to prevent pedestrians from cutting across Front Street to get to the other side of the path.
- Install Americans with Disabilities Act (ADA) compliant detectable warning tactile strips on all sidewalk approaches.
- Install MUTCD compliant signage including W10-9 "NO TRAIN HORN" signs.
- Application of MUTCD compliant pavement markings

The Commission's Rail Crossings Engineering Section (RCES) investigated the request filed by the City, and finds it adequately addresses compliance and safety. As the City, NCTD, MTS, BNSF, and Amtrak are all in agreement as to the design and apportionments of the cost under the provisions of GO 88-B, the improvements as described in your request dated February 4, 2010 and summarized above are authorized.

Temporary traffic controls shall be provided in compliance with Section 8A.05, Temporary Traffic Control Zones, of the California Manual on Uniform Traffic Control Devices (CA MUTCD), published by the California Department of Transportation. All parties shall comply with all applicable rules, including Commission General Orders and the CA MUTCD.

This project is categorically exempt from the requirements of the California Environment Quality Act of 1970, as amended. [California Public Resources Code 21084].

This authorization shall expire if the above conditions are not complied with or if the work is not completed within two years of the date of this letter. Upon written request to this office, the time to complete the project may be extended. Any written request for a time extension must include concurrence letters by involved parties in support of the time extension. If an extension is requested, RCES may reevaluate the crossing prior to granting an extension.

Within 30 days after completion of this project, BNSF shall notify RCES that the authorized work is completed, by submitting a completed Commission Standard Form G titled *Report of Changes at Highway Grade Crossings and Separations*. Form G requirements and forms can be obtained at the CPUC web site Form G page at <http://www.cpuc.ca.gov/formg>. This report may be submitted electronically to [rces@cpuc.ca.gov](mailto:rces@cpuc.ca.gov) as outlined on the web page.

If you have any questions, please contact Laurence Michael at (213) 576-7076 or [ldi@cpuc.ca.gov](mailto:ldi@cpuc.ca.gov).

Sincerely,



Daren Gilbert, Supervisor  
Rail Crossings Engineering Section  
Consumer Protection and Safety Division

C: John Shurson, BNSF  
Wayne Terry, MTS

Keith Kranda, NCTD  
John Eschenbach, Amtrak