

C.H. Harvey  
Deputy CEO  
Peninsula Corridor Joint Powers Board  
1250 San Carlos Ave  
P.O. Box 3006  
San Carlos, CA 94070-1306

James Smith  
Union Pacific  
9451 Atkinson St  
Roseville, CA 95747

Jack Witthaus  
Transportation and Traffic Manager  
City of Sunnyvale  
456 W. Olive Ave  
Sunnyvale, CA 94086

## PUBLIC UTILITIES COMMISSION

180 Promenade Circle, Suite 115  
SACRAMENTO, CA 95834-2939



July 8, 2010

File Number: G.10-07-002

C.H. Harvey, Deputy CEO  
Peninsula Corridor Joint Powers Board  
1250 San Carlos Ave  
San Carlos, CA 94070-1306

**Re: GO 88-B Request for Authority to Alter the Sunnyvale Avenue Highway-Rail Crossing, CPUC Crossing No. 105E-38.90, DOT No. 755042X in the City of Sunnyvale, Santa Clara County.**

Dear Mr. Harvey:

This refers to your letter dated June 28, 2010 and received by us on July 6, 2010 requesting authorization pursuant to Commission General Order (GO) 88-B to alter an at-grade highway-rail crossing of the Peninsula Corridor Joint Powers Board (JPB) track in the City of Sunnyvale (City), Santa Clara County. The crossing is identified as the Sunnyvale Avenue Highway-Rail Crossing, CPUC Crossing No. 105E-38.90, DOT No. 755042X.

The Sunnyvale Avenue crossing is currently a three track crossing on the Caltrain mainline, and is equipped with two Commission Standard 9 warning devices (flashing light signal assemblies with automatic gates). The JPB operates 90 passenger trains per day over this crossing and Union Pacific Railroad (UPRR) operates approximately four freight trains per day over this crossing.

Modification of this crossing is part of a county wide project in which the JPB is proposing systematic improvements to eight of the grade crossings along the corridor in Santa Clara County to improve safety. The JPB states in its GO 88-B request letter that "The crossing modifications proposed in this request will enhance pedestrian and motorist safety at this crossing. Additional signal installations will provide greater warning of train movements to motorists and pedestrians."

The proposed alterations as indicated in the request letter and/or shown in the attachments shall consist of:

- Replacement of the Commission Standard 9 in the northwest quadrant with a Commission Standard 9-A (Commission Standard 9 with additional flashing light signals over the roadway on a cantilevered arm).
- Installation of a nine foot wide raised concrete median on the south approach.
- Installation of a median mounted Commission Standard 8 (flashing light signal assembly) with an additional pair of flashing light signals pointed at the driveway in the southeast quadrant on the south approach median.
- Installation of a painted median on the north approach.

- Installation of a new signal box in the northwest quadrant.
- Installation of two Commission Standard 9 pedestrian gate warning devices, one each in the northeast and southwest quadrants
- Installation of two pedestrian gate arms on separate masts in the northwest and southeast quadrants (no bells or flashers).
- Installation of emergency exit swing gates; one in each quadrant.
- Installation of ADA compliant detectable warning tactile strips just prior to the pedestrian gate arms in each quadrant, along the full width of the walkway.
- Installation of guardrails in all quadrants to channelize pedestrians to the pedestrian gates and prevent pedestrians from easily circumventing the gates.
- Installation of additional concrete panels to widen the crossing surface and accommodate the pedestrian pathways over the crossing.
- Installation of new asphaltic concrete (AC) ramps around the crossing surface to provide a proper transition for pedestrians from the sidewalks to the crossing surface.
- Installation of continuous fencing in the northeast quadrant tying to the guardrail and extending 50 feet east to channelize pedestrians to the safe and lawful crossing.
- Installation of continuous fencing in the southeast quadrant tying to the guardrail and to the existing wall to channelize pedestrians to the safe and lawful crossing.
- Installation of continuous fencing in the southwest quadrant tying to the guardrail and to the existing signal box to channelize pedestrians to the safe and lawful crossing.
- Reconstruction of the sidewalks in all quadrants.
- Replacement of the existing text R3-1 Active “No Right Turn” signs with a new R3-1 Active “No Right Turn” signs.
- Installation of pavement markings to delineate the pedestrian and vehicle travel ways through the crossing.
- Installation of lane guidance striping from the left turn lanes on westbound Hendy Avenue to southbound Sunnyvale Avenue to direct vehicles to the appropriate lanes.
- Painting the curbs red for 50 feet in the southeast and southwest quadrants to restrict parking near the crossing.
- Installation of passive signage and pavement markings associated with railroad crossings as indicated in Chapter 8 of the California Manual on Uniform Traffic Control Devices (CA MUTCD).
- Replacing all incandescent light units with new LED units on existing Commission standard 9 warning device in southeast quadrant.
- Relocating existing “No Trespassing/Suicide Prevention” signs on both sides of the crossing to improve visibility.

Staff has investigated the JPB’s request, and finds it adequately addresses compliance and safety. As the JPB and City are in agreement as to the design and apportionments of the cost under the provisions of GO 88-B, you may proceed with the improvements as described in your request letter and attachments and summarized above.

Temporary traffic controls shall be provided in compliance with Section 8A.05, Temporary Traffic Control Zones, of the CA MUTCD, published by Caltrans.

All parties shall comply with all applicable rules, including Commission General Orders and CA MUTCD.

This project is categorically exempt from the requirements of the California Environment Quality Act of 1970, as amended [California Pubic Resources Code 21084].

This authorization shall expire if the above conditions are not complied with or if the work is not completed within two years of the date of this letter. Upon written request to this office, the time to complete the project may be extended. Any written request for a time extension must include concurrence letters by involved parties in support of the time extension. If an extension is requested, the Commission's Rail Crossings Engineering Section (RCES) may reevaluate the crossing prior to granting an extension.

Within 30 days after completion of this project, the JPB shall notify RCES that the authorized work is completed, by submitting a completed Commission Standard Form G titled *Report of Changes at Highway Grade Crossings and Separations*. Form G requirements and forms can be obtained at the CPUC web site Form G page at <http://www.cpuc.ca.gov/formg>. This report may be submitted electronically to [rces@cpuc.ca.gov](mailto:rces@cpuc.ca.gov) as outlined on the web page.

If you have any questions, please contact Felix Ko at (415) 703-3722 or [fko@cpuc.ca.gov](mailto:fko@cpuc.ca.gov).

Sincerely,



Daren Gilbert, Supervisor  
Rail Crossings Engineering Section  
Consumer Protection and Safety Division

C: Jack Witthaus, Transportation and Traffic Manager  
City of Sunnyvale  
456 W. Olive Ave  
Sunnyvale, CA 94086

Benjamin H. Scharf  
Senior Assistant Counsel  
Santa Clara VTA  
3331 North First Street  
San Jose, CA 95134-1906

James Smith, Manager Industry & Public Projects  
Union Pacific  
9451 Atkinson St  
Roseville, CA 95747